

PLANNING COMMISSION CONDITIONS OF APPROVAL

144 LAS ONDAS
COASTAL DEVELOPMENT PERMIT
NOVEMBER 17, 2005

- A. **Recorded Agreement.** Prior to the issuance of any Public Works permit or building permit for the project on the Real Property, the following conditions shall be imposed on the use, possession and enjoyment of the Real Property and shall be recorded by the Owner in a written instrument, which shall be reviewed as to form and content by the City Attorney, Community Development Director and/or Public Works Director:
1. **Uninterrupted Water Flow.** The Owner shall provide for the uninterrupted flow of water through the Real Property including, but not limited to, swales, natural water courses, conduits and any access road, as appropriate. The Owner is responsible for the adequacy of any drainage facilities and for the continued maintenance thereof in a manner that will preclude any hazard to life, health or damage to the Real Property or any adjoining property.
 2. **Allowed Development.** The development of the Real Property approved by the Planning Commission on November 17, 2005 is limited to one residential unit of no more than 2,755 square feet of interior floor area including the garage and the improvements shown on the Site Plan signed by the chairman of the Planning Commission on said date and on file at the City of Santa Barbara.
 3. **Storm Water Pollution Control Systems Maintenance.** The Owner(s) shall maintain drainage system, storm drain water interceptor and other storm water pollution control devices in accordance with the Operations and Maintenance Procedure Plan approved by the City Engineer.
 4. **Drainage System Maintenance.** The Owner(s) shall maintain the on-site drainage system, storm drain water interceptor and other on-site storm water pollution control devices in accordance with the Operations and Maintenance Procedure Plan approved by the City Engineer.
- B. **Design Review.** The following is subject to the review and approval of the Architectural Board of Review (ABR):
1. **Lighting.** Exterior lighting, where provided, shall be consistent with the City's Lighting Ordinance. No floodlights shall be allowed. Lighting shall be directed toward the ground.
 2. **Trash Enclosure Provision.** A trash enclosure with an area for recycling containers shall be provided on the Real Property and screened from view from surrounding properties and the street.
 3. **Neighborhood Compatibility.** Minimize the plate heights and simplify the roof forms.
- C. **Public Works Submittal Prior to Building Permit Issuance.** The Owner shall submit the following or evidence of completion of the following to the Public Works Department prior to the issuance of a Building Permit for the project:
1. **Water Rights Assignment.** The Owner shall execute an Agreement Assigning Water Extraction Rights. Said assignment and any related agreements are subject to the review

EXHIBIT A

and approval of the City Attorney. Said agreement shall be recorded in the Office of the County Recorder.

2. **Public Street Improvement Plans.** The Owner shall submit building plans for construction of improvements along the subject property road frontage on Las Ondas. As determined by the Public Works Department, the improvements shall include new, and/or remove and replace to City standards: cracked and/or uplifted sidewalk, driveway apron modified to meet Title 24 requirements, drainage system including two 4 inch curb drain outlets and on-site silt detention prior to discharge to public right of way, drought-tolerant parkway landscaping, new street trees as approved by the City Arborist and provide adequate positive drainage from site. The building plans shall be prepared by a registered civil engineer or licensed architect and reviewed by the City Engineer.
 3. **Storm Water Pollution Control Systems Maintenance.** The Owner(s) shall submit a Storm Water Operations and Maintenance Procedure Plan for approval by the City Engineer.
 4. **Storm Water Quality.** New residential development projects, shall address water quality through the use of best management practices (BMPs) as determined by the City. Projects shall seek to reduce post-development runoff volumes from pre-development volumes through such measures as infiltration, evapo-transpiration, and storage/reuse.
 5. **Construction Best Management Practices.** Construction Best Management Practices Required. Construction activities shall address water quality through the use of best management practices (BMP's) as approved by the City Building Official.
- D. **Building Permit Plan Requirements.** The following requirements shall be incorporated into the construction plans submitted to the Building & Safety Division with applications for building permits. All of these construction requirements shall be carried out in the field and completed prior to the issuance of a Certificate of Occupancy:
1. **Unanticipated Archaeological Resources Contractor Notification.** Prior to the start of any vegetation or paving removal, demolition, trenching or grading, contractors and construction personnel shall be alerted to the possibility of uncovering unanticipated subsurface archaeological features or artifacts associated with past human occupation of the parcel. If such archaeological resources are encountered or suspected, work shall be halted immediately, the City Environmental Analyst shall be notified and an archaeologist from the most current City Qualified Archaeologists List shall be retained by the applicant. The latter shall be employed to assess the nature, extent and significance of any discoveries and to develop appropriate management recommendations for archaeological resource treatment, which may include, but are not limited to, redirection of grading and/or excavation activities, consultation and/or monitoring with a Barbareño Chumash representative from the most current City qualified Barbareño Chumash Site Monitors List, etc.

If the discovery consists of possible human remains, the Santa Barbara County Coroner shall be contacted immediately. If the Coroner determines that the remains are Native American, the Coroner shall contact the California Native American Heritage

Commission. A Barbareño Chumash representative from the most current City Qualified Barbareño Chumash Site Monitors List shall be retained to monitor all further subsurface disturbance in the area of the find. Work in the area may only proceed after the Environmental Analyst grants authorization.

If the discovery consists of possible prehistoric or Native American artifacts or materials, a Barbareño Chumash representative from the most current City Qualified Barbareño Chumash Site Monitors List shall be retained to monitor all further subsurface disturbance in the area of the find. Work in the area may only proceed after the Environmental Analyst grants authorization.

2. **Demolition/Construction Materials Recycling.** Recycling and/or reuse of demolition/construction materials shall be carried out and containers shall be provided on site for that purpose in order to minimize construction-generated waste conveyed to the landfill.
3. **Construction-Related Truck Trips.** Construction-related truck trips shall not be scheduled during peak hours (7:00 a.m. to 9:00 a.m. and 4:00 p.m. to 6:00 p.m.) to help reduce truck traffic on adjacent streets and roadways.
4. **Haul Routes.** The haul route(s) for all construction-related trucks, three tons or more, entering or exiting the site, shall be approved by the Transportation Operations Manager.
5. **Construction Hours.** Construction (including preparation for construction work) is prohibited before 8:00 a.m. and after 5:00 p.m., Monday through Friday, and all day on Saturdays, Sundays and holidays observed by the City of Santa Barbara as shown below:

New Year's Day	January 1 st *
Martin Luther King's Birthday	3 rd Monday in January
Presidents' Day	3 rd Monday in February
Memorial Day	Last Monday in May
Independence Day	July 4 th *
Labor Day	1 st Monday in September
Thanksgiving Day	4 th Thursday in November
Following Thanksgiving Day	Friday following Thanksgiving Day
Christmas Day	December 25 th *

*When a holiday falls on a Saturday or Sunday, the preceding Friday or following Monday, respectively, shall be observed as a legal holiday.

6. **Construction Parking/Storage.** Construction parking and storage shall be provided as follows:
 - a. During construction, free parking spaces for construction workers shall be provided on-site or off-site in a location subject to the approval of the Streets, Parking, and Transportation Operations Manager.

- b. On-site or off-site storage shall be provided for construction materials and equipment. Any off-site storage location for equipment or materials shall be approved by the Community Development Director.
 - c. Storage of construction materials within the public right-of-way is prohibited without an encroachment permit issued by the City.
7. **Water Sprinkling During Grading.** During site grading and transportation of fill materials, regular water sprinkling shall occur using reclaimed water whenever the Public Works Director determines that it is reasonably available. During clearing, grading, earth moving or excavation, sufficient quantities of water, through use of either water trucks or sprinkler systems, shall be applied to prevent dust from leaving the site. Each day, after construction activities cease, the entire area of disturbed soil shall be sufficiently moistened to create a crust.
- Throughout construction, water trucks or sprinkler systems shall also be used to keep all areas of vehicle movement damp enough to prevent dust raised from leaving the site. At a minimum, this will include wetting down such areas in the late morning and after work is completed for the day. Increased watering frequency will be required whenever the wind speed exceeds 15 mph.
8. **Covered Truck Loads.** Trucks transporting fill material to and from the site shall be covered from the point of origin.
9. **Construction Contact Sign.** Immediately after building permit issuance, signage shall be posted at the points of entry to the site that list the contractor(s) name, contractor(s) telephone number, work hours and site rules to assist Building Inspectors and Police Officers in the enforcement of the conditions of approval.
10. **Construction Equipment Maintenance.** All construction equipment, including trucks, shall be professionally maintained and fitted with standard manufacturers' muffler and silencing devices.
11. **Conditions on Plans/Signatures.** All Planning Commission Conditions of Approval shall be provided on a full size drawing sheet as part of the drawing sets. A statement shall also be placed on the above sheet as follows: The undersigned have read and understand the above conditions, and agree to abide by any and all conditions which is their usual and customary responsibility to perform, and which are within their authority to perform.

Signed:

Property Owner

Date

Contractor

Date

License No.
