Community Development 630 Garden Street 805-564-5485

## **Best Management Practices for Construction Activities:**

wind and water.

- □ Eroded sediments and other pollutants must be retained on site and may not be transported from the site via sheet flow, swales, area drains, natural drainage courses or wind.
- □ Stockpiles of earth and other construction related materials must be protected from being transported from the site by the forces of wind or water.
- □ Fuels, oils, solvents and other toxic materials must be stored in accordance with their listing and are not to contaminate the soil and surface waters. All approved storage containers are to be protected from the weather. Spills may not be washed into the drainage system.
- □ Excess or waste concrete may not be washed into the public way or any other drainage system. Provisions must be made to retain concrete wastes on site until they can be disposed of as a solid waste.
- □ Trash and construction related solid wastes must be deposited into a covered receptacle to prevent contamination of rainwater and dispersal by wind.
- □ Sediments and other material may not be traced from the site by vehicle traffic. The construction entrance roadways must be stabilized so as to inhibit sediments from being deposited into the public way Accidental depositions must be swept up immediately and may not be washed down by rain or other means.

□ Any slopes with disturbed soils or denuded of vegetation must be stabilized so as to inhibit erosion by

Other