

SEISMIC RETROFIT STUDY

Santa Barbara Police Station Santa Barbara, CA



PREPARED FOR

Santa Barbara Department of Public Works Santa Barbara, California

Project No. 10303

September, 2010

TABLE OF CONTENTS

Ι	EXECUTIVE SU	JMMARY	2				
II	INTRODUCTION AND SCOPES						
III	METHODOLOG	YY AND RESULTS	10				
IV	ADDITIONAL H	RETROFIT CONSIDERATIONS AND ACTIONS	14				
V	ESTIMATED R	ETROFIT COST ANALYSIS	16				
VI	CONCLUSIONS	AND RECOMMENDATIONS	17				
VII	LIMITATIONS of	& Exclusions	17				
VIII	CONTACTS		18				
IX	REFERENCES.		18				
Х	APPENDICES						
	А	SEISMIC HAZARD ANALYSIS	20				
	В	DESIGN LOADING CRITERIA	25				
	С	MATERIAL TESTING REPORT	28				
	D	GEOTECHNICAL REPORT	30				
	E	LDP ANALYSIS – ETABS MODEL	31				
	F	NSP ANALYSIS – PERFORM 3D MODEL	43				
	G	MISC CALCULATIONS	69				
	Н	ESTIMATED RETROFIT COST ANALYSIS (2 SCHEMES)	82				
	Ι	PROPOSED RETROFIT SCHEMATIC DRAWINGS					

1

I – EXECUTIVE SUMMARY

This report has been prepared in accordance with an agreement between Coffman Engineers, Inc. and Santa Barbara Department of Public Works. The report pertains only to the Santa Barbara Police Station located at 215 East Figueroa Street, Santa Barbara, California.

The Santa Barbara Police Station building was designed and constructed around 1959. It is located within one mile of the North Channel Slope Fault and two miles from the Arroyo Parida Fault. The potential ground motion (seismic hazard) for this site is significant and the proximity of known active faults is very close. The site observations and our review of the design drawings and analysis indicate that the existing building has deficiencies that could result in poor seismic performance during a design earthquake event.

Performance Based Rehabilitation methodology following ASCE41-06 was used as a guideline for the evaluation and retrofit of the structure. As a first step in the evaluation of the building, the Demand Capacity Ratios (DCRs) of individual wall elements under linear elastic dynamic loads (MCE & 2/3MCE response spectra) was checked by using an ETABS 3D computer model. The final results show that many wall piers and spandrels are flagged with shear / flexural DCRs greater than 1. Numerous existing concrete elements (piers and spandrels) have DCRs greater than 2. The basement 10" wall piers along Grid 6 (East Elevation) and spandrels along Grid-F (interior 3-story walls) are severely overstressed in shear and flexure at the 2/3MCE seismic hazard level (475 year reoccurrence).

A non-linear static analysis (NSP) was performed to better characterize the behavior of the structure and to achieve selected seismic performance objectives for specific seismic hazards. Nonlinear PERFORM 3D models were created in compliance with ASCE41-06 standards. The nonlinear pushover analytical results, from the existing building computer model, show that the basement wall piers along Grids 1, 2 and 6 (Y-direction, N/S orientation) exhibit shear failure at the *Life Safety* (LS) performance level at 2/3 MCE (475 year) before achieving the target roof displacement. Also, the existing building does not develop enough base shear along Y-direction when the shear failure occurs. The pushover curve in the Y-direction shows significant strength and stiffness degradation before a reasonable base shear is developed. Along X-direction (E/W orientation) Grid F three basement 10" spandrels fail in shear (at LS performance) before the target displacement.

Implementation of a cost-effective retrofit scheme was based on extensive and iterative nonlinear pushover analysis. We proposed an innovative multifaceted retrofit scheme that includes shotcrete walls (pneumatically applied concrete) and FRP (Fiber Reinforced Polymers) laminates to strengthen the structure and provide increased ductility. The final nonlinear pushover analytical result shows that the retrofitted building would achieve the LS performance objective and come close to the *Immediate Occupancy* (IO) performance objective at 2/3 MCE event.

In addition to the proposed retrofit scheme, a number of issues need to be addressed to provide satisfactory seismic performance including; 1. Out-of-plane anchorage of third floor walls to roof

diaphragm. 2. Strengthening concrete columns for deformation compatibility and ductility. 3. Diaphragm strengthening for load path to new shear walls. 4. Heavy suspended plaster ceiling removal.

Overall, the seismic rehabilitation measures required, when considered alone, are straightforward, reasonable and relatively cost efficient. However, when handicap accessibility, asbestos removal, replacement of antiqued MEP systems and architectural finishes, and temporary relocation of essential police services are considered the cost and complexity of this proposed rehabilitation increases dramatically. Nonstructural work is likely to make up the majority of work required to complete the proposed seismic retrofit.

Alternative Scheme:

One alternate option was investigated during this study. The rear (northerly) two-story portion of the existing police station could be torn down and replaced by a modern structure separated by a seismic separation joint. The remaining (southerly) three-story structure would require a significant seismic retrofit to meet the *Life Safety* performance criteria of ASCE41 for the 2/3MCE (475 year) seismic hazard. Additional shear walls would be required at the Basement Level on the east and west elevation. On the east elevation the existing mechanical room has three openings where at least one will need to be in filled. The north elevation would require strengthening of the spandrel beams. The roof diaphragm will need strengthening along with remediation of the out-of-plane anchorage of roof framing to the existing concrete walls.

II – INTRODUCTION AND SCOPE

As-Built Existing Building Structural Description

The Santa Barbara Police Station building located at 215 East Figueroa Street was designed and constructed around 1959. The building footprint is 89 feet by 144 feet in the largest dimensions. There are three stories at the southern elevation and two stories at the northern elevation. The total floor area of the building is approximately 27,000 square feet. The 1st and 2nd floors are a concrete pan-joist system including a 4½ inch thick slab and 18½ inch deep joists. The high roof over the southern street entry consists of steel and wood frame with a tile roof. From the south street entrance the building has one story partially below grade (Basement Level). The west elevation also has the Basement Level partially below grade. The east elevation starts at the south partially below grade and daylights out completely moving north to the garage openings.

The structure is a concrete structure with interior and exterior perforated shear walls. The thickness of walls at Basement Level is 10 inches, and 8 inches at the first floor and above. On the first floor, there are several discontinuous shear walls (interior) supported by the concrete girders and concrete columns. The columns are founded on conventional spread, concrete footings. The typical rectangular strip footings with various widths were designed for all concrete shear walls. The lateral loads (wind and seismic forces) are distributed horizontally through the wood/steel framed high roof and the concrete pan joist floors (including low roof on the northerly portion of the building) to the perimeter concrete perforated walls. The shear walls were designed before modern detailing and analysis techniques were developed for buildings located in high seismic locations, and not in compliance with the modern building codes.

Site Visit Observations

The existing building is in good condition considering the age of the original structure. There were no apparent signs of significant deterioration or distress. Some minor cracks were observed in the low roof parapet at the large notch in the roof diaphragm directly above the west entrance door (Second Level). On the east elevation there are two additional window openings not shown on the original drawings from 1959. On the west elevation, First Level, one narrow wall opening has been closed (northern end of east elevation, old holding cell area) and another narrow opening has been enlarged to accommodate a new door. There is no evidence of subsidence or differential settlement.

4

Destructive Testing

Destructive testing was performed under the guidelines of ASCE41. Limited concrete cores and reinforcing steel samples were extracted in conformance with ASCE4. Material sampling locations and quantities were selected to reduce disruption at the functioning police station. Eight concrete shear wall core samples were taken at random locations on the exterior walls. Additionally, two beam cores and two slab cores samples were extracted. Compressive strength of existing concrete shear wall samples ranged from 4,815 psi to 2,196 psi. The coefficient of variation is 26% for the tests. The mean minus one standard deviation is 2,523 psi. The 1959 design documents indicate the concrete strength as 2,500 psi for all elements except for the slab-The concrete design values used in this study are appropriate for Basic Safety on-grade. Objective (BSO) of Life Safety Building Performance Level (LS) at BSE-1. The large coefficient of variation found would not be appropriate for the Enhanced Rehabilitation Objectives of Immediate Occupancy (IO) at BSE-1. Additional testing samples could be performed to lower the coefficient of variation. However, the cost and disruption is not warranted based on the findings and recommendations of this study.

Rebar samples have virtually identical yield values (51.3 ksi and 51.2 ksi). A value of 50 ksi was used for rebar properties. The rebar samples are consistent with steel reinforcement of the 1950s.

Site Seismic Hazards

The Santa Barbara Police Station is located within one mile of the North Channel Slope Fault and two miles from the Arroyo Parida Fault. The North Channel Slope Fault could generate a 7.4 magnitude earthquake that could result in 0.747g of ground acceleration at the site (MMI = XI). The USGS 475 year seismic hazard (2/3 MCE) has SDS = 1.364g and SD1 = 0.782g and the USGS 2,475 (MCE) year seismic hazard has SDS = 2.047g and SD1 = 1.173g. The design earthquake for new buildings is the 475 year hazard (2/3 MCE) and corresponds to Seismic Design Category F (seismic hazards range from A to F) when you consider a police station is an essential facility (Occupancy Class IV). The potential ground motion (seismic hazard) for this site is significant and the proximity of known active faults is very close. (See Appendix A for the seismic hazard analysis by using EQFAULT Version 2.20).

The only major historical earthquake that caused moderate ground shaking at the SB Police Station site was a 5.5 magnitude earthquake on August 13, 1978 where the epicenter was south of the city in the Santa Barbara Channel (See Appendix A). It appears that the 1978 ground shaking did not cause any significant damage to the SB Police Station. The ground motion from the August 13, 1978 earthquake was likely very small (approximately 0.15g or less) when compared to the potential ground motion due to a rupture of the North Channel Slope Fault or Arroyo Parida Fault (up to 0.747g).

Existing Building Deficiencies

FEMA 454 (see page 7-42, Figure 7-11A) recognizes that concrete buildings with perforated shear walls (window and door openings in a concrete wall) can be unstable when subjected to large ground motion unless properly detailed. Reinforcement detailing and shear wall layout factor greatly into the seismic performance of perforated shear wall buildings. Unfortunately, the SB Police Station (circa 1959) was designed before modern detailing and analysis techniques were developed for buildings located in high seismic locations. Our review of the design drawings and analysis indicate that the existing building has the following deficiencies:

- Out-of-plane anchorage of third floor (2nd Floor as labeled by original drawings) walls to roof diaphragm. This deficiency could result in partial roof collapse. An adequate connection needs to be added between the steel roof trusses and the exterior concrete wall. Also, the existing straight sheathed roof diaphragm needs to be strengthened by adding new plywood.
- 2) Discontinuous shear walls on second floor in the east west direction (1st Floor per plans) that do not continue to Basement level. Dynamic behavior of this type of system is undesirable without special detailing considerations which are absent in the original configuration. Adding new continuous walls to the basement level is impractical and would be a major disruption in the current building programming. Strengthening and improving the ductility of the existing concrete columns below the discontinuous shear walls will improve seismic performance and mitigate the potential hazard of column failure.
- 3) Spacing and minimum reinforcing ratios for vertical and horizontal reinforcement (rebar) in the existing shear walls exceeds current code requirements. Modern code requirements, in high seismic regions, dictate maximum spacing and minimum reinforcement ratios for concrete shear walls to provide a minimum expected ductility (deformation without brittle failure) needed to control damage and provide stability during strong ground motion. The concrete shear wall reinforcing requirements of modern codes improves energy dissipation and reduces crack widths in shear walls when subjected to a design earthquake. Based on the nonlinear analysis most walls have sufficient strength to perform well under strong ground motion. Localized strengthening will be added as needed to improve overall seismic performance and to achieve the seismic performance objective.
- 4) Existing concrete column detailing does not provide the required ductility (ability to deform without brittle failure) to support gravity beams and discontinuous shear walls. Building sway under earthquake motion requires that the columns have tightly spaced transverse ties (confinement) to preclude buckling of longitudinal (vertical) reinforcing. The existing detailing of the concrete columns could result in brittle shear or buckling

failure. Partial collapse could occur. Wrapping the existing concrete columns with FRP (Fiber Reinforced Polymers) is an effective method to improve ductility and strength.

- 5) Insufficient lateral resistance along the East Elevation (driveway running north south where mechanical room door, stair well and motorcycle garage are located). Many openings are located in the East Elevation running in the long direction of the building. The nonlinear analysis indicates that a "story mechanism" (failure mode of plastic hinges) can form along the Basement Level in the north south direction. This mechanism then transfers lateral loading to the West Elevation and another "story mechanism" forms along the West Elevation. Additional stiffness and strength is required along the East and West Elevations at the Basement Level.
- 6) Very high flexural and shear demands develop across window and door openings in the spandrel beams. In the east west direction (short direction) the spandrels (header) beams transfer forces between the solid piers (vertical wall elements) when the building deforms due to strong ground motion. Spandrel beams need additional strength to transfer wall forces.
- 7) Insufficient rebar lap splices can cause tension failures in perforated shear walls. However, the detailing and anticipated locations of lap splices in shear walls do not appear to be a significant hazard. Some wall damage and strength/stiffness degradation is anticipated from the insufficient lap splices. The nonlinear backbone curves of ASCE41 were developed using shear wall segments that had antiquated reinforcement detailing. Recent testing of shear wall piers and spandrels indicate that the backbone curves of ASCE41 are conservative. Therefore, we believe our nonlinear analysis captures the effects of insufficient lap splices without being overly conservative or un-conservative.
- 8) Large reentrant corner (notch in roof diaphragm) midway down the West Elevation at side entrance at 2nd Floor. This notch causes a discontinuity in the roof diaphragm. It is expected that the notch will cause significant damage in the roof diaphragm due to stress concentrations. Also, the notch interrupts the flow of inertial forces through the roof diaphragm to the adjacent shear walls. Closing the notch by filling in the roof opening with a reinforced concrete slab will improve seismic performance and reduce earthquake damage.
- 9) There are many original hard ceilings throughout the police station consisting of cement or gypsum plaster suspended by gravity wires. The ceiling weighs approximately 10 to 14 pounds per square foot. There are no earthquake sway bracing or compression struts as required for new construction. Corrosion of the gravity wires along with inadequate bracing could result in a significant falling hazard during a major earthquake. The heavy ceilings could block egress and cause injury to occupants. Original plaster ceilings should be properly braced or removed.

<u>Note</u>: Other nonstructural seismic hazards may exist. This study specifically excludes nonstructural seismic hazards. A comprehensive investigation of nonstructural hazards is required under ASCE31 and ASCE41 along with structural evaluation. In order to provide a

complete seismic hazard study a nonstructural hazard assessment is required. The absence of properly anchored architectural elements, mechanical equipment, furniture, computers and other components can cause significant falling hazards that pose a risk of injury and operational disruption. Falling hazards can block egress and result in hazardous material spills.

Discussion of Retrofit Performance Objective

The anticipated seismic performance of the SB Police Station under the Design Earthquake (BSE-1, 2/3 MCE, 475 year reoccurrence) is poor. In order to meet the *Life Safety* seismic performance requirements of ASCE41 for the Design Earthquake significant strengthening is required. The proposed retrofit scheme exceeds the *Life Safety* performance level approaching the *Immediate Occupancy* requirement.

In our opinion, a retrofit scheme that would achieve the *Immediate Occupancy* seismic performance is almost impossible and impractical. The *Immediate Occupancy* level of seismic performance requires very strict limits on damage. Based on the 1959 concrete reinforcing detailing standards reducing crack widths to 1/8 of an inch (see ASCE41 Table C1-3) is practically impossible without considerable cost and loss of usable space.

New building code requirements for police stations require a *Life Safety* seismic performance level. Additionally, police stations are required to be designed for pseudo earthquake forces 50% higher than a typical private building (I = 1.5) because they are used as essential facilities. The increase in design forces "enhance" the seismic performance of the building by reducing the ductility demands (less deformation results in less damage). The seismic performance for a police station, fire station and hospital could be categorized as "enhanced *Life Safety*". The term *Immediate Occupancy* is not required or even discussed in new building design codes for emergency service buildings. The *Immediate Occupancy* seismic performance objective of ASCE41 appears to be appropriate and rational for an essential police facility. The reality is that ASCE41 is the only national standard to address seismic performance above *Life Safety* but only for existing structures. New construction building codes may adopt the enhanced seismic performance objectives, such as *Immediate Occupancy*, appear to be a roadblock to implementation in new building design and codes.

Current seismic detailing practices improve seismic performance and reduce the extent of earthquake damage. Codes are regularly updated to reflect new research and "lessons learned" from recent earthquake damage worldwide. A circa 1959 building is more likely to experience more earthquake damage than a new building because modern detailing reduces the likelihood of earthquake damage. However, the epicenter distance, local geology, building orientation, building configuration, structural system and quality of construction all effect how new or older

buildings perform in a major earthquake. Ironically, sometimes an older building seismically performs better than an adjacent modern structure. Typically modern structures fair much better after major earthquakes due to improvements in design and detailing.

The Santa Barbara Police Station is categorized as a non-ductile perforated concrete shear wall structure. Thousands of buildings of this type and of similar age exist statewide. There is a reasonable concern that buildings of this age and type could be a significant seismic hazard. Currently, state and local governments do not require a mandatory retrofit for this type and age of structure. However, a change in occupancy or a major renovation would likely trigger an ASCE41 seismic retrofit under the 2007 California Building Code.

The proposed seismic retrofit scheme will provide *Life Safety* to occupants while reducing earthquake damage. However, earthquake damage to the retrofitted structure is anticipated due to the age, original design methodologies and existing concrete reinforcing detailing of the original structure. Cracks in the perforated shear walls will likely occur under the anticipated strong ground motion. The retrofitted building could be damaged where repair is not economical or practical. Replacement could be the only option after a major earthquake close to the building site.

III – METHODOLOGY AND RESULTS

Seismic Retrofit & Design Code:

ASCE 41-06: Seismic Rehabilitation of Existing Buildings

Linear Dynamic Procedure (LDP Analysis) – ETABS 3D Models

-See Appendix E for the detail analysis

Seismic Hazard: MCE and 2/3MCE response spectra (See Appendix B)

Modeling Assumptions:

Gravity Loading (see Appendix B for the design load criteria)

Effective lateral stiffness of exiting walls:

- 50% E_cI_g for Flexural rigidity;
- 40% E_cA_w for Shear rigidity
- (fc' = 2.5 ksi; fy = 50 ksi)

MODEL1: Existing Building with Pinned Base (Rigid Base)

Assume all walls and columns are pinned at the base Building Periods:

 $T_1 = 0.10$ sec along Y-direction (longitudinal direction)

 $T_2 = 0.08$ sec along X-direction (short direction)

Building Base Shear for 2/3MCE:

4325 kips along X-direction 5020 kips along Y-direction

MODEL2: Existing Building with Flexible-Base (Soil- Structure Interaction)

All walls and columns are supported by soil spring derived from ASCE41-06. <u>Building Periods</u>:

 $T_1 = 0.17$ sec along Y-direction (longitudinal direction)

 $T_2 = 0.16$ sec along X-direction (short direction)

Building base shear for 2/3MCE:

5883 kips along X-direction (Note: Higher base shear than pinned base) 5889 kips along Y-direction

Summary of LDP Analytical Results:

Based on ASCE41, the DCR (Demand Capacity Ratio) with appropriate m-factor were calculated for all existing wall piers and spandrels at different performance and earthquake hazard levels. Two cases of 2/3MCE at LS (*Life Safety*) and MCE at CP (*Collapse Prevention*) were included. The final results show that many wall piers and spandrels are flagged with shear / flexural DCRs (demand capacity ratios) greater than 1. Numerous elements have DCRs greater than 2. The basement 10" wall piers along Grid 6 (East Elevation) and spandrels along Grid-F (interior 3-story walls) are severely overstressed in shear and flexure at the 2/3MCE seismic hazard level (475 year reoccurrence). The LDP model was used to understand the dynamic behavior and act as a benchmark for elevating the results of the Nonlinear Static Procedure of ASCE41.

Nonlinear Static Procedure (NSP Analysis / Push Over Analysis) – PERFORM 3D

-See Appendix F for the detail analysis

Modeling Assumptions:

Gravity Loading:

Based on ETABS model, all gravity loads are applied as line loads to the PERFORM model. The self weight of columns and walls are automatically accounted by program. Use the following load combinations for gravity loads: $Q_G = 1.1(DL + \frac{1}{4} LL)$, and $Q_G = 0.9 DL$

Boundary Conditions:

All columns and walls are pinned on the base. All gravity beams and columns are modeled as linear elements, and concrete walls are modeled as inelastic elements.

Material Properties:

Use the stress-strain curves of reinforcing bar and concrete to define the inelastic properties of rebar and concrete fibers in PERFORM model (trilinear / bilinear), see Appendix F. The initial lateral stiffness of concrete wall was defined as follows: 50% $E_c = 0.5 \times 57000 \sqrt{f_c}$ ' for concrete flexure; $G_c = 0.4 \times E_c / [2(1+v)]$ and v = 0.2 for concrete shear (f_c ' = 2.5 ksi for concrete; $f_y = 50$ ksi and $E_s = 29000$ ksi for rebars)

Fiber Element Modeling:

Concrete wall is modeled as an inelastic wall element by using Fiber Model, including

- i). Inelastic concrete fiber (4, 3, and 2 fibers are used in an element depending on the different length/ height of wall piers/spandrels);
- ii). Inelastic steel fiber (4, 3, and 2 fibers are used in an element depending on the different length/ height of wall piers/spandrels);
- iii). Inelastic shear material component (Based on Table 6-19 of ASCE41-06, and shear stress capacity v_n based on the shear reinforcing area of walls)

Mass Assignments:

Nodes on each floor are slaved as a rigid diaphragm, and apply the following masses at mass center (from ETABS, unit: kip-in).

Diaphragm	MassX	MassY	MMI	XM	YM	ZM
ROOF	0.9448	0.9448	195212	538.118	-1471.5	390
2NDFLR	6.5607	6.5607	2893717	555.887	-889.258	270
1STFLR	7.6347	7.6347	2895851	554.393	-886.818	120

Pushover Profiles:

The vertical distribution of lateral pushover forces is proportional to the fundamental mode shape $(1^{st} \text{ Mode of Free Vibration})$ in the direction under consideration.

Target Displacement:

Target displacement calculation is based on ASCE 41-06 and coefficients input under "user defined" in PERFORM 3D. Manually input all coefficients C_0 , C_1 , C_2 , C_3 and S_a (computed from hand calculations based on linear and nonlinear models).

Nonlinear Acceptance Criteria:

The limits for wall rotation and wall shear strain under the different performance levels are defined as follows (based on ASCE 41-06):

Performance Level	Wall Rotation	Wall Shear Strain
Immediate Occupancy (IO)	0.002	0.40%
Life Safety (LS)	0.004	0.60%
Collapse Prevention (CP)	0.006	0.75%

Summary of Pushover Analytical Results:

1). Pushover Analysis for the Existing Building:

Target Displacement drift ratio: $\delta_t = 0.07\%$ along X-direction $\delta_t = 0.17\%$ along Y-direction

The pushover curves of the existing building show that the basement wall piers along Grids 1, 2 and 6 exhibit shear failure at the *Life Safety* performance level at 2/3 MCE (475 year) before achieving the target roof displacement. Also, the existing building does not develop enough base shear along Y-direction when the shear failure occurs. The pushover curve in the Y-direction shows significant strength and stiffness degradation before a reasonable base shear is developed.

Along X-direction Grid F the three basement 10'' spandrels shear fail (LS) before target displacement.

2). Pushover analysis for the retrofitted building:

Proposed Retrofit Scheme: (see schematic retrofit drawings)

- Infill two openings and add 8" shotcrete wall to existing 10" wall along Grid-6 and Grid-1
- Use FRP (fiber reinforced polymers) shear/flexural strengthening of concrete spandrels to increase the shear capacity
- Confine existing concrete columns with FRP to improve ductility and deformation compatibility
- Add out-of-plane anchorage to high roof diaphragm and strengthening wood diaphragm
- Infill notch in concrete diaphragm on low roof (2nd Floor) with reinforced concrete slab

Target Displacement drift ratio: $\delta_t = 0.06\%$ along X-direction $\delta_t = 0.09\% \text{ along Y-direction}$

Pushover curves show that the building was able to achieve *Immediate Occupancy* (IO) performance level before target displacement for shear, and achieve *Life Safety* (LS) level for flexure. However, the building would achieve IO performance level if numerous other locations had enhanced flexural strength.

IV - ADDITIONAL RETROFIT CONSIDERATIONS AND ACTIONS

In addition, the following deficiencies of the existing building were examined, and the corresponding retrofit actions are proposed (See Appendix I for Schematic Drawings).

1). Deformation Incompatibility and Ductility of Existing Concrete Columns:

Deficiencies:

- All gravity concrete columns are non-ductile and incompatible with the anticipated inelastic building lateral drift.
- Existing columns at Basement Level supporting discontinuous shear walls on First Level do not have sufficient ductility (transverse tie spacing and detailing) to resist overturning loads from shear walls above.

Retrofit Actions:

✓ FRP all gravity concrete columns to improve the ductility.

2) Load Path:

Deficiencies:

- Diaphragm and collector strength to new lateral elements (load path)
- Large reentrant corner (notch in roof diaphragm) midway down the West Elevation at side entrance at 2nd Floor.
- Out-of-plane anchorage of third floor walls to roof diaphragm.
- Foundation capacity at shotcrete walls

Retrofit Actions:

- \checkmark Strengthen the diaphragm to provide an adequate load path to new lateral elements
- Closing the notch by filling in the roof opening with a reinforced concrete slab will improve seismic performance and reduce earthquake damage.
- \checkmark Add steel member HSS to strengthen the anchorage
- ✓ Modify foundations for concentrated loading from new braced framed columns

3) Falling Hazards:

Deficiency:

• Heavy suspended gypsum plaster ceilings are located throughout the building. The existing suspension anchorage consists of gravity wires only. Hanger wires cannot resist compression loading and lateral loading from strong ground motion.

Retrofit Actions:

✓ Remove all existing suspended heavy gypsum plaster ceilings or retrofit ceilings with new gravity wires, compression struts and sway braces in compliance with current code.

Note: Nonstructural anchorage is specifically excluded from this study. The ceiling falling hazard was included in this study because of the potential severity of the hazard and the cost implications. A complete nonstructural hazard assessment should be conducted as a supplement to this study in conformance with ASCE41.

V – ESTIMATE RETROFIT COST ANALYSIS

A construction estimate was prepared by a professional construction estimator for the two proposed seismic retrofit schemes. The first scheme is for a complete seismic retrofit of the entire existing structure. The second scheme is a partial seismic retrofit of the southern threestory portion of the building where the back two-story structure is demolished and replaced by a new structure.

The estimates include only the work required to complete the seismic retrofit schemes and the associated collateral architectural, mechanical, plumbing and electrical work required. The estimate does not include the new structure proposed in the second scheme where the northern two-story portion of the existing building is demolished. Also, a demolition cost for the northern two-story structure is excluded from the second scheme estimate.

Scheme #1 – Complete Seismic Retrofit (with collateral architectural and MEP work)

Estimated Cost - \$3,147,300 (see Appendix H for detailed estimate)

Scheme #2 – Partial Seismic Retrofit (three-story southern portion only with collateral architectural and MEP work)

Estimated Cost - \$1,864,700 (see Appendix H for detailed estimate)

Exclusions:

- 1. ADA upgrades
- 2. Asbestos abatement other than ceilings as indicated on schematic plans
- 3. Hazardous waste surveys and remediation (mold, fuel, lead and others)
- 4. Mechanical, electrical and plumbing (MEP) system upgrades (only local MEP replacement due to associated retrofit actions)
- 5. Relocation of personnel and/or essential facilities including temporary services or structures

VI – CONCLUSIONS AND RECOMMENDATIONS

The retrofit scenarios performed in this study has resulted in the following recommendations:

- Shotcrete new shear walls and infill openings at the existing Basement Level along Grids 1 and 6
- Add new 8" wall pier at the basement garage door of the north-east corner
- FRP laminate selected wall spandrels
- FRP wrap existing concrete columns to increase ductility and deformation compatibility
- FRP laminate existing floor diaphragm to provide an adequate load path to new shear walls
- Remove or retrofit all existing heavy suspended gypsum plaster ceilings

See Appendix I for proposed retrofit scheme drawings.

The provided schematic retrofit drawings shall be used for pricing purposes only and shall not be used for construction. Complete design and construction drawings are not part of the current scope of work. Future implementation of the proposed retrofit scheme requires additional detailed analysis and design to create a comprehensive and complete set of construction documents.

A complete ASCE41 nonstructural anchorage evaluation should be part of a comprehensive seismic rehabilitation project.

VII-Limitations and Exclusions

This report is based on a limited physical observation of the premises and the limited structural evaluation described above. Construction drawings were also available for the review. The onsite observation was made solely to determine the vertical and lateral load structural integrity of the building based on observed features, which were exposed and accessible. The specific items noted were those that were observable, and there may be additional defects that were not observed. The recommendations are based on the assumptions stated herein. Neither the observation, evaluation, nor the recommendations are intended to cover mechanical, electrical, geotechnical, environmental, pest control, or architectural features.

CEI has prepared this report for the exclusive use by the City of Santa Barbara. Services were performed by CEI in a manner consistent with the level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions. No other warranty, expressed or implied, is made.

VIII - CONTACTS

Paul Van Benschoten, SE Principal vanbenschoten@coffman.com

Silian Lin, PhD, PE lin@coffman.com

Coffman Engineers Inc 16133 Ventura Blvd. Suite 1010 Encino, California 91436

Phone (818) 285-2650 Fax (818) 285-2651

XI – REFERENCES

<u>Reference Standards</u>:

ASCE / SEI 31-03: Seismic Evaluation of Existing Buildings ASCE/SEI 41-06: Seismic Rehabilitation of Existing Buildings FEMA 454: Designing for Earthquakes: A Manual for Architects FEMA 356: Prestandard and Commentary for the Seismic Rehabilitation of Buildings

<u>X – APPENDICES</u>

- APPENDIX A SEISMIC HAZARD ANALYSIS
- APPENDIX B DESIGN LOADING CRITERIA
- APPENDIX C MATERIAL TESTING REPORT
- APPENDIX D GEOTECHNICAL REPORT
- APPENDIX E LDP ANALYSIS ETABS MODEL
- APPENDIX F NSP ANALYSIS PERFORM 3D MODEL
- APPENDIX G MISC CALCULATIONS
- APPENDIX H ESTIMATED RETROFIT COST ANALYSIS
- APPENDIX I PROPOSED RETROFIT SCHEMATIC DRAWINGS

APPENDIX A: SEISMIC HAZARD ANALYSIS

SITE SEISMIC HAZARDS

The site is located in the City of Santa Barbara, California. Although this region has not been as seismically active as other areas of the state in recent history, the site may experience strong ground shaking from earthquakes on a number of fault zones. Using the computer program EQFAULT Version 2.20, we have determined the approximate distances to the most significant faults and have listed the Maximum Capable Earthquake (MCE) magnitudes. The MCE corresponds to the maximum earthquake that appears capable of occurring under the presently known tectonic framework.

Earthquake Fault	Distance (miles)	Maximum Credible Earthquake Magnitude
North Channel Slope	1	7.4
Mission Ridge-Arroyo Parida-Santa Ana	2	7.2
Red Mountain	5	7.0
Santa Ynez (West)	6	7.1
Santa Ynez (East)	6	7.1
Ventura-Pitas Point	12	6.9
Oakridge (Mid-Channel)	12	6.6
Oak Ridge (Offshore)	17	7.1
Big Pine	24	6.9
Los Alamos-W. Baseline	25	6.9
Santa Cruz Island	28	7.0
Santa Rosa Island	30	7.1
Channel Island Thrust	31	7.5
Oak Ridge (Onshore)	31	7.0
San Cayetano	31	7.0
Anacapa-Dume	32	7.5
San Andreas	39	8.0

PROBABILISTIC GROUND MOTION HAZARD ASSESSMENT

The seismic intensity (see **Glossary**) at the site was estimated for earthquakes on the known active fault zones within a 50-mile radius of the site. Using the computer program FRISKSP, Version 4.00, we evaluated the peak ground acceleration and then converted the acceleration to a corresponding modified Mercalli Intensity (see **Glossary** and **Table 1**).

Average Recurrence Interval	Peak Ground Acceleration	Modified Mercalli Intensity
475 years	0.46g	VIII1⁄2


OTHER SEISMIC HAZARDS


The other earthquake hazards at the site were evaluated based on the following information:


Regional Sources:

- California Geological Survey: Special Publication 42 (1999); Geologic Data Map No. 6 (1994).
- City of Santa Barbara: Safety Element of the General Plan (1979); Draft Environmental Impact Report (2010).

Seismic Hazard	Potential	Within State Hazard Zone?	Within City Hazard Zone?
Surface Fault Rupture	Low	No	No
Liquefaction (see Glossary)	Low	Not Mapped	No
Earthquake-Induced Landslides	Low	Not Mapped	No







Major Historical Earthquakes in The Santa Barbara Region:

APPENDIX B: DESIGN LOADING CRITERIA

STRUCTURAL DESIGN CRITERIA:

BUILDING CODE USED FOR DESIGN :		ASCE 41-06
SEISMIC CRITERIA USED FOR DESIGN:		ASCE 41-06
Latitude Longitude	34.42525 -119.70077	Project Site : 215 East Figueroa St. Santa Barbara, CA
Ss	2.047	Ganta Darbara, Gre
S1 Sds	0.782 1.364	Soil Type: SD
Sd1	0.782	
LATERAL FORCE RESISTING SYSTEM:		Concrete Shear Walls

DEAD LOADS:

Main Roof Diaphragm:					Mass
	Gravity		Seismic		(slugs/ft ²)
Tile Roofing	20.0	psf	20.0	psf	0.62
Plywood Roofing	3.0	psf	3.0	psf	0.09
Framing	4.0	psf	4.0	psf	0.12
MEP	2.0	psf	2.0	psf	0.06
Fire Sprinklers	1.5	psf	1.5	psf	0.05
Cement Plaster Ceiling	15.0	psf	15.0	psf	0.47
FLOOR DL (ADD PARTITION WEIGHT, SEISMIC ONLY)	45.5	psf	45.5	psf	1.41
2nd Floor Diaphragm:					Mass

ind i loor brapinagini					mado
	Gravity		Seismic	_	(slugs/ft ²)
Concrete Pan Joist System	110.0	psf	110.0	psf	3.42
Flooring	5.0	psf	5.0	psf	0.16
Fire Sprinklers	1.5	psf	1.5	psf	0.05
MEP	3.0	psf	3.0	psf	0.09
Ceiling	2.0	psf	2.0	psf	0.06
FLOOR DEAD LOAD (ADD PARTITION WEIGHT)	121.5	psf	121.5	psf	3.77

Flat Roof (2nd Level) Diaphragm:					Mass
	Gravity	_	Seismic	_	(slugs/ft ²)
Concrete Pan Joist System	110.0	psf	110.0	psf	3.42
Roofing (2 Layers)	10.0	psf	10.0	psf	0.31
Fire Sprinklers	1.5	psf	1.5	psf	0.05
MEP	3.0	psf	3.0	psf	0.09
Ceiling	2.0	psf	2.0	psf	0.06
FLOOR DL (ADD PARTITION WEIGHT, SEISMIC ONLY)	126.5	psf	126.5	psf	3.93

1st Floor Diaphragm:	Gravity		Seismic		Mass (slugs/ft ²)
Concrete Pan Joist System	110.0	_ psf	110.0	_ psf	<u>(siugs/it)</u> 3.42
Flooring	5.0	psi	5.0	psi	0.16
Fire Sprinklers	1.5	psf	1.5	psf	0.05
MEP	3.0	psf	3.0	psf	0.09
Ceiling	2.0	psf	2.0	psf	0.06
TOTAL DEAD LOAD (ADD PARTITION WEIGHT)	121.5	psf	121.5	psf	3.77
Partition Loads:					Mass
	Gravity		Seismic		(slugs/ft ²)
ROOF PARTITION LOAD	0	psf	10.0	psf	0.31
2ND FLOOR PARTITION LOAD	20	psf	20.0	, psf	0.62
1ST FLOOR PARTITION LOAD	20	psf	20.0	psf	0.62
LIVE LOADS:					
Roof	20	psf			
Floor	50	psf			
Corridor/Stairs	80	psf			
Property Room	150	psf	(high den	sity file	cab)
MATERIALS:					
Concrete, Slab on Grade	$f'_{c} =$	2	ksi		
Concrete, Structural Slabs	f' _c =	2.5	ksi		
Concrete, Column	f' _c =	2.5	ksi		
Reinforcing Steel	$f_y =$	40	ksi	Турі	cal
		50	ksi	Colu	mns

LOAD COMBINATIONS: (ASCE41-06)

- 1). 1.1 ($Q_D + Q_L$) ± Q_E
- 2). $0.9 Q_{D} \pm Q_{E}$
- Note: $Q_D = Design Dead Loads;$

Q_L = Design Live Loads (unreduced);


 Q_E = Design Earthquake Loads.

CRACKED WALL EFFECTIVE STIFFNESS: (Table 6-5 in ASCE41-06)

Flexural Rigidity:	0.5 E _c I _g
Shear Rigidity:	$0.4 \; E_c \; A_w$
Axial Rigidity:	$E_{c} A_{q}$

MCE & 2/3MCE RESPONSE SPECTRA (USGS)

Conterminous 48States2006 InternationalBuildingCodeLatitude34.425246Longitude = -119.70774Site Modified Response Spectrum for Site ClassDSMs =Ss andFaSM1= FVS1				2006 Inter Latitude Longitud Site Modit Class D	nous 48 States rnational 34.42524 e = -119.70 fied Response S s x SMs and	Building 6 774 Spectrum fo SD1 = 2/3	
Site Class		= 1.0 ,Fv	= 1.5	Site Cla	ss D - Fa	= 1.0 ,Fv	
Period (sec)	Sa (g)	Sd (inches)	Period (sec)	Sa (g)	Sd (inches)
0	0.819	0	/	0	0.546	0	,
0.115	2.047	0.263		0.115	1.364	0.175	
0.2	2.047	0.8		0.2	1.364	0.533	
0.573	2.047	6.571		0.573	1.364	4.38	
0.6	1.955	6.877		0.6	1.304	4.585	
0.7	1.676	8.024		0.7	1.117	5.349	
0.8	1.467	9.17		0.8	0.978	6.113	
0.9	1.304	10.316		0.9	0.869	6.877	
1	1.173	11.462		1	0.782	7.642	
1.1	1.067	12.609		1.1	0.711	8.406	
1.2	0.978	13.755		1.2	0.652	9.17	
1.3	0.902	14.901		1.3	0.602	9.934	
1.4	0.838	16.047		1.4	0.559	10.698	
1.5	0.782	17.194		1.5	0.521	11.462	
1.6	0.733	18.34		1.6	0.489	12.227	
1.7	0.69	19.486		1.7	0.46	12.991	
1.8	0.652	20.632		1.8	0.435	13.755	
1.9	0.617	21.779		1.9	0.412	14.519	
2	0.587	22.925		2	0.391	15.283	



APPENDIX C: MATERIAL TESTING REPORTS

Summary of Material Testing Results *

* See Attached Test Results from ACCU-TEST Structural Laboratories Inc.

Member	CORE #	f'c	E	Unit Weight
		psi	ksi	pcf
	1	3885	3,553	142.0
	2	3322	3,285	139.0
	3	2196	2,671	139.0
WALL	4	2961	3,102	137.0
VVALL	5	4487	3,818	142.0
	6	4815	3,955	139.0
	7	2779	3,005	134.0
	8	2937	3,089	135.0
	Mean=	3423	3310	138.4
	Variance=	809044	189664	
	Standard Deviation=	899	436	
	Coefficient of Variation=	26.3%	13.2%	

Mean - Std. 2523 Deviation=

Member	CORE #	f'c	E	Unit Weight
		psi	ksi	pcf
BEAM	1	3895	3,557	144.0
DEAIVI	2	4129	3,663	137.0
	Mean=	4012	3610	140.5
	Variance=	27378	5544	
	Standard Deviation=	165	74	
Coefficient of Variation= Mean - Std. Deviation=		4.1%	2.1%	
		3847		

Member	CORE #	f'c	E	Unit Weight
		psi	ksi	pcf
SLAB	1	4937	4,005	144.0
SLAD	2	6191	4,485	137.0
	Mean=	5564	4245	140.5
	Variance=	786258	115147	
	Standard Deviation=	887	339	
Coefficient Variatio		15.9%	8.0%	
	Mean - Std. Deviation=	4677		

Member	Specimen#	Yield Point	Tensile Strenght
	·	ksi	ksi
Rebar	1	51.3	80.4
Rebai	2	51.2	76.4
	Mean=	51.3	78.4
	Variance=	0.0	8.0
	Standard Deviation=	0.1	2.8
	Coefficient of Variation=	0.1%	3.6%
Mean - Std. Deviation=		51.2	


APPENDIX D: GEOTECHNICAL REPORT (LETTER):


acific		
Materials	35-A South La Patera Lane P.O. Box 96 Goleta, CA 93116 Ph: (805) 964-6901	Santa Ynez Ph: (805) 688-7587
Laboratory of Santa Barbara, Inc.		ml.sbcoxmail.com
	July 16, 201 Lab No: 890 File No: 10-	030-2
City of Santa Barbara c/o Coffman Engineers, Inc. Attn: Paul Van Benschoten 16133 Ventura Blvd., Suite 1010 Encino, CA 91436		
SUBJECT: Seismic Resistance Retrofit Santa Barbara Police Statio 215 East Figueroa Street Santa Barbara, California		
REFERENCE: This Laboratory's Report No	o. 47479-2, Dated October 16	5 2001
Dear Mr. Van Benschoten:		
It is my understanding you are designi retrofitting of the building at the subject site. the Police Station located at 215 East Figuer report for the District Attorney Office building	The District Attorney Office I roa Street. I have reviewed th	ouilding is adjacent to he reference soil
The soil conditions encountered at the geologic formation known as the Older Alluvia a Geotechnical viewpoint, having a Site Class Building Code.	um. The Older Alluvium is a	stable formation from
The Allowable Soil Pressure provided building footings was 2,500 psf for a footing of assumed, therefore, the Ultimate Soil Pressu estimated to be approximately 200 pci.	depth of 30 inches. A Factor	of Safety of 3 was
It is my opinion these soil values, which the District Attorney Office building, may be a building.		
If you have any questions concerning t you for the opportunity of providing this servic		sitate to call. Thank
	Respectfully submitted,	
	PACIFIC MATERIALS LAP	BORATORY, INC.
	Ronald J. Pike Geotechnical Engineer, G.	E. 2291
RJP:vlh	- Seteen Lingmool, O.	
cc: Coffman Engineers, Attn: Paul Van Be		

APPENDIX E: LDP ANALYSIS – ETABS MODEL:

MODEL1: Existing Building With Rigid Base (Pinned Base)

Assume all walls and columns are pinned at the base (as shown in the following picture).





As shown in the response spectra above, the first mode periods of existing building $T_1 \approx 0.1$ sec along Y- direction, and $T_2 \approx 0.08$ sec along X-direction, and both fall within the first part of code design response spectrum (less than T_0), which building is very rigid and unconservative design. Therefore we consider the soil – structure interaction effects for the existing building. Also see the following page for the story shear distribution and modal participating mass ratios up to 100% (total 9 modes). 2991

51%

STORY SHEAR OF EXISTING BUILDING w/ PINNED BASE (Unit: kips) Static (CODE) 2/3 MCE MCE Story $V_{\rm x}$ V_y $V_{\rm x}$ Vy $V_{\rm x}$ Vy ROOF 361 361 370 500 555 750 SECOND FL 2095 2095 2754 3212 4132 4821

4325

74%

5020

86%

6490

111%

7533

129%

51% Unit: kip-in ETABS Mass Output

2991

FIRST FL

Vbase/Wt

ETABS Mass	Output	Unit: kip-in				
Story	Diaphragm	MassX	MassY	MMI	XM	YM
ROOF	ROOF	0.9448	0.9448	195211.82	538.118	-1471.5
SECOND FL	2NDFLR	6.5607	6.5607	2893716.7	555.887	-889.258
FIRST FL	1STFLR	7.6347	7.6347	2895850.6	554.393	-886.818
-						


	ETABS Model	Hand Calc	AutoSeismic
Floor Level	Weight (kips)	Weight (kips)	Weight (kips)
ROOF	365	342	1
SECOND FL	2535	2469	
FIRST FL	2950	2987	\checkmark
Total	5850 kips	5799 kips	5845 kips
Error %	0.88%		

MODAL PARTICIPATING MASS RATIOS w/ PINNED BASE

			,es /										
Mode	Period	UX	UY	UZ	SumUX	SumUY	SumUZ	RX	RY	RZ	SumRX	SumRY	SumRZ
1	0.0997	0.30	90.36	0	0.30	90.36	0	96.44	0.18	1.69	96.44	0.18	1.69
2	0.0802	85.76	0.45	0	86.06	90.81	0	0.75	88.35	6.54	97.19	88.53	8.23
3	0.0702	4.91	0.55	0	90.97	91.36	0	1.27	10.02	78.39	98.47	98.55	86.62
4	0.0409	0.09	6.67	0	91.06	98.03	0	1.38	0.00	0.43	99.84	98.56	87.04
5	0.0337	0.21	1.68	0	91.26	99.71	0	0.01	0.00	0.01	99.85	98.56	87.05
6	0.0319	6.95	0.00	0	98.21	99.71	0	0.05	1.23	0.00	99.90	99.79	87.05
7	0.0275	0.81	0.25	0	99.02	99.96	0	0.09	0.01	10.84	99.99	99.79	97.89
8	0.0266	0.52	0.01	0	99.53	99.97	0	0.00	0.00	0.16	99.99	99.80	98.05
9	0.0229	0.47	0.03	0	100	100	0	0.01	0.20	1.95	100	100	100

MODEL1: Existing Building With Flexible Base (Soil – Structure Interaction)

Assume all walls and columns are supported by Soil Spring derived from ASCE41-06.



SOIL - STRUCTURE INTERACTION EFFECTS (Section 4.4.2.1 of ASCE41-06)

Summary Table of Soil Stiffness - Shallow Bearing Foundations

SOIL PROPERTIES: Site Class: $S_{XS}/2.5 = S_{MS}/2.5 = F_aS_5/2.5 =$ Unit weight of soil $\gamma =$	D 0.8188 110	pcf	
Shear wave velocity $v_s =$	1000	ft/sec	bottom center
Gravity Acceleration g =	32.2	ft/sec ²	
Initial shear modulus G ₀ =	23.72	ksi (Eq.4-4)	
Effective shear modulus G/G ₀ =	0.10	(Table 4-7)	
G =	2.37	ksi	
Poisson's ratio v =	0.3		

LINE SPRING STIFFNESS (See the calc detail in Appendix)

Wall		Dimension Translational Stiffness (per length) Rotational Stiffness (pe				er length)			
Footing	Length	Width	Depth	K _x /L	K _y /L	K _z /L	K _{xx}	K _{yy}	K _{zz}
ID	L (ft)	B (in)	d (in)	k/in/in	k/in/in	k/in/in	k-in/rad	k-in/rad	k-in/rad
FTG34X12X29	29.00	34.0	12.0	3.56	5.40	4.03	1176545	21293617	31327774
FTG24X12X55	55.58	24.0	12.0	2.41	4.53	3.16	1325434	76430735	146465104
FTG36X12X13	13.00	36.0	12.0	5.56	7.32	5.43	620324	3679525	4791550
FTG24X12X59	59.67	24.0	12.0	2.33	4.44	3.10	1416744	90027367	174042550
FTG45X12X52	52.33	45.0	12.0	2.86	4.39	3.50	3116362	97019509	135210480
FTG24X12X23	23.67	24.0	12.0	3.66	5.95	4.11	604090	10920069	18628540
FTG45X12X21	21.08	45.0	12.0	4.50	6.05	4.75	1333754	12284881	15426134
FTG34X12X44	44.08	34.0	12.0	2.90	4.70	3.53	1738183	55295200	85805106
FTG39X12X43	43.50	39.0	12.0	3.01	4.68	3.62	2102762	58247271	84611431
FTG45X12X56	56.08	45.0	12.0	2.76	4.30	3.43	3328767	113780658	159829362
FTG36X12X32	32.92	36.0	12.0	3.38	5.16	3.90	1438140	29385695	42783378
FTG42X12X21	21.17	42.0	12.0	4.41	6.04	4.67	1205048	11897652	15354286
FTG51X12X27	27.00	51.0	12.0	4.08	5.53	4.47	2035609	23115748	28418165
FTG60X12X89	89.00	60.0	12.0	2.42	3.72	3.14	8215708	393921993	517595518

SOIL - STRUCTURE INTERACTION EFFECTS (Section 4.4.2.1 of ASCE41-06)

Summary Table of Soil Stiffness - Shallow Bearing Foundations

SOIL PROPERTIES: Site Class: $S_{XS}/2.5 = S_{MS}/2.5 = F_aS_5/2.5 =$ Unit weight of soil $\gamma =$ Shear wave velocity v _s = Gravity Acceleration g =	D 0.8188 110 1000 32.2	pcf ft/sec ft/sec ²	bottom center
Initial shear modulus G ₀ =	23.72	ksi (Eq.4-4)	
Effective shear modulus G/G ₀ =	0.10	(Table 4-7)	
G =	2.37	ksi	
Poisson's ratio v =	0.3		

POINT SPRING STIFFNESS (See the calc detail in Appendix)

Column	Dimension			Translational Stiffness			Rotational Stiffness			
Footing	Length	Width	Depth	K _x	Ky	Kz	K _{xx}	K _{yy}	K _{zz}	
ID	L (ft)	B (in)	d (in)	k/in	k/in	k/in	k-in/rad	k-in/rad	k-in/rad]
FTG1	5.75	69.0	14.0	815	815	695	966656	966656	1813523	FTG3
FTG2	7.50	90.0	18.0	987	987	890	2114649	2114649	3995782	
FTG4	7.25	86.0	18.0	961	963	861	1907984	2158319	3606973	
FTG5	8.50	86.0	18.0	1005	1036	922	2149924	2914004	4311566	
FTG6	9.50	114.0	20.0	1167	1167	1101	4012300	4012300	7623901	
FTG7	6.75	81.0	16.0	914	914	805	1535774	1535774	2895117	FTG8/18/23
FTG9	10.00	120.0	22.0	1214	1214	1161	4770913	4770913	9079194	
FTG10	12.00	144.0	26.0	1386	1386	1382	8155402	8155402	15575282	
FTG11	9.00	108.0	20.0	1124	1124	1051	3502457	3502457	6650632	
FTG12	9.00	86.0	20.0	1027	1069	956	2378202	3371172	4890097	FTG15
FTG13	9.00	84.0	20.0	1018	1065	947	2288289	3316575	4759830	
FTG14	6.50	78.0	16.0	891	891	780	1399987	1399987	2634071	FTG21
FTG16	8.00	84.0	18.0	978	1002	889	1973247	2550359	3884232	
FTG17	6.00	72.0	16.0	847	847	730	1153209	1153209	2157735	FTG24
FTG19	7.25	87.0	18.0	965	965	865	1945976	1945976	3670864	FTG20
FTG22	7.00	84.0	18.0	943	943	840	1786638	1786638	3363158	
FTG25	4.75	57.0	14.0	724	724	595	611935	611935	1128439	

A sample calculation spreadsheet for soil spring stiffness based on ASCE41-06:

SOIL - STRUCTURE INTERACTION EFFECTS (ASCE41-06) Foundation ID: FTG34X12X29 - Shallow Bearing Foundations SOIL PROPERTIES: Site Class: D S_{xs}/2.5 = S_{Ms}/2.5 = F_sS₅/2.5 = 0.8188 Unit weight of soil γ = 110 pcf bottom center Shear wave velocity v₅ = 1000 ft/sec Gravity Acceleration g = 32.2 ft/sec² Initial shear modulus Go = 23.72 ksi (Eq.4-4) Effective shear modulus G/G₀ = 0.10 (Table 4-7) G = 2.37 ksi Poisson's ratio v = 0.3 FOUNDATION DIMENSIONS: Orient axes such that L>B. If L=B, use Length L = 29.00 ft x-axis equations for both x-axis and y-axis. Width B = 34.0 in Thickness d = 12.0 in Depth D = 2.00 ft Depth to centroid h = 18.0 in TRANSLATIONAL STIFFNESS: (Figure 4-4) at surface, K_{x.sur} = 788 k/in embedment factor, $\beta_{x} =$ 1.57 at depth, K_x = 1238 k/in at surface, K_{v.sur} = 964 k/in embedment factor, $\beta_v =$ 1.95 d = height of effective sidewall at depth, K_v = 1880 k/in contact (may be less than total foundation height) at surface, K_{z.sur} = 1114 k/in h = depth to centroid of effective sidewall contact embedment factor, β, = 1.26 at depth, K, = 1402 k/in For each degree of freedom, calculate $K_{amb} = \beta K_{aur}$ ROTATIONAL STIFFNESS: (Figure 4-4) at surface, K_{xx,sur} = 558668 k-in/rad embedment factor, β_{xx} = 2.11 at depth, K_{xx} = 1176545 k-in/rad at surface, K_{vv.sur} = 16632975 k-in/rad embedment factor, β_{vv} = 1.28 at depth, K_w = 21293617 k-in/rad at surface, K_{22,sur} = 14792145 k-in/rad embedment factor, β_{zz} = 2.12 at depth, K₂₂ = 31327774 k-in/rad


SOIL - STRUCTURE INTERACTION EFFECTS (Section 4.5.1 of ASCE41-06)

Kinematic Interaction (Simplified Procedure)

Effective Foundation Size: Embedment: a = 89.00 ft e = 5.00 ft b = 144.00 ft b_==√(ab) = 113.21 ft Ratio of response spectra for base slab averaging: (RRS factor) $RRS_{bsa} = 1 - 1/14100 \times (b_e/T)^{1.2} \ge the value for T = 0.2 sec$ (Eq. 4-11) min RRS_{bsa} = 0.8574 RRS factor for embedment e: (Eq. 4-12) $RRS_e = cos(2\pi e/Tnv_s) \ge the larger of 0.453 or the RRSe value for T = 0.2 sec$ Shear wave velocity v_s = 1000 ft/sec $n = \sqrt{G/G_0} = 0.3162$ RRS_e (T=0.2) = 0.8791

Foundation Input Motion (FIM):

 $(S_a)_{FIM} = RRS_{bsa} RRS_e (S_a)_{FFM}$ $(S_a)_{FFM} = Free Field Motion spectrum$



STORY SH	IEAR OF EXISTING BUIL	DING w/ FLEXIBLE BA	SE (Unit: kips)

	Statio	c (CODE)	2/3 N	1CE	MCE		
Story	V _x	Vy	V _x	Vy	V _x	Vy	
ROOF	361	361	516	516	774	774	
SECOND FL	2095	2095	3429	3455	5146	5186	
FIRST FL	2991	2991	5883	5889	8828	8838	
Vbase/Wt	51%	51%	101%	101%	151%	151%	


ETABS Mass Output Unit: kip-in

LIADS Wass	output	onit. kip-in				
Story	Diaphragm	MassX	MassY	MMI	XM	YM
ROOF	ROOF	0.9448	0.9448	195211.82	538.118	-1471.5
SECOND FL	2NDFLR	6.5607	6.5607	2893716.7	555.887	-889.258
FIRST FL	1STFLR	7.6347	7.6347	2895850.6	554.393	-886.818

	ETABS Model	Hand Calc	AutoSeismic
Floor Level	Weight (kips)	Weight (kips)	Weight (kips)
ROOF	365	342	
SECOND FL	2535	2469	
FIRST FL	2950	2987	\checkmark
Total	5850 kips	5799 kips	5845 kips
Error %	0.88%		

MODAL PARTICIPATING MASS RATIOS w/ FLEXIBLE BASE

_				,										
Г	Mode	Period	UX	UY	UZ	SumUX	SumUY	SumUZ	RX	RY	RZ	SumRX	SumRY	SumRZ
	1	0.1688	5.75	87.99	0	5.75	87.99	0	87.43	5.54	0.01	87.43	5.54	0.01
	2	0.1589	88.30	5.62	0	94.05	93.61	0	5.54	86.28	0.87	92.97	91.82	0.88
	3	0.1372	0.75	0.06	0	94.80	93.68	0	0.12	0.24	96.75	93.09	92.06	97.63
	4	0.0530	0.00	4.82	0	94.80	98.50	0	6.20	0.00	0.27	99.29	92.06	97.90
	5	0.0472	4.44	0.00	0	99.24	98.51	0	0.00	7.67	0.04	99.29	99.73	97.94
	6	0.0396	0.02	0.00	0	99.25	98.51	0	0.26	0.00	1.57	99.55	99.73	99.51
	7	0.0365	0.00	0.28	0	99.26	98.78	0	0.16	0.00	0.08	99.72	99.73	99.59
	8	0.0277	0.01	0.01	0	99.26	98.79	0	0.00	0.00	0.00	99.72	99.74	99.59
	9	0.0240	0.01	0.00	0	99.2678	98.792	0	0.00	0.02	0.02	99.715	99.755	99.605
	10	0.022218	0.0333	1.1809	0	99.3011	99.9729	0	0.2386	0	0.09	99.954	99.755	99.694
	11	0.019283	0.6975	0.0135	0	99.9986	99.9864	0	0.0166	0.23	0.05	99.971	99.99	99.743
	12	0.016583	0.0014	0.0136	0	100	100	0	0.0294	0.01	0.26	100	100	100



For the soil-structure model, the first mode periods of existing building $T_1 \approx 0.17$ sec along Ydirection, and $T_2 \approx 0.16$ sec along X-direction, and both fall within the max design response spectrum (greater than T_0 and less than T_s), which building design is reasonable. Therefore we check the DCRs (Demand Capacity Ratios) of concrete walls by using the soil – structure interaction model.

Wall DCR CHECK (2/3 MCE @ LS)

Note: Tables list the piers and spandrels with the shear or/and flexural DCR \ge 1.0 only

For Shear Che	ck				φ =	1.0	Shear	m-factor		For Flexura	al Check		_
8" wall #4@1	3" H. ea. Face	As =	0.27	in²/ft	f'c =	2.5 ksi	IO & LS	2		8" wall #4@24" v. ea. Face			
10" wall #4@:	15" H. ea. Face	e As =	0.32	in²/ft	fy =	50 ksi	CP	3		10" wall #4	@12" v. ea	. Face	
Select	Earthquake Ha	azard Level:	2/3MCE							I	-		,
9	Select Perform	nance Level:	LS					_					
Story	PierLbl	PierLen	PierThk	A _{s existing} /ft	φVn	Vu	Shear	DesignLen	φM _n	Mu	Pu	Flexural	Flexural
		(inch)	(inch)	(in²/ft)	(kips)	(kips)	DCR	(inch)	(ft-k)	(ft-k)	(kips)	m-Factor	DCR
SECOND FL	P16	36	8	0.27	69	66	0.48	36	82	214	109	1.50	1.73
SECOND FL	P18	52	8	0.27	99	140	0.71	52	158	310	43	1.50	1.31
SECOND FL	P51	50	8	0.27	96	77	0.40	50	151	437	72	2.36	1.23
SECOND FL	P64	51	8	0.27	97	116	0.59	50	151	448	49	2.05	1.44
SECOND FL	PF7	34	8	0.27	65	61	0.47	33	73	225	93	1.50	2.05
SECOND FL	PC6	51	8	0.27	97	94	0.48	51	154	375	61	2.23	1.09
SECOND FL	PC7	42	8	0.27	80	71	0.44	42	97	271	19	2.30	1.22
SECOND FL	PE2	24	8	0.27	46	29	0.32	24	34	116	45	2.49	1.35
FIRST FL	P16	36	10	0.32	84	146	0.87	36	108	287	106	1.94	1.37
FIRST FL	P61	28	10	0.32	65	71	0.54	28	82	177	45	2.16	1.00
FIRST FL	P62	23	10	0.32	54	103	0.96	23	50	153	70	1.93	1.58
FIRST FL	P63	36	10	0.32	84	200	1.19	36	108	279	151	1.77	1.46
FIRST FL	P65	41	10	0.32	96	167	0.87	41	151	369	79	1.50	1.63
FIRST FL	P66	62	10	0.32	145	401	1.39	62	310	826	158	1.99	1.34
FIRST FL	P67	65	10	0.32	152	421	1.39	65	326	866	194	1.94	1.37
FIRST FL	P68	70	10	0.32	163	335	1.03	70	351	734	134	1.50	1.39

EXISTING CONCRETE WALL SPANDREL DCR CHECK - EXISTING BUILDING w/FLEXIBLE BASE

For Shear Check				φ = 1.0	For Flexural Check	
8" wall #4@24" V. e	a. Face As =	0.20	in²/ft	f'c = 2.5 ksi	8" wall #4@18" H. ea. Face	
10" wall #4@12"V.I	. #4@20"V.OF. =	0.32	in²/ft	fy = 50 ksi	10" wall #4@15" H. ea. Face	
Select Earth	quake Hazard Level:	2/3MCE				
Selec	Performance Level:	LS				


Story	SpandLbl	SpandHt	SpandThk	$A_{s existing}/ft$	φVn	Vu	Shear	Shear	DesignHt	φMn	Mu	Flexural	Flexural
		(inch)	(inch)	(in²/ft)	(kips)	(kips)	m-Factor	DCR	(inch)	(ft-k)	(ft-k)	m-Factor	DCR
SECOND FL	SC4	62	8	0.20	101	162	1.20	1.34	62	231	309	1.80	0.74
FIRST FL	S14	56	8	0.20	108	177	1.20	1.36	56	208	373	1.80	1.00
FIRST FL	S66	82	8	0.20	151	204	1.20	1.13	82	358	1725	1.80	2.68
FIRST FL	SF1	33	10	0.32	77	101	1.20	1.10	33	98	151	1.80	0.86
FIRST FL	SF2	33	10	0.32	77	172	1.20	1.87	33	98	185	1.80	1.05
FIRST FL	SF3	33	10	0.32	77	144	1.20	1.56	33	98	214	1.80	1.22
FIRST FL	SF4	33	10	0.32	77	146	1.20	1.58	33	98	213	1.80	1.21
FIRST FL	SA5	24	10	0.32	56	65	1.44	0.81	24	53	118	2.12	1.04
BASE	S14	70	10	0.32	163	265	1.20	1.35	70	304	452	1.80	0.82
BASE	S15	70	10	0.32	163	353	1.20	1.80	70	304	839	1.80	1.53
BASE	S64	58	10	0.32	135	191	1.20	1.18	58	216	1015	1.80	2.62
BASE	S65	44	10	0.32	103	119	1.46	0.79	44	132	208	2.14	0.74
BASE	S66	58	10	0.32	135	178	1.20	1.10	58	216	1038	1.80	2.68
BASE	S67	44	10	0.32	103	139	1.20	1.13	44	132	484	1.80	2.03
BASE	S68	44	10	0.32	103	154	1.20	1.25	44	132	545	1.80	2.29
BASE	SA5	48	10	0.32	112	146	1.20	1.09	48	178	720	1.80	2.25














Wall DCR CHECK (MCE @ CP)

Note: Tables list the piers and spandrels with the shear or/and flexural DCR \ge 1.0 only

EXISTING CONCRETE WALL PIER DCR CHECK - EXISTING BUILDING w/ FLEXIBLE BASE

For Shear Ch	eck				φ =	1.0	Shear	m-factor		For Flexura	al Check		
8" wall #4@1	.8" H. ea. Face	As =	0.27	in²/ft	f'c =	2.5 ksi	10 & LS	2		8" wall #4@	@24" v. ea.	Face	
10" wall #4@	15" H. ea. Fac	e As =	0.32	in²/ft	fy =	50 ksi	CP	3		10" wall #4	@12" v. ea	. Face	
Select	Earthquake H	lazard Level:	MCE										
	Select Perform	mance Level:	СР					-					
Story	PierLbl	PierLen	PierThk	A _{s existing} /ft	φV _n	Vu	Shear	DesignLen	φMn	Mu	Pu	Flexural	Flexural
		(inch)	(inch)	(in ² /ft)	(kips)	(kips)	DCR	(inch)	(ft-k)	(ft-k)	(kips)	m-Factor	DCR
SECOND FL	P15	54	8	0.27	103	142	0.46	54	163	413	98	2.00	1.26
SECOND FL	P16	36	8	0.27	69	93	0.45	36	82	305	143	2.00	1.85
SECOND FL	P17	35	8	0.27	67	104	0.52	35	80	253	87	2.38	1.33
SECOND FL	P18	52	8	0.27	99	205	0.69	52	158	452	51	2.00	1.43
SECOND FL	P19	52	8	0.27	99	176	0.59	54	163	384	44	2.00	1.18
SECOND FL	P51	50	8	0.27	96	99	0.35	50	151	543	105	1.75	2.05
SECOND FL	P64	51	8	0.27	97	173	0.59	50	151	664	72	2.00	2.20
SECOND FL	PF7	34	8	0.27	65	85	0.43	33	73	311	123	2.10	2.02
SECOND FL	PC6	51	8	0.27	97	136	0.47	51	154	537	66	2.00	1.74
SECOND FL	PC7	42	8	0.27	80	103	0.43	42	97	389	24	2.00	2.01
SECOND FL	PE2	24	8	0.27	46	36	0.26	24	34	140	49	1.75	2.32
FIRST FL	P16	36	10	0.32	84	212	0.84	36	108	413	149	2.17	1.76
FIRST FL	P61	28	10	0.32	65	105	0.53	28	82	263	54	2.00	1.60
FIRST FL	P62	23	10	0.32	54	152	0.94	23	50	228	87	2.24	2.04
FIRST FL	P63	36	10	0.32	84	300	1.19	36	108	414	185	1.97	1.95
FIRST FL	P65	41	10	0.32	96	248	0.86	41	151	548	101	2.00	1.81
FIRST FL	P66	62	10	0.32	145	594	1.37	62	310	1220	193	2.38	1.65
FIRST FL	P67	65	10	0.32	152	629	1.38	65	326	1289	230	2.29	1.73
FIRST FL	P68	70	10	0.32	163	486	0.99	70	351	1065	158	2.00	1.52
FIRST FL	PG3	34	10	0.32	79	59	0.25	34	101	236	103	1.75	1.33

EXISTING CONCRETE WALL SPANDREL DCR CHECK - EXISTING BUILDING w/FLEXIBLE BASE

For Shear Check			$\phi = 1.0$	For
8" wall #4@24" V. ea. Face As =	0.20	in²/ft	f'c = 2.5 ksi	8"
10" wall #4@12"V.IF. #4@20"V.OF. =	0.32	in²/ft	fy = 50 ksi	10'
Select Earthquake Hazard Level:	MCE			


For Flexural Check
8" wall #4@18" H. ea. Face
10" wall #4@15" H. ea. Face

	Select Perfor		СР										
Story	SpandLbl	SpandHt	SpandThk	A _{s existing} /ft	φVn	Vu	Shear	Shear	DesignHt	φMn	Mu	Flexural	Flexural
		(inch)	(inch)	(in²/ft)	(kips)	(kips)	m-Factor	DCR	(inch)	(ft-k)	(ft-k)	m-Factor	DCR
SECOND FL	S65	206	8	0.20	336	541	1.50	1.07	206	1757	1335	2.50	0.30
SECOND FL	S66	86	8	0.20	140	178	1.91	0.66	86	374	1534	3.18	1.29
SECOND FL	S67	206	8	0.20	336	589	1.50	1.17	206	1757	1163	2.50	0.26
SECOND FL	SF8	63	8	0.20	103	176	1.50	1.14	54	163	375	2.50	0.92
SECOND FL	SF9	63	8	0.20	103	192	1.50	1.25	54	163	291	2.50	0.71
SECOND FL	SD4	20	8	0.20	33	57	1.50	1.16	20	43	93	2.50	0.86
SECOND FL	SC4	62	8	0.20	101	226	1.50	1.49	62	231	441	2.50	0.76
SECOND FL	SC5	62	8	0.20	101	195	1.50	1.28	62	231	393	2.50	0.68
SECOND FL	SA5	98	8	0.20	160	247	1.50	1.03	90	392	468	2.50	0.48
SECOND FL	S60	54	8	0.20	88	151	1.50	1.14	54	163	420	2.50	1.03
FIRST FL	S12	56	8	0.20	91	172	1.50	1.25	54	163	314	2.50	0.77
FIRST FL	S13	32	8	0.20	52	79	1.50	1.01	24	53	134	2.50	1.00
FIRST FL	S14	56	8	0.20	108	254	1.50	1.57	56	208	536	2.50	1.03
FIRST FL	S17	44	8	0.20	72	118	1.50	1.09	44	132	418	2.50	1.26
FIRST FL	S21	64	10	0.32	149	231	1.50	1.03	64	278	169	2.50	0.24
FIRST FL	S66	82	8	0.20	151	301	1.50	1.33	82	358	2577	2.50	2.88
FIRST FL	SF1	33	10	0.32	77	142	1.50	1.23	33	98	212	2.50	0.87
FIRST FL	SF2	33	10	0.32	77	250	1.50	2.16	33	98	267	2.50	1.09
FIRST FL	SF3	33	10	0.32	77	214	1.50	1.85	33	98	317	2.50	1.30
FIRST FL	SF4	33	10	0.32	77	207	1.50	1.79	33	98	303	2.50	1.24
FIRST FL	SA5	24	10	0.32	56	94	1.50	1.12	24	53	172	2.50	1.29
FIRST FL	S60	64	8	0.20	105	208	1.50	1.33	64	239	660	2.50	1.10
BASE	S12	70	10	0.32	163	265	1.50	1.08	65	242	439	2.50	0.72
BASE	S14	70	10	0.32	163	382	1.50	1.56	70	304	653	2.50	0.86
BASE	S15	70	10	0.32	163	502	1.50	2.05	70	304	1196	2.50	1.57
BASE	S61	36	10	0.32	84	132	1.50	1.05	36	132	200	2.50	0.61
BASE	S64	58	10	0.32	135	276	1.50	1.36	58	216	1470	2.50	2.73
BASE	S65	44	10	0.32	103	175	1.50	1.13	44	132	312	2.50	0.94
BASE	S66	58	10	0.32	135	254	1.50	1.25	58	216	1515	2.50	2.81
BASE	S67	44	10	0.32	103	201	1.50	1.30	44	132	704	2.50	2.13
BASE	S68	44	10	0.32	103	223	1.50	1.45	44	132	792	2.50	2.40
BASE	SA5	48	10	0.32	112	215	1.50	1.28	48	178	1065	2.50	2.40

APPENDIX F: NSP ANALYSIS – PERFORM 3D MODEL:


In the Nonlinear Static Procedure (NSP), the model directly incorporates the non-linear loaddeformation characteristics of individual elements of the building. Finite elements in the PERFORM model have the capacity of modeling nonlinear stress-strain behavior. The structure is analyzed subject to monotonically increasing lateral loads (Push-Over) representing the inertia forces in an earthquake until a target displacement is exceeded. The target displacement is intended to represent the maximum displacement likely to be experienced during the design earthquake.


NONLINEAR STRESS-STRAIN BACKBONE CURVES




1). Inelastic Reinforcing Bar:

2). Inelastic Concrete Compression Property:








PERFORM Model Input Parameters:

$$\begin{split} K_0 &= G_c = 0.4 \; E_c/2(1+\nu) = 475 \; \text{ksi} \; ; \; \; F_u = v_n \; (\text{Varies, see the following table}); \\ D_L &= 0.75\%; \; \; D_R = 0.85\%; \; \; F_R/F_u = 0.40; \; \; D_X = 2\% \end{split}$$

Shear Stress Capacity v _n						
	(E) f _v =	50	(ksi)			
	(E) f _c ' =	2500	(psi)			
	$v_c = 2v(fc') =$	0.1000	(ksi)			
	6√(fc') =	0.3000	(ksi)			
Existing	Reinforcing					
Wall t _w (in)	(*)-Layer	As (in2)	s (in)	v _s (ksi)	v _n (ksi)	$v_n / v(f_c')$
8	(2) #4@18" (H)	0.4	18	0.1389	0.2389	4.8
8	(2) #4@24" (V)	0.4	24	0.1042	0.2042	4.1
10	(2) #4@15" (H)	0.4	15	0.1333	0.2333	4.7
10	(2) #4@14" (V)	0.4	14	0.1429	0.2429	4.9
10	#4@12" (V.I.F), #4@20" (V.O.F)	0.32	12	0.1333	0.2333	4.7

PERFORM INPUT PROPERTIES


1). Existing Rebar:



2). Existing Concrete Compression Material Property:

COMPONENT PROPERTIES						
Inelastic Elastic Cross Sects.						
Inelastic Elastic Cross Sects.	-5.00E-01					
Materials Stiength Sects Compound						
Type Inelastic Concrete Material	-1.00E+00		/			
New Choose type and name to edit an existing material.	-1.50E+00					
	-2.00E+00					
Name Existing Concrete	2.002.000		\setminus /			
📇 Purge Rename Text for filter. Filter	-2.50E+00					
Length Unit in Force Unit kip	-9.00E-03	-6.00E-03	-3.00E-03 0	3.00E-03 6.	00E-03 9.00E-03	
	Cuclic	Degradation	Upper/Lower Bo	ande		
Status Saved.		elationship	Strength Loss		ain Capacities	
Close Graph Plot Loops Save As Delete		L				
	F = st	ess. D = strain.				
Shape of Relationship Tension Strength						
© E-P-P ○ Yes		Positive	Tension Stre	esses Compressio	on Stresses	
⊂ Trilinear ⊙ No		•	FY	FY		
- Strain Capacities		tiffness, K0	FU	FU 2.5		
C Yes © No	ll ľ	Modulus, E 1425				
		Modulus, E 1425	- Tension Stra	ains Compressio	on Strains	
Strength Loss Cyclic Degradation		KH/K0 Pos =	DU DU	DU		
		KH/K0 Neg =		DX 0.00		
C YULRX		Kinko Kog -	DX	DX 10.00	•	
Upper/Lower Bounds C Yes No C YX+3						
]		Cyclic Degradation	Upper/Lower Bo	unda	
			asic Relationship	Strength Loss		train Capacities
Import Components Export Components			" "	e nongar cooo		·
Selected components of this type.						
C All components of all types.		Tensio	in Strains	Compression Strains		
- a componente en un oppet		- DL		DL 0.003		
		DR		DR 0.006		
		FB/	FU	FR/FU 0.2		
				,		


3). Existing Concrete Shear Property:



TARGET DISPLACEMENT CALCULATION (EXISTING STRUCTURE)


		ULATION	l (E	Based on a	ASCE 41-06)		
(EXISTING B	0.8						(TABLE 2.4)
							(TABLE 3-1)
-	1.2	F C -					(TABLE 3-2)
	S _{MS} =						(Eq. 1-4)
	S _{M1} =						(Eq. 1-5)
-			1.0024 ;	þ =	5.0%		(Eq. 1-3)
-	$S_{X1}/S_{XS} =$						(Eq. 1-13)
-	0.2 T _s =						(Eq. 1-12)
	390 in	Total Buildir	ng height)				
Total WT =		For Site Class	- D)				
	60 (386.4	For Site Class	s D)				
6							
Along X-Dire			le & Period T ₂ =	:	0.09232 sec		
Based on Pu	ishover Curve a	-		ling V -	coop la		
	Initial : V _i =			,	6928 k		
		1.069E-04			4.020E-04		
	К _i =	V _i /(d _i xH)=	4.8092E+04	к _е =	$V_y/(d_y xH)=$	4.4189E+04	
	⊤ _e =	T _i ν(K _i /K _e)=	0.09631 sec				(Eq. 3-13)
	S, =	1.8469					(Eq.1-8~10)
	R = S,	C _m /(V _y /W)=	1.2265				
	C1 = 1+(F	$(aT_e^2) =$	1.4069				
	C2 = 1+[(R-1)/T _e] ² /800 =	1.0069				
Target Di			= C ₀ C ₁ C ₂ S ₂ T _e ²	$g/(4\pi^2) =$	0.2850 in		(Eq. 3-14)
	Drift Ratio :		0.073%				(
Along Y-Dire	ection:	1st Mode	e & Period T ₁ =		0.10840 sec		
Based on Pu	ishover Curve a	-					
	Initial : V _i =	1499 k	Yield	ding:V _γ =	4605 k		
	d _i =	1.262E-04		d _y =	4.106E-04		
	K _i =	V _i /(d _i xH)=	3.0456E+04	К. <mark>е</mark> =	Vy/(dyxH)=	2.8757E+04	
	T _e =	T _i √(K _i /K _e)=	0.11156 sec				(Eq. 3-13)
	S, =	2.0096					(Eq.1-8~10)
	R = S,	C _m /(V _y /W)=	2.0078				
		R-1)/(aT_2) =					
	C ₂ = 1+[(R-1	-					
Target Di	splacement:		= C ₀ C ₁ C ₂ S ₂ T _e ²	$g/(4\pi^2) =$	0 7606 in		(Eq. 3-14)
Turget Di	Drift Ratio :		r	5,,,-	5.7000 m		(Ed. 0 14)

PUSHOVER CURVES (EXISTING STRUCTURE)




1). Pushover Along X-Direction

Note: In the pushover curve above, the red mark 1 indicates the wall rotation (bending) limit at LS performance; and the red mark 2 indicates the wall shear strain limit (shear) at LS performance. The curve shows that the existing wall shear fails before the target displacement and wall bending failure. See the following figure for the shear failure locations.




DEFLECTED SHAPE SHOWING ELEMENT USAGE RATIOS Structure = Existing0831 (Entire Existing Building with Pinned Base) Analysis Series = Modal Push (Push force distribution based on modal shapes) Load Case = [2] = [1] + Push +X (Modal) Reference Drift = 9.044e-4 Limit state group = Wall Shear Strain Minimum usage ratio for each color : 0.0 0.7 0.8 0.9 1

2). Pushover Along Y-Direction



Note: In the pushover curve above, the red mark 2 indicates the wall shear strain limit (shear) at LS performance. The curve shows that the existing wall shear fails before the target displacement, and the stiffness degradation of the existing structure occurs away before the target displacement since the wall piers along Grids 1, 2 and 6 lost the shear stiffness. See the following figure for the shear failure locations.



DEFLECTED SHAPE SHOWING ELEMENT USAGE RATIOS Structure = Existing0831 (Entire Existing Building with Pinned Base) Analysis Series = Modal Push (Push force distribution based on modal shapes) Load Case = [3] = [1] + Push +Y (Modal) Reference Drift = 0.001699 Limit state group = Wall Shear Strain

Minimum usage ratio for each color : 0.0 0.7 0.8 0.9 1

TARGET DISPLACEMENT CALCULATION (RETROFITTED STRUCTURE)

Based on the pushover analysis of the existing structure, the retrofit scheme was proposed to use the shotcrete and fiber reinforced polymers (FRP) to strengthen the existing wall piers and spandrels where were shown as shear/bending failure of the existing structure. See the proposed retrofit schematic drawings for detail. The pushover analyses were performed for two load combinations $Q_G \pm Q_E = 1.1(DL + \frac{1}{4} LL) \pm Q_E$ and $Q_G \pm Q_E = 0.9 DL \pm Q_E$; and four directions Positive/Negative X-direction and Positive/Negative Y-direction.

Retofitted Reinforcing

Shear capacity of shotcrete wall and new concrete wall:

Retofitted	Reinforcing					
Wall t _w (in)	(*)-Layer	As (in2)	s (in)	v _s (ksi)	v _n (ksi)	v _n / v (f _c ')
(E)10" wall +	(2) #4@15" (H)					
(N) 8" shotcete wall	+ (N)#6@12"	0.76	12	0.1759	0.2759	5.5
(N) 8" Wall	(N) #6@12" (H)	0.44	12	0.2750	0.4015	6.3
(N) 8" Wall	(N) f _v =	60	(ksi)			
	(N) f _c ' =	4000	(psi)			

Shear capacity of FRP wall by using Tyfo SEH51A:

Shear capacity of one layer Tyfo SEH51A = 1.74 kips per ft of wall, where efficiency factor k =0.75 for one-side bonding to a wall. Therefore, the shear capacity for 8" spandrel with vertical reinforcing of #4@24" each face can be increased to $6V(f_c') = 6V(2500)/1000 = 0.3$ ksi by applying 3 layers Tyfo SEH51A on each side of wall.

TARGET DISPLACEMENT CALCULATION (Based on ASCE 41-06) (RETROFITTED BUILDING)

C _m =	0.8				(TABLE 3-1)
C ₀ =	1.2				(TABLE 3-2)
S _{XS} =	S _{MS} =	$F_a S_s =$	2.047 g		(Eq. 1-4)
S _{X1} =	S _{M1} =	$F_v S_1 =$	1.173 g		(Eq. 1-5)
B ₁ =	4/[5.6-ln(1	.00β)] =	1.0024	β = 5%	(Eq. 1-3)
T _s =	$S_{x1}/S_{xS} =$	0.573 sec			(Eq. 1-13)
T ₀ =	0.2 T _s =	0.1146 sec			(Eq. 1-12)
H =	390 in	(Total Buildi	ng height)		
Total WT =	5751 k				
a =	60	(For Site Clas	s D)		
g =	386.4				

٦

Load Case: $Q_G \pm Q_E = 1.1(DL + \frac{1}{4}LL) \pm Q_E$

Along Positive X-Direction:	2nd Mode & Period	T ₂ =0.08763 se	ec		
Based on Pushover Curve	along X-Direction				
Initial : V _i =	2002 k	Yielding	: V _y =	7312 k	
d _i =	1.026E-04		d _y =	4.042E-04	
K _i =	$V_i/(d_i xH)=$	5.0032E+04	K _e =	$V_y/(d_y xH)=$	4.6385E+04
T _e =	$T_i V(K_i/K_e) =$	0.09101 sec			(Eq. 3-13)
	1.7903				(Eq.1-8~10)
- a	$R = S_a C_m / (V_y / W) =$	1.1265			(
	$C_1 = 1+(R-1)/(aT_e^2) =$	1.2545			
	$C_2 = 1 + [(R-1)/T_e]^2/800 =$	1.0024			
Target Displacement:	$\delta_{t,X} = C_0$	$C_1 C_2 S_a T_e^2 g / (4$	4π ²) =	0.2190 in	(Eq. 3-14)
Drift Ratio :	$\Delta_{t,X}$ =	0.056%			
Along Positive Y-Direction:	•	∫ ₁ =0.10090 se	С		
Based on Pushover Curve	along Y-Direction				
Initial : V _i =	1512 k	Yielding		7185 k	
d _i =	1.155E-04		d _y =	6.308E-04	
K _i =	$V_i/(d_i xH)=$	3.3566E+04	K _e =	$V_y/(d_y xH)=$	2.9206E+04
T _e =	$T_i v(K_i/K_e) =$	0.10817 sec			(Eq. 3-13)
S _a =	1.9735				(Eq.1-8~10)
	$R = S_a C_m / (V_y / W) =$	1.2637			
	$C_1 = 1+(R-1)/(aT_e^2) =$	1.3756			
	$C_2 = 1 + [(R-1)/T_e]^2/800 =$	1.0074			
Target Displacement:	$\delta_{t,Y} = C_0$	$C_1C_2 S_a T_e^2 g / (4$	1 π ²) =	0.3758 in	(Eq. 3-14)
Drift Ratio :	$\Delta_{t,Y}$ =	0.096%			

Load Case: $Q_G \pm Q_E = 1.1(DL + \frac{1}{4}LL) \pm Q_E$

Along Negative X-Direction:	2nd Mode & Period	T ₂ =0.08763 se	C		
Based on Pushover Curve a	long X-Direction				
Initial : V _i =	2002 k	Yielding	: V _y =	7361 k	
d _i =	1.026E-04		d _y =	3.999E-04	
K _i =	$V_i/(d_i xH)=$	5.0032E+04	K _e =	$V_y/(d_y xH)=$	4.7198E+04
T _e =	$T_i V(K_i/K_e) =$	0.09022 sec			(Eq. 3-13)
S _a =	1.7819				(Eq.1-8~10)
	$R = S_a C_m / (V_y / W) =$	1.1137			
	$C_1 = 1+(R-1)/(aT_e^2) =$	1.2328			
	$C_2 = 1 + [(R-1)/T_e]^2/800 =$	1.0020			
Target Displacement:	$\delta_{t,X} = C_0$	$C_1 C_2 S_a T_e^2 g / (4$	π ²) =	0.2104 in	(Eq. 3-14)
Drift Ratio :	$\Delta_{t,X}$ =	0.054%			
Along Negative Y-Direction:	1st Mode & Period 1	Γ ₁ =0.10090 sec	2		
Based on Pushover Curve a	long Y-Direction				
Initial : V _i =	1512 k	Yielding	: V _y =	6773 k	
d _i =	1.155E-04		d _y =	5.988E-04	
K _i =	$V_i/(d_i xH)=$	3.3566E+04	K _e =	$V_y/(d_y xH)=$	2.9002E+04
T _e =	$T_i V(K_i/K_e) =$	0.10855 sec			(Eq. 3-13)
S _a =	1.9775				(Eq.1-8~10)
	$R = S_a C_m / (V_y / W) =$	1.3433			
	$C_1 = 1+(R-1)/(aT_e^2) =$	1.4856			
	$C_2 = 1 + [(R-1)/T_e]^2/800 =$	1.0125			
Target Displacement:	$\delta_{t,Y} = C_0$	$C_1 C_2 S_a T_e^2 g / (4$	π ²) =	0.4116 in	(Eq. 3-14)
Drift Ratio :	$\Delta_{t,Y}$ =	0.106%			

Load Case: $Q_G \pm Q_E = 0.9 DL \pm Q_E$

Along Positive X-Direction:	2nd Mode & Period	T ₂ =0.08763 sec		
Based on Pushover Curve	along X-Direction			
Initial : V _i =	2012 k	Yielding : V_y =	7096 k	
d _i =	1.048E-04	d _y =	4.063E-04	
$K_i =$	V _i /(d _i xH)= 4.9227E+04	K _e =	$V_y/(d_y xH)=$	4.4782E+04
T _e =	T _i √(K _i /K _e)= 0.09188 sec			(Eq. 3-13)
S _a =	1.7995			(Eq.1-8~10)
	$R = S_a C_m / (V_y / W) =$	1.1668		
	$C_1 = 1 + (R-1)/(aT_e^2) =$	1.3292		
	$C_2 = 1 + [(R-1)/T_e]^2/800 =$	1.0041		
Target Displacement:	$\delta_{t,X} = C_0 C_1 C_2$	$S_{a} T_{e}^{2} g / (4\pi^{2}) =$	0.2381 in	(Eq. 3-14)
Drift Ratio :	$\Delta_{t,X}$ =	0.061%		
Along Positive Y-Direction:	1st Mode & Period T	- 1 =	0.10090 sec	
Along Positive Y-Direction: Based on Pushover Curve	-	- 1 =	0.10090 sec	
-	along Y-Direction	1 = Yielding : V _y =		
Based on Pushover Curve Initial : V _i =	along Y-Direction	Yielding : V _y =		
Based on Pushover Curve Initial : V _i = d _i =	along Y-Direction 1502 k	Yielding : $V_{\gamma} = d_{\gamma} =$	7204 k	2.8227E+04
Based on Pushover Curve Initial : V _i = d _i = K _i =	along Y-Direction 1502 k 1.176E-04	Yielding : $V_{\gamma} = d_{\gamma} =$	7204 k 6.544E-04	2.8227E+04 (Eq. 3-13)
Based on Pushover Curve Initial : V _i = d _i = K _i = T _e =	along Y-Direction 1502 k 1.176E-04 V _i /(d _i xH)= 3.2749E+04	Yielding : $V_{\gamma} = d_{\gamma} =$	7204 k 6.544E-04	
Based on Pushover Curve Initial : V _i = d _i = K _i = T _e =	along Y-Direction 1502 k 1.176E-04 V _i /(d _i xH)= 3.2749E+04 T _i v(K _i /K _e)= 0.10868 sec	Yielding : $V_{\gamma} = d_{\gamma} = K_e =$	7204 k 6.544E-04	(Eq. 3-13)
Based on Pushover Curve Initial : V _i = d _i = K _i = T _e =	along Y-Direction 1502 k 1.176E-04 V _i /(d _i xH)= 3.2749E+04 T _i v(K _i /K _e)= 0.10868 sec 1.9789	Yielding : $V_{\gamma} = d_{\gamma} = K_{e} =$ 1.2638	7204 k 6.544E-04	(Eq. 3-13)
Based on Pushover Curve Initial : V _i = d _i = K _i = T _e =	along Y-Direction 1502 k 1.176E-04 $V_i/(d_i xH) = 3.2749E+04$ $T_i v(K_i/K_e) = 0.10868$ sec 1.9789 $R = S_a C_m / (V_y/W) =$	Yielding : V _y = d _y = K _e = 1.2638 1.3723	7204 k 6.544E-04	(Eq. 3-13)
Based on Pushover Curve Initial : V _i = d _i = K _i = T _e =	along Y-Direction 1502 k 1.176E-04 $V_i/(d_i xH) = 3.2749E+04$ $T_i v(K_i/K_e) = 0.10868 \text{ sec}$ 1.9789 $R = S_a C_m / (V_y/W) =$ $C_1 = 1 + (R-1)/(aT_e^2) =$ $C_2 = 1 + [(R-1)/T_e]^2/800 =$	Yielding : V _y = d _y = K _e = 1.2638 1.3723	7204 k 6.544E-04 V _y /(d _y xH)=	(Eq. 3-13) (Eq.1-8~10)

Load Case: $Q_G \pm Q_E = 0.9 DL \pm Q_E$

Along Negative X-Direction:	2nd Mode & Period	Γ ₂ =0.08763 sec		
Based on Pushover Curve a	long X-Direction			
Initial : V _i =	2002 k	Yielding : V _y =	7185 k	
d _i =	1.048E-04	d _y =	3.999E-04	
K _i =	V _i /(d _i xH)= 4.8982E+04	K _e =	$V_y/(d_y xH)=$	4.6069E+04
Т _е =	T _i ν(K _i /K _e)= 0.09036 sec			(Eq. 3-13)
S _a =	1.7833			(Eq.1-8~10)
	$R = S_a C_m / (V_y / W) =$	1.1419		
	$C_1 = 1 + (R-1)/(aT_e^2) =$	1.2897		
	$C_2 = 1 + [(R-1)/T_e]^2 / 800 =$	1.0031		
Target Displacement:	$\delta_{t,X} = C_0 C_1 C_2$	$S_a T_e^2 g / (4\pi^2) =$	0.2212 in	(Eq. 3-14)
Target Displacement: Drift Ratio :			0.2212 in	(Eq. 3-14)
U .	$\Delta_{t,X} =$	$\frac{S_a T_e^2 g / (4\pi^2)}{0.057\%} =$	0.2212 in	(Eq. 3-14)
Drift Ratio :	$\Delta_{t,X}$ = 1st Mode & Period T	$\frac{S_a T_e^2 g / (4\pi^2)}{0.057\%} =$	0.2212 in	(Eq. 3-14)
Drift Ratio : Along Negative Y-Direction:	∆ _{t,X} = 1st Mode & Period T llong Y-Direction	$\frac{S_a T_e^2 g / (4\pi^2)}{0.057\%} =$		(Eq. 3-14)
Drift Ratio : Along Negative Y-Direction: Based on Pushover Curve a Initial : V _i =	∆ _{t,X} = 1st Mode & Period T llong Y-Direction	$\frac{S_a T_e^2 g / (4\pi^2)}{0.057\%} = 0.057\%$ 1 = 0.10090 sec Yielding : V _y =		(Eq. 3-14)
Drift Ratio : <u>Along Negative Y-Direction:</u> Based on Pushover Curve a Initial : V _i = d _i =	Δ _{t,X} = 1st Mode & Period T llong Y-Direction 1502 k	$\frac{S_{a} T_{e}^{2} g / (4\pi^{2}) =}{0.057\%}$ 1 = 0.10090 sec Yielding : V _y = d _y =	6576 k	
Drift Ratio : Along Negative Y-Direction: Based on Pushover Curve a Initial : V _i = d _i = K _i =	$\Delta_{t,x} =$ 1st Mode & Period T long Y-Direction 1502 k 1.198E-04 $V_i/(d_i xH) = 3.2148E+04$	$\frac{S_{a} T_{e}^{2} g / (4\pi^{2}) =}{0.057\%}$ 1 = 0.10090 sec Yielding : V _y = d _y =	6576 k 5.988E-04	2.8159E+04
Drift Ratio : Along Negative Y-Direction: Based on Pushover Curve a Initial : V _i = d _i = K _i = T _e =	Δ _{t,x} = 1st Mode & Period T long Y-Direction 1502 k 1.198E-04	$\frac{S_{a} T_{e}^{2} g / (4\pi^{2}) =}{0.057\%}$ 1 = 0.10090 sec Yielding : V _y = d _y =	6576 k 5.988E-04	

 $R = S_a C_m / (V_y / W) = 1.3780$ $C_1 = 1 + (R-1) / (a T_e^2) = 1.5420$

 $\delta_{t,Y} = C_0 C_1 C_2 S_a T_e^2 g / (4\pi^2) = 0.4210 \text{ in} \quad \text{(Eq. 3-14)}$ $\Delta_{t,Y} = \boxed{0.108\%}$


 $C_2 = 1 + [(R-1)/T_e]^2/800 = 1.0154$

Target Displacement:


Drift Ratio :

PUSHOVER CURVES (RETROFITTED STRUCTURE)

1). Pushover Along Positive X-Direction with Load Case: $Q_G \pm Q_E = 1.1(DL + \frac{1}{4}LL) \pm Q_E$ BASE SHEAR (kip)




NOTE: Red mark 1 indicates the wall rotation limit at IO performance level; Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. All limits occur after the target displacement (0.056%). See the following pictures for the locations of the first wall rotation / shear strain reaching the IO performance level after the target displacement.



Wall Shear Strain at IO Performance:

Wall Rotation at IO Performance:







NOTE: Red mark 1 indicates the wall rotation limit at IO performance level, and it occurs before the target displacement (0.054%), see the following page for the location; Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. All shear limits occur at / after the target displacement (0.054%).




NOTE: Red-marked Pier indicates the wall rotation exceeds the limit at IO performance level, and it should be saw-cut three sides of pier to turn into a non-bearing wall (see the schematic drawings – Appendix H). The right-side picture shows, the first spandrel location (Grid-F) which shear strain reaches the shear strain limit at IO performance.







NOTE: Red marks 1 and 2 indicate the wall rotation limit at IO and LS performance levels; Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. All limits occur after the target displacement (0.096%). See the following pictures for the locations of the first wall rotation / shear strain reaching the IO performance level after the target displacement.




4). Pushover Along Negative Y-Direction with Load Case: $Q_G \pm Q_E = 1.1(DL + \frac{1}{4}LL) \pm Q_E$



NOTE: Red marks 1 and 2 indicate the wall rotation limit at IO and LS performance levels; Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. All limits occur after the target displacement (0.106%). See the following pictures for the locations of the first wall rotation / shear strain reaching the IO performance level after the target displacement.




5). Pushover Along Positive X-Direction with Load Case: $Q_G \pm Q_E = 0.9 DL \pm Q_E$




NOTE: Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. All limits occur after the target displacement (0.061%).

6). Pushover Along Negative X-Direction with Load Case: $Q_G \pm Q_E = 0.9 \text{ DL} \pm Q_E$ BASE SHEAR (kip)




NOTE: Red mark 1 indicates the wall rotation limit at IO performance level; Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. Red marks 1 & 4 occur before the target displacement (0.057%), which means the structure is not able to reach the IO performance level before the target displacement (0.057%).

7). Pushover Along Positive Y-Direction with Load Case: $Q_G \pm Q_E = 0.9 DL \pm Q_E$




NOTE: Red marks 1 and 2 indicate the wall rotation limit at IO and LS performance levels; Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. All IO wall rotation limit (Red mark 1) occur before the target displacement (0.097%).


7). Pushover Along Negative Y-Direction with Load Case: $Q_G \pm Q_E = 0.9 DL \pm Q_E$



NOTE: Red mark 1 indicates the wall rotation limit at IO and LS performance levels; Red marks 4, 5 and 6 indicate the wall shear strain limit at IO, LS and CP performance levels. All limits occur after the target displacement (0.108%).


APPENDIX G: MISC CALCULATIONS:






Coffman Engineers, Inc.

COFFMAN	project	JOB NO
202788884 ALNGINEEKS	MADE BY JL	DATE PAGE OF
W/ 3×3" A	THAT FOR A 34" A THE ROD STRENLTH	WILL GOVERN
	GREATER THAN MA	,
Bar 100-De sol de ser d'array a	4 × 1.840 × /1.0 = 7.3	
USE 3/4	BOLT THEN WALL M Q 4'-0" O.L.	√ 3×3×38 Å
CROSS TIE DESIG CROSS TIE FORC TRIE WIDTH MAX	E = (920) 1230 21.75' 21-9"	$= \begin{pmatrix} 20^{k} \\ 26.8^{k} \\ 40^{k} \end{pmatrix}$
FORLE / M-FACTORS 26.8 40 / 6 1.25	$ = \begin{pmatrix} 2,5^k \\ 4,5^k \\ 32^k \end{pmatrix} = \begin{cases} A_b \\ h \\ 5 \\ 5 \\ 5 \\ 5 \\ 5 \\ 5 \\ 5 \\ 5 \\ 5$	DO'L STRENATH EXISTS N (E) CONNENTIONS IGNIFICANT STRENGTHENING REQUIRED BY INSPECTION
EXISTING FRAMI ADEQUATE TO FOR CP AND	NA PER 1/5-4 API TRANSFER CROSSTIE LS. SIGNIFICANT DONLD BE REQUIRED	FORCES FORCES RSAND





PROJECT SBPD JOB NO.
MADE BY JLD DATE PAGE OF
MADE BY JLD DATE PAGE OF


$$a_y nce = 75.95 \frac{F}{52}$$

 $a_y nce = 75.95 \frac{F}{52}$
 $a_y 23mce = 50.61 \frac{F}{52}$
 $Feasibe @ CP {75.95} 3668 scms/2 sibes = {139.3k}{9.28k}$
 $V = {3202 pli}{2134 pli}$
 $Consultant To Realineed ASD STRENGTH VALUES$
 $m_{25} = 2.5 Mp = 3.0 \frac{LRED}{ASD} = 2.0$
 $V_{ASD ReadD} = {3202}{12.01}{3.0} = {534 pli}{2134 pli}$
 $Use \frac{19}{22} Rig w 10d @ 212, 4, 12
w 2x FRAMINAL $V_a = 640 > 534 \frac{1}{24}$$

	Unit: in/sec ²								
	Story	Diaphragm	Load	UX	UY	UZ	RX	RY	RZ
	ROOF	ROOF	MCE1X03Y	682.2651	529.6275	24.3232	0.43653	0.35	0.64061
\rightarrow	ROOF	ROOF	MCE03X1Y	274.7229	911.3735	36.155	1.23162	0.133	0.29967
	ROOF	ROOF	23MCE1X03Y	454.6215	352.9125	16.2096	0.29089	0.23323	0.42686
\rightarrow	ROOF	ROOF	23MCE03X1Y	183.0592	607.2857	24.0935	0.82073	0.08863	0.19968
	SECOND FL	2NDFLR	MCE1X03Y	1105.4	492.3605	33.4344	1.12513	2.57436	0.62995
	SECOND FL	2NDFLR	MCE03X1Y	445.0248	882.1838	38.3724	2.98639	1.00637	0.29572
	SECOND FL	2NDFLR	23MCE1X03Y	736.5732	328.08	22.2802	0.74975	1.71548	0.41976
	SECOND FL	2NDFLR	23MCE03X1Y	296.5383	587.8353	25.571	1.99005	0.67061	0.19705
	FIRST FL	1STFLR	MCE1X03Y	1040.946	454.0175	92.8935	3.31057	7.94325	0.5847
	FIRST FL	1STFLR	MCE03X1Y	422.8363	832.9077	215.3212	9.30738	4.02648	0.27907
	FIRST FL	1STFLR	23MCE1X03Y	693.6252	302.5305	61.8997	2.20602	5.29311	0.38961
	FIRST FL	1STFLR	23MCE03X1Y	281.7532	555.0006	143.4812	6.20217	2.68309	0.18595


	PROJECT SBPD		
COFFMAN	PROJECT	·	JOB NO
	MADE BY JW	DATE	PAGE OF
4	_		
ANALYZE DISCONTINU	ous SHEARWALL S	SUPPORT C	ornans
MAX COMPRESSION OCC W/ No TENSION F	urs @ Column 13 Er Etabs M=1	=) 44.39 14 ^{×11}	3 K
MAX TENSION OCCURS	@ Cauma 15	= 114.85*	
W/ 157.64 "Compr	ESSIM PER ETABS	M= 69*	"
- COLUMN 13 IN ETABS		5 Coumn	15 on
THE ORIGINAL DRA	WINGS. (4) #9 BARS	# 2	@ 14" ~ c
AT 2/3 MCE CHECK			
	1	MI0= 1,29	125-1.6
ADJUST FORCES FO	1.89/{1.25} x.85	= { 166.5 }	- · ·
	"12/{ 1.05} ×.9 = {	, ,	SEE INTERACTION DIAGRAM
1.			
Due To	13 IS OK FOR LOA DISCONSTINUOUS SI	Waus	
- COLUMN IS IN ETAL THE DRIGINAL		clasma 14 c	Ś
	1" w/ (4) #7 AND	#3 TIES @1	Ч"о.с.
ADJUST FORCER FOR Pu = 157	K / (1.25 × .85 =	(107×) (84×)	SEE INTERACTION
$M_{\rm w}=69^{\mu}$	"/12/{1.25}x.9	= (4.2) = (3.3)	DIAGRAM

COFFMAN	PROJECT	JOB NO
	MADE BY JW D	ATE PAGE OF
4	N FORCES FOR MA	AND \$
	=1.25 AND \$=.9 Kx.9/1.25=83K	SEE INTERACTION DIALRAM
Cozumu Dug To	15 15 OK FOR LOAD DISCONTINUOUS SWALLS	5
CHELK TENISION		
	" (<u>50 K51</u>) . 875"-	
	NUNTH OF #9 W/ 24 (24/43.7)= 16.5K	
Assume Force	Construction (Tension	J LAP FARMRE)
Dels	$LS J = 1.0 @ I$ $6.5^{k} \times 2.0 = 132^{k}$	
O @ I o $T_a = 4 \times$	16.5"×1.0 = 66"<	< 114.9K N.G.
TENSION LAP BUT ARE ON	Splices FAIL AT J L AT LS LEVELS	TO LEVELS





11	21.99	1.71	2.38	5.642	11.763	7.686
12	-141.5	-8.62	-10.52	0	-90.206	-73.984
12	-45.92	8.7	10.61	0	89.455	73.31
	-244.9	-13.32	-10.42	0	-88.555	-113.824
13	24.56	13.46	10.47	0	88.174	112.676
15	-157.6	-13.29	-14.63	-28.577	-68.667	-34.985
	114.85	15.5	16.01	29.797	64.575	35.461
16	-156.4	-11.22	-19.81	0	-168.949	-95.541
16	-82.87	11.24	19.88	0	168.384	95.401
17	-180.6	-11.85	-20.06	0	-170.215	-100.832
17	-66.18	11.86	20.03	0	170.473	100.692

ETABS



ETABS v9.7.0 - File: 10303-SB-Police-Station-Full-Building with soil spring 07-22-2010 - July 26,2010 15:24 Plan View - FIRST FL - Elevation 120 - Kip-in Units





APPENDIX H: ESTIMATED RETROFIT COST ANALYSIS:

OPINION OF PROBABLE COST OF CONSTRUCTION FOR SEISMIC RETROFIT FOR MAIN POLICE DEPARTMENT BUILDING 215 EAST FIGUEROA STREET CITY OF SANTA BARBARA SANTA BARBARA, CA

FULL BUILDING RETROFIT

OPINION OF PROBABLE COST OF CONSTRUCTION OCTOBER 14, 2010

ENGINEERS: Coffman Engineers

16133 Ventura Blvd #1010 Encino, CA 91436 Tel: (818)285-2650 Fax: (818)285-2651

COST CONSULTANTS

Iskander Associates, Inc

600 N. Tustin Avenue #130 Santa Ana, CA 92705 Tel: (714) 544-4214 Fax: (714) 544-1206

	Iskander	Associates,	Inc
--	----------	-------------	-----

SEISMIC RETROFIT	STATUS:	PRELIMINARY
MAIN POLICE DEPT BUILDING	DATE:	5-Oct-10
215 EAST FIGUEROA STREET, SANTA BARBARA, CA	DATE REV.	14-Oct-10
FULL BUILDING RETROFIT	IAI PROJ #:	10-1950
A/E: COFFMAN ENGINEERING	GFA:	

BASIS OF THE ESTIMATE:

GENERAL:

This probable preliminary cost of construction estimate for the seismic retrofit for the Main police department building in the city of Santa Barbara is based on preliminary structural plans prepared by the design team of Coffman Engineers.

The estimate is also based on measurement of approximate quantities from the plans provided and priced in accordance with the outline specifications discussed with the design team. Where measurement was not possible reasonable allowances have been included in the estimates.

ARRANGEMENT:

It is assumed that the work will be done in phases. Therefore, allowances included for phasing in this estimate. The estimate is arranged as follows:

- 1. Estimate for the proposed seismic retrofit work as designed by the engineers.
- 2. Estimate for reworking areas impacted by the proposed seismic retrofit.

DOCUMENTS USED FOR THE ESTIMATE:

The following drawings were received from Coffman Engineers and used in developing this probable cost of construction: Progress Structural Set dated August 24, 2010: S0.1, S0.2, S1.1, S2.1, S2.2, S2.3, S2.4 S2.5, S3.1, S3.2 and S3.3 As built set of drawings dated April 4, 1959: Architectural drawings 1 through 7, and 10, Structural Drawings - S-1 through S-8.

ASSUMPTIONS:

The following assumptions were used in developing the cost estimate:

- 1 Labor wages are based on prevailing wages for normal working hours.
- 2 Material prices include all related freight, sales taxes and waste.
- 3 The estimate is based on receiving a minimum of 5 responsive bids with three sub contractor bid in each trade.
- 4 The building will remain occupied through out the construction period.
- 5 The work will be done in phases.
- 6 The phased work will be released to the contractor in timely manner
- 7 The contractor will be provided with phasing schedule.
- 8 The contractor will be provided with adequate staging space and parking for his workers.
- 9 All noise generating work will be done during off hours and weekends.
- 10 Pathway etc, on site damaged during construction will be repaired and made good
- 11 Patching and repairing of Impacted architectural and MEP disciplines are included as allowances
- 12 Hazardous material will be abated prior to demo work at impacted areas and included in the budget by the Engineer.
- 13 Allowances included for seismic restraints of equipment, pipes, ducts, conduits etc.,
- 14 Each phase will be totally cleaned after finish of work.

SEISMIC RETROFIT	STATUS:	PRELIMINARY
MAIN POLICE DEPT BUILDING	DATE:	5-Oct-10
215 EAST FIGUEROA STREET, SANTA BARBARA, CA	DATE REV.	14-Oct-10
FULL BUILDING RETROFIT	IAI PROJ #:	10-1950
A/E: COFFMAN ENGINEERING	GFA:	

EXCLUSION:

The following items are not included in the hard construction costs for each building.

- o. Hazardous material abatement by others.
- o. Professional fees.
- o. Agencies fee, if any.
- o. Construction contingencies.
- o. Escalation beyond the 4th Quarter of 2010.
- o. Demolition work other than what is in the estimate
- o. Off site work
- o. Owner's costs.
- o. Public agencies costs.
- o. Relocation of personnel to swing space
- o. All Risk Insurance
- o. Preparation of the swing spaces
- o. ADA work.
- o. Architectural work beyond what is called for on the drawings.
- o. FF&E
- o. Seismic work beyond what is shown on the plans.
- o. Electrical work , other than allowance for impacted areas by seismic retrofit work.
- o. Mechanical systems other than allowance for impacted areas by seismic retrofit work.

LIMITATIONS

Since we have no control over the cost of labor, material and equipment, or the contractor's method of carrying out the work and determining the price, or over competitive bidding or market conditions, this opinion of probable construction cost provided, is made on the basis of experience and qualifications. This opinion represents our best judgment as professional construction consultants with the Construction Industry. However, we cannot and do not guarantee that proposals, bids or the construction cost will not vary from opinions of probable cost in this estimate.

SEISMIC RETROFIT			Statu	JS:	Conceptual
MAIN POLICE DEPT BUILDING			Date):	5-Oct-10
215 EAST FIGUEROA STREET, SANTA BARBA	RA, CA		Date	Revised	14-Oct-10
FULL BUILDING RETROFIT			Proje	ect #	10-1950
A/E: COFFMAN ENGINEERING			GFA	- SF	
Item Description	Quantity	Unit		Rate	Total
Gross Floor area:					
Basement floor			sf		12,072
First Floor					12,040
Second Floor			sf		3,887
Total Gross Floor area			sf		27,999
PREPAREATORY WORK			\$	3.21	90,000
ASBESTOS ABATEMENT WORK			\$	4.52	126,500
SELECTIVE DEMOLITION			\$	1.64	46,000
STRUCTURAL			\$	15.35	429,800
SEISMIC RESTRAINTS			\$	1.50	42,000
ARCHITECTURAL			\$	11.13	311,700
ROOF			\$	2.99	83,800
IMPACTED MEP			\$	12.16	340,500
MISCELLANEOUS COSTS			\$	10.00	280,000
TOTAL DIRECT COST			\$	62.51	\$ 1,750,300
General Conditions		20.00%	\$	12.50	\$ 350,100
Contractor's Overhead & Profit or Fee		15.00%	\$	11.25	\$ 315,100
Insurance and Bond		3.00%	\$	2.59	\$ 72,500
TOTAL INCLUDING MARK-UPS					\$ 2,488,000
Phasing allowance		10.00%			\$ 248,800
DESIGN CONTINGENCY		15.00%			\$ 410,500
PROBABLE CONSTRUCTION COST OCTOBER 2010			\$	112.41	\$ 3,147,300

Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20		ls ls ls ls	Unit	Da Pro GF \$ \$ \$	ate: ate Revised oject # FA - SF Rate 45,000.00 20,000.00 10,000.00 \$5,000.00 \$10,000.00		5-Oct-10 14-Oct-10 10-1950 Total 45,000 20,000 10,000 5,000 10,000 90,000
FULL BUILDING RETROFIT A/E: COFFMAN ENGINEERING Item Description Quantit 01 PREPERATORY WORK: Barricades 1.0 Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 Old ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 1.0 Scrape ceilings 8,20 8,20 Remove Ballast from fl fixtures allow 20 20 Disposal of Contaminated material allow 8,20		ls ls ls ls	Unit	Pro GF \$ \$	oject # FA - SF Rate 45,000.00 20,000.00 10,000.00 \$5,000.00	\$ \$ \$ \$	10-1950 Total 45,000 20,000 10,000 5,000 10,000
A/E: COFFMAN ENGINEERING Item Description Quantit 01 PREPERATORY WORK: Barricades 1.0 Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		ls ls ls ls	Unit	GF \$ \$	FA - SF Rate 45,000.00 20,000.00 10,000.00 \$5,000.00	\$ \$ \$ \$	Total 45,000 20,000 10,000 5,000 10,000
Item Description Quantit 01 PREPERATORY WORK: Barricades 1.0 Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		ls ls ls ls	Unit	\$\$\$	Rate 45,000.00 20,000.00 10,000.00 \$5,000.00	\$ \$ \$ \$	45,000 20,000 10,000 5,000 10,000
01 PREPERATORY WORK: Barricades 1.0 Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		ls ls ls ls		\$	45,000.00 20,000.00 10,000.00 \$5,000.00	\$ \$ \$ \$	45,000 20,000 10,000 5,000 10,000
Barricades 1.0 Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 O2 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow 1.0 Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		Is Is Is Is		\$	20,000.00 10,000.00 \$5,000.00	\$ \$ \$ \$	20,000 10,000 5,000 10,000
Barricades 1.0 Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 O2 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow 1.0 Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		Is Is Is Is		\$	20,000.00 10,000.00 \$5,000.00	\$ \$ \$ \$	20,000 10,000 5,000 10,000
Barricades 1.0 Noise control allowance 1.0 Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 O2 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow 1.0 Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		Is Is Is Is		\$	20,000.00 10,000.00 \$5,000.00	\$ \$ \$ \$	20,000 10,000 5,000 10,000
Dust Control Allowance 1.0 Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		ls Is Is		\$	10,000.00 \$5,000.00	\$ \$ \$	10,000 5,000 10,000
Trash bins 1.0 Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 1.0 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		Is Is			\$5,000.00	\$ \$	5,000 10,000
Protect existing work during construction 1.0 TOTAL PREPARATORY WORK: 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20		Is				\$	10,000
TOTAL PREPARATORY WORK: 02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20	0 1	ls			\$10,000.00		
02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20	0 1					\$	90,000
02 ASBESTOS ABATEMENT: Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Preparatory work to abate space allow Equipment and set up and removal 1.0 Containment construction set up and removal 1.0 Scrape ceilings 8,20 Remove Ballast from fl fixtures allow 20 Disposal of Contaminated material allow 8,20	0 1			ŕ			
Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas.Preparatory work to abate space allow Equipment and set up and removal1.0Containment construction set up and removal Scrape ceilings1.0Remove Ballast from fl fixtures allow Disposal of Contaminated material allow20	0 1			¢			
Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas.Preparatory work to abate space allow Equipment and set up and removal1.0Containment construction set up and removal Scrape ceilings1.0Remove Ballast from fl fixtures allow Disposal of Contaminated material allow20	0 1			¢			
contaminated with asbestos. The following work is limited to the ceiling areas.Preparatory work to abate space allow Equipment and set up and removal1.0Containment construction set up and removal Scrape ceilings8,20Remove Ballast from fl fixtures allow20Disposal of Contaminated material allow8,20	0 1			¢			
Preparatory work to abate space allowEquipment and set up and removal1.0Containment construction set up and removal1.0Scrape ceilings8,20Remove Ballast from fl fixtures allow20Disposal of Contaminated material allow8,20	0 1			¢			
Equipment and set up and removal1.0Containment construction set up and removal1.0Scrape ceilings8,20Remove Ballast from fl fixtures allow20Disposal of Contaminated material allow8,20	0 1			۴			
Equipment and set up and removal1.0Containment construction set up and removal1.0Scrape ceilings8,20Remove Ballast from fl fixtures allow20Disposal of Contaminated material allow8,20	0 1			φ			
Containment construction set up and removal1.0Scrape ceilings8,20Remove Ballast from fl fixtures allow20Disposal of Contaminated material allow8,20				\$	40,000.00	\$	40,000
Scrape ceilings8,20Remove Ballast from fl fixtures allow20Disposal of Contaminated material allow8,20	0 9	15		\$	25,000.00	\$	25,000
Disposal of Contaminated material allow 8,20		sf		\$	2.00	\$	16,400
	0 (ea		\$	50.00	\$	10,000
Monitoring/sampling	0 :	sf		\$	2.00	\$	16,400
	1	ls		\$	5,000.00	\$	5,000
Decontaminate area	1	ls		\$	7,500.00	\$	7,500
Cover furniture and equipment during							
decontamination work. 8,20	0 :	sf		\$	0.75	\$	6,200
TOTAL ASBESTOS ABATEMENT WORK						\$	126,500
03 SELECTIVE DEMOLITION: Ceilings:							
Remove Gypsum plaster ceilings 11,460.0	0		sf	\$	1.50	\$	17,200
Remove suspended gypsum plaster clg 300.0			sf	\$	2.00	\$	600
Windows and doors	-			Ŧ		\$	-
Remove windows 2.0	0		ea	\$	150.00	\$	300
Remove overhead door 2.0			ea	\$	500.00	\$	1,000
Remove doors as required and store 1.0			ls	\$	2,500.00	\$	2,500
Roof				-			
Remove existing roof tiles. 4,110.0	0		sf	\$	2.00	\$	8,200
Remove from site 1.0	0		ls	\$	1,200.00	\$	1,200
Miscellaneous:							
Allowance for removing cabinets, lockers, etc.,							
to seismic work 1.0	0		ls	\$	10,000.00	\$	10,000
Allowance for removing misc specialties 1.0	0		ls	\$	5,000.00	\$	5,000
SUBTOTAL SELECTIVE DEMO						\$	46,000

	SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARBA FULL BUILDING RETROFIT A/E: COFFMAN ENGINEERING	RA, CA		Dat Dat Pro	tus: e: e Revised ject # A - SF		Conceptual 5-Oct-10 14-Oct-10 10-1950
ltem	Description	Quantity	Unit		Rate		Total
04	STRUCTURALSEISMIC RETROFIT WORK: Foundation work (details 11, 12, 16/S1.1)	-					
	Saw cut slab on grade	146.00	lf	\$	20.00	\$	2,900
	Breakup and remove slab on grade	550.00	sf	\$	4.00	\$	2,200
	Excavate for foundations and tie beams	41.00	су	\$	50.00	\$	2,100
	Backfill and compact	14.00	су	\$	50.00	\$	700
	Haul surplus	10.50	су	\$	20.00	\$	200
	Drill and epoxy dowel into existing concrete footing.		-				
	•	144.00	ea	\$	30.00	\$	4,300
	Roughen surfaces of existing concrete	130.00	sf	\$	5.00	\$	700
	Concrete in enlarging existing footing	46.50	су	\$	400.00	\$	18,600
	Concrete Tie beam	18.50	су	\$	400.00	\$	7,400
	Forming sides of footing	137.00	sf	\$	15.00	\$	2,100
	Forming sides of tie beam	100.00	sf	\$	20.00	\$	2,000
	Reinforcing bars in foundation	1,325.00	lb	\$	1.25	\$	1,700
	Reinforcing bars in tie beam	2,775.00	lb	\$	1.25	\$	3,500
2	Slab on Grade: Drill/ epoxy dowel into existing slab Reinforced concrete slab in patching existing slab on grade Reinforcing rebar and connector to wall Finish concrete slab to receive architectural finishes.	118.00 1,440.00 2880.00 1,440.00	ea sf Ib sf	\$ \$ \$	35.00 15.00 1.25 2.50	\$ \$ \$	4,100 21,600 3,600 3,600
3	Shotcrete Shear Wall (Detail 11/S1.1)		51			·	
	Roughen surfaces of existing concrete	380.00	sf	\$	5.00	\$	1,900
	Drill and epoxy into existing concrete wall Drill and epoxy dowel into soffit of concrete	420.00	ea	\$	30.00	\$	12,600
	beam Drill and epoxy dowel into existing concrete ftg.	92.00	ea	\$	40.00	\$	3,700
		60.00	ea	\$	30.00	\$	1,800
	Shotcrete over existing conc wall	16.10	су	\$	400.00	\$	6,400
	Rebound	1.00	ls	\$	1,000.00	\$	1,000
	Finish surface of shotcrete	650.00	sf	\$	2.50	\$	1,600
	Reinforcing bars in shotcrete wall	2,590.00	lb	\$	1.25	\$	3,200
	Block window opening with shotcrete	27.00	sf	\$	60.00	\$	1,600
4	Concrete Shear wall (Detail 12/S1.1) Roughen soffits of beam	10.00	sf	\$	5.00	\$	100
	Reinforced concrete wall	3.15	су	\$	300.00	\$	900
	Forming both sides	250.00	sf	\$	20.00	\$	5,000
	Reinforcing steel bars	500.00	lb	\$	1.25	\$	600
	Finish concrete wall	250.00	sf	\$	2.50	\$	600
	Drill/dowel/epoxy soffit of beam	16.00	ea	\$	35.00	\$	600

SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARBA FULL BUILDING RETROFIT A/E: COFFMAN ENGINEERING			Da Da Pro	te Revised oject # A - SF	Conceptual 5-Oct-10 14-Oct-10 10-1950
Item Description	Quantity	Unit		Rate	Total
5 Fiber Wrap:					
Saw cut CMU partition walls for Fiber wrap	590.00	lf	\$	20.00	\$ 11,800
Breakup and remove CMU wall	590.00	sf	\$	5.00	\$ 3,000
3 layers to Columns	1,195.00	sf	\$	45.00	\$ 53,800
3 Layers to Walls	320.00	sf	\$	45.00	\$ 14,400
6 Layers to walls	310.00	sf	\$	75.00	\$ 23,300
3 Layers to concrete floor slab	890.00	sf	\$	45.00	\$ 40,100
6 Fill Opening in 2nd Floor:					
Drill/epoxy/dowel in existing slab	80.00	ea	\$	40.00	\$ 3,200
Reinforced concrete in slab fill 6" thick	40.00	су	\$	400.00	\$ 16,000
Form soffit of slab	192.00	sf	\$	25.00	\$ 4,800
Reinforcing steel bars in slab	500.00	lb	\$	1.25	\$ 600
Finish concrete	192.00	sf	\$	2.50	\$ 500
7 Roof Seismic Work:					
Drill through concrete wall for 3/4" Dia bolt	72.00	ea	\$	50.00	\$ 3,600
3/4" Bolt with nut	72.00	ea	\$	10.50	\$ 800
HSS member	11000.00	lb	\$	5.00	\$ 55,000
WT welded to bottom of existing steel beam	46.00	lf	\$	125.00	\$ 5,800
Miscellaneous steel plates	20.00	ea	\$	500.00	\$ 10,000
Miscellaneous steel in strengthening work	1.00	ls	\$	10,000.00	\$ 10,000
New plywood sheathing 19/32"	4,110.00	sf	\$	5.00	\$ 20,600
Allowance for sistering existing members	4,110.00	sf	\$	5.00	\$ 20,600
Allowance for removing and replacing dry rot of	·				
existing sheathing (10%)	450.00	sf	\$	15.00	\$ 6,800
8 Seismic Joint:					
Saw cut wall to remove 4" strip of concrete	52.00	lf	\$	25.00	\$ 1,300
Remove concrete strip 4" wide	4.00	mh	\$	150.00	\$ 600
6" x 10.5" x 3/16 Steel plate	1.00	ea	\$	300.00	\$ 300
5/8" bolt and nut	2.00	ea	\$	15.00	\$ -
SUBTOTAL STRUCTURAL					\$ 429,800
05 SEISMIC RESTRAINTS:					
Impact area seismic restraints	27,999.00	sf	\$	1.50	\$ 42,000
SUBTOTAL SEISMIC RESTRAINTS					\$ 42,000

	SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARBAI FULL BUILDING RETROFIT A/E: COFFMAN ENGINEERING	RA, CA		Da Da Pre	ite: ite Revised oject #		Conceptual 5-Oct-10 14-Oct-10 10-1950
ltem	Description	STREET, SANTA BARBARA, CA ROFIT Date Revised Project # GFA - SF Quantity Unit Rate PACT REPAIR 300.00 sf \$ 10.00 \$ ceiling 11,460.00 sf \$ 10.00 \$ pact REPAIR 590.00 sf \$ 30.00 \$ ceiling 11,460.00 sf \$ 40,000.00 \$ cee 1.00 Is \$ 40,000.00 \$ cee 1.00 Is \$ 25,000.00 \$ ing cabinets, replacing 1.00 Is \$ 10,000.00 \$ g specialties items 1.00 Is \$ 10,000.00 \$ rectrural 4,110.00 sf \$ 15.00 \$ orane 4,110.00 sf \$ 5,000.00 \$ torane 4,110.00 sf \$ 5,000.00 \$ torane 4,110.00 sf \$ 5,000.00 \$	Total				
06	ARCHITECTURAL IMPACT REPAIR						
	New Gypsum plaster ceiling						114,600
	Ditto suspended						4,500
	Rebuild CMU Walls partitions						17,700
	Floor finishes allowance				-		40,000
	Wall finishes allowance						25,000
	Column surfaces finishes allowance						23,900
	Allowance for reinstalling removed doors	1.00	ls	\$	5,000.00	\$	5,000
	Allowance for rebuilding cabinets, replacing						
	lockers etc.,		ls	\$		\$	15,000
	Allowance for replacing specialties items	1.00	ls	\$	10,000.00	\$	10,000
	Allowance for painting	27,999.00	sf	\$	2.00	\$	56,000
	SUBTOTAL ARCHITECTURAL					¢	311,700
						Ψ	011,700
07	ROOF			•		•	
	New clay roof tile						61,700
	Waterproofing membrane						14,400
	Sheet metal work						2,700
	Modify roof drains	1.00	ls	\$	5,000.00	\$	5,000
	SUBTOTAL ROOF					\$	83,800
08	IMPACTED MEP						
	Plumbing Work allowances due to Seismic work						
	Remove and replace plumbing fixtures where						
	impacted by seismic work including modification						
	of all piping to the fixtures allow	1.00	ls	\$	50,000.00	\$	50,000
						Φ	-
	HVAC Allowances due to Seismic work impact:	1.00	1.	^	500.00		-
	Protect louvers in mechanical rooms	1.00	IS	\$	500.00	\$	500
	Route / move / and reinstall mechanical	4.00		•	~~ ~~ ~~	•	
	equipment impacted by seismic work	1.00	st	\$	80,000.00	\$	80,000
	Allow for rerouting ducts, pipes, registers etc., in						
	ceilings	1.00	sf	\$	20,000.00	\$	20,000
	Electrical Allowances due to Seismic Impact:						-
	Remove and replace lighting fixtures in	1.00	sf	\$	125.000.00		125,000
	Modify all branch circuitry for lighting fixtures				-		50,000
	Reroute electrical conduits			•			15,000
			_	÷	,	r	-,
	SUBTOTAL IMPACTED MEP					\$	340,500

SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARBARA, CA FULL BUILDING RETROFIT A/E: COFFMAN ENGINEERING			Status: Date: Date Revised Project # GFA - SF			Conceptual 5-Oct-10 14-Oct-10 10-1950	
Item Description	Quantity	Unit		Rate		Total	
09 MISCELLANEOUS COSTS							
Miscellaneous cuts and patch	27,999.00	sf	\$	1.50	\$	42,000	
Scaffolding and barricades	27,999.00	sf	\$	2.00	\$	56,000	
Patch interior pathway of construction	27,999.00	sf	\$	2.50	\$	70,000	
	07,000,00	of		2.50	\$	70,000	
Regular cleaning and final clean up	27,999.00	sf	\$	2.50	Φ	70,000	
Regular cleaning and final clean up Miscellaneous items	27,999.00 27,999.00	sf	ъ \$	2.50 1.50	Գ \$	70,000 42,000	

OPINION OF PROBABLE COST OF CONSTRUCTION FOR SEISMIC RETROFIT FOR MAIN POLICE DEPARTMENT BUILDING 215 EAST FIGUEROA STREET CITY OF SANTA BARBARA SANTA BARBARA, CA

PARTIAL BUILDING RETROFIT FROM GRID LINES 1-6 & F-H

OPINION OF PROBABLE COST OF CONSTRUCTION OCTOBER 14, 2010

ENGINEERS: Coffman Engineers

16133 Ventura Blvd #1010 Encino, CA 91436 Tel: (818)285-2650 Fax: (818)285-2651

COST CONSULTANTS

Iskander Associates, Inc

600 N. Tustin Avenue #130 Santa Ana, CA 92705 Tel: (714) 544-4214 Fax: (714) 544-1206

Iskander	Associates,	Inc
----------	-------------	-----

SEISMIC RETROFIT	STATUS:	PRELIMINARY
MAIN POLICE DEPT BUILDING	DATE:	5-Oct-10
215 EAST FIGUEROA STREET, SANTA BARBARA, CA	DATE REV.	14-Oct-10
PARTIAL BUILDING RETROFIT	IAI PROJ #:	10-1950
A/E: COFFMAN ENGINEERING	GFA:	

BASIS OF THE ESTIMATE:

GENERAL:

This probable preliminary cost of construction estimate for the seismic retrofit for the Main police department building in the city of Santa Barbara is based on preliminary structural plans prepared by the design team of Coffman Engineers.

The estimate is also based on measurement of approximate quantities from the plans provided and priced in accordance with the outline specifications discussed with the design team. Where measurement was not possible reasonable allowances have been included in the estimates. The estimate covers the south portion of the building from grid lines 1-6 and F-H.

ARRANGEMENT:

It is assumed that the work will be done in phases. Therefore, allowances included for phasing in this estimate. The estimate is arranged as follows:

- 1. Estimate for the proposed seismic retrofit work as designed by the engineers.
- 2. Estimate for reworking areas impacted by the proposed seismic retrofit.

DOCUMENTS USED FOR THE ESTIMATE:

The following drawings were received from Coffman Engineers and used in developing this probable cost of construction: Progress Structural Set dated August 24, 2010: S0.1, S0.2, S1.1, S2.1, S2.2, S2.3, S2.4 S2.5, S3.1, S3.2 and S3.3 As built set of drawings dated April 4, 1959: Architectural drawings 1 through 7, and 10, Structural Drawings - S-1 through S-8.

ASSUMPTIONS:

The following assumptions were used in developing the cost estimate:

- 1 Labor wages are based on prevailing wages for normal working hours.
- 2 Material prices include all related freight, sales taxes and waste.
- 3 The estimate is based on receiving a minimum of 5 responsive bids with three sub contractor bid in each trade.
- 4 The building will remain occupied through out the construction period.
- 5 The work will be done in phases.
- 6 The phased work will be released to the contractor in timely manner
- 7 The contractor will be provided with phasing schedule.
- 8 The contractor will be provided with adequate staging space and parking for his workers.
- 9 All noise generating work will be done during off hours and weekends.
- 10 Pathway etc, on site damaged during construction will be repaired and made good
- 11 Patching and repairing of Impacted architectural and MEP disciplines are included as allowances
- 12 Hazardous material will be abated prior to demo work at impacted areas and included in the budget by the Engineer.
- 13 Allowances included for seismic restraints of equipment, pipes, ducts, conduits etc.,
- 14 Each phase will be totally cleaned after finish of work.

SEISMIC RETROFIT	STATUS:	PRELIMINARY
MAIN POLICE DEPT BUILDING	DATE:	5-Oct-10
215 EAST FIGUEROA STREET, SANTA BARBARA, CA	DATE REV.	14-Oct-10
PARTIAL BUILDING RETROFIT	IAI PROJ #:	10-1950
A/E: COFFMAN ENGINEERING	GFA:	

EXCLUSION:

The following items are not included in the hard construction costs for each building.

- o. Hazardous material abatement by others.
- o. Professional fees.
- o. Agencies fee, if any.
- o. Construction contingencies.
- o. Escalation beyond the 4th Quarter of 2010.
- o. Demolition work other than what is in the estimate
- o. Off site work
- o. Owner's costs.
- o. Public agencies costs.
- o. Relocation of personnel to swing space
- o. All Risk Insurance
- o. Preparation of the swing spaces
- o. ADA work.
- o. Architectural work beyond what is called for on the drawings.
- o. FF&E
- o. Seismic work beyond what is shown on the plans.
- o. Electrical work , other than allowance for impacted areas by seismic retrofit work.
- o. Mechanical systems other than allowance for impacted areas by seismic retrofit work.

LIMITATIONS

Since we have no control over the cost of labor, material and equipment, or the contractor's method of carrying out the work and determining the price, or over competitive bidding or market conditions, this opinion of probable construction cost provided, is made on the basis of experience and qualifications. This opinion represents our best judgment as professional construction consultants with the Construction Industry. However, we cannot and do not guarantee that proposals, bids or the construction cost will not vary from opinions of probable cost in this estimate.

SEISMIC RETROFIT MAIN POLICE DEPT BUILDING			Statu Date			Conceptual 5-Oct-10
215 EAST FIGUEROA STREET, SANTA BARBA			2 0.10	Revised		14-Oct-10
	RA, CA		Proje			10-1950
PARTIAL BUILDING RETROFIT A/E: COFFMAN ENGINEERING			-	- SF		10-1950
Item Description	Quantity	Unit	GFA	Rate		Total
	Quantity	Unit		Nale		Total
Gross Floor area:						
Basement floor			sf			3,842
First Floor						3,842
Second Floor			sf			3,842
Total Gross Floor area			sf			11,526
			¢	7.05		00 500
PREPAREATORY WORK ASBESTOS ABATEMENT WORK			\$	7.85 5.40		90,500 62,200
SELECTIVE DEMOLITION			\$ \$	5.40 2.47		82,200 28,500
STRUCTURAL			э \$	2.47		26,500
SEISMIC RESTRAINTS			φ \$	1.50		240,300 17,300
ARCHITECTURAL			φ \$	15.02		173,100
ROOF			\$	7.27		83,800
			\$	19.10		220,100
MISCELLANEOUS COSTS			\$	10.00		115,300
			Ŷ			,
			*		•	4 007 400
TOTAL DIRECT COST		00.000/	\$	89.98	\$	1,037,100
General Conditions		20.00%	\$	17.99	\$	207,400
Contractor's Overhead & Profit or Fee		15.00%	\$ \$	16.20	\$	186,700
Insurance and Bond TOTAL INCLUDING MARK-UPS		3.00%	\$	3.72	\$ \$	42,900
		10.00%				1,474,100 147,400
Phasing allowance DESIGN CONTINGENCY		10.00%			\$ \$	243,200
PROBABLE CONSTRUCTION COST OCTOBER 2010		10.0070	S	161.78	Ψ \$	1,864,700
			Ψ		Ŧ	.,

Noise control allowance 1.00 is \$ 10,00.00 \$ 50,000.00 \$ 50,00 Dust Control Allowance 1.00 is \$ 50,000.00 \$ 30,00.00 \$ 30,00.00 \$ 30,00.00 \$ 30,00.00 \$ 30,00.00 \$ 30,00.00 \$ 30,00.00 \$ 7,50 TOTAL PREPARATORY WORK: \$ 90,50 \$ 90,50 \$ 90,50 \$ 90,50 02 ASBESTOS ABATEMENT: \$ 20,000.00 \$ 20,00 \$ 20,00 \$ 20,00 Ceilings with Acoustic spray assumed to be contaminated with absetsos. The following work is limited to the ceiling areas. Preparatory work to abate space allow \$ 20,000.00 \$ 20,00 Containment construction set up and removal 1.00 is \$ 20,000.00 \$ 20,00 Strape ceilings 3,300 sf \$ 2.00 \$ 6,61 \$ 6,61 Monitoring/sampling 1 is \$ 3,000.00 \$ 7,55 \$ 6,61 Monitoring/sampling 1 is \$ 4,000.00 \$ 4,00 \$ 6,61 Monitoring/sampling 1 is \$ 3,000.00 \$ 4,00 \$ 5,50 \$ 5,50 \$ 5,50	SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARB PARTIAL BUILDING RETROFIT A/E: COFFMAN ENGINEERING	ARA, CA			Da Da Pro	atus: te: te Revised oject # FA - SF		Conceptual 5-Oct-10 14-Oct-10 10-1950
Barricades 1.00 is \$ 20,000.00 \$ 20,0 Noise control allowance 1.00 is \$ 10,000.00 \$ 10,00 Dust Control Allowance 1.00 is \$ 30,000.00 \$ 50,000 Trash bins 1.00 is \$ 30,000.00 \$ 50,000 Protect existing work during construction 1.00 is \$ \$7,500.00 \$ 7,50 TOTAL PREPARATORY WORK: \$ 90,50 \$ 90,50 \$ 90,50 \$ 90,50 02 ASBESTOS ABATEMENT: \$ 90,50 \$ 90,50 \$ 90,50 Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. \$ 90,50 \$ 20,000.00 \$ 20,00 Cortanimate construction set up and removal 1.00 \$ 12,000.00 \$ 12,00 \$ 12,00 Corabal of Contaminated material allow 3,300 \$ \$ 2.00 \$ 6,61 \$ \$ 6,00 \$ \$ 0,00 \$ \$ 2.00 \$ \$ \$ 6,61 Remove Ballast from ff ixtures allow 1.00 \$ \$ 2.00 \$ \$ \$ \$ 0,75 \$ \$ 2.50 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	tem Description	Quantity		Unit		Rate		Total
Barricades 1.00 is \$ 20,000.00 \$ 20,0 Noise control allowance 1.00 is \$ 10,000.00 \$ 10,00 Dust Control Allowance 1.00 is \$ 30,000.00 \$ 50,000 Trash bins 1.00 is \$ 30,000.00 \$ 50,000 Protect existing work during construction 1.00 is \$ \$7,500.00 \$ 7,50 TOTAL PREPARATORY WORK: \$ 90,50 \$ 90,50 \$ 90,50 \$ 90,50 02 ASBESTOS ABATEMENT: \$ 90,50 \$ 90,50 \$ 90,50 Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. \$ 90,50 \$ 20,000.00 \$ 20,00 Cortanimate construction set up and removal 1.00 \$ 12,000.00 \$ 12,00 \$ 12,00 Corabal of Contaminated material allow 3,300 \$ \$ 2.00 \$ 6,61 \$ \$ 6,00 \$ \$ 0,00 \$ \$ 2.00 \$ \$ \$ 6,61 Remove Ballast from ff ixtures allow 1.00 \$ \$ 2.00 \$ \$ \$ \$ 0,75 \$ \$ 2.50 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$								
Barricades 1.00 is \$ 20,000.00 \$ 20,0 Noise control allowance 1.00 is \$ 10,000.00 \$ 10,00 Dust Control Allowance 1.00 is \$ 30,000.00 \$ 50,000 Trash bins 1.00 is \$ 30,000.00 \$ 50,000 Protect existing work during construction 1.00 is \$ \$7,500.00 \$ 7,50 TOTAL PREPARATORY WORK: \$ 90,50 \$ 90,50 \$ 90,50 \$ 90,50 02 ASBESTOS ABATEMENT: \$ 90,50 \$ 90,50 \$ 90,50 Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. \$ 90,50 \$ 20,000.00 \$ 20,00 Cortanimate construction set up and removal 1.00 \$ 12,000.00 \$ 12,00 \$ 12,00 Corabal of Contaminated material allow 3,300 \$ \$ 2.00 \$ 6,61 \$ \$ 6,00 \$ \$ 0,00 \$ \$ 2.00 \$ \$ \$ 6,61 Remove Ballast from ff ixtures allow 1.00 \$ \$ 2.00 \$ \$ \$ \$ 0,75 \$ \$ 2.50 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$								
Noise control allowance 1.00 is \$ 10,00.00 \$ 50,00 Dust Control Allowance 1.00 is \$ 50,000.00 \$ 50,00 Trash bins 1.00 is \$ 30,000.00 \$ 30,000.00 \$ 7,50 TotAL PREPARATORY WORK: \$ 90,50 \$ 7,50 \$ 90,50 \$ 90,50 02 ASBESTOS ABATEMENT: \$ 90,50 \$ 20,000.00 \$ 20,00 Ceilings with Acoustic spray assumed to be contaminated with abbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow \$ 20,000.00 \$ 20,00 Scrape ceilings 3,300 sf \$ 20,00 \$ 20,00 \$ 12,00 Scrape ceilings 3,300 sf \$ 20,00 \$ 6,60 \$ 7,55 Disposal of Contaminated material allow 3,300 sf \$ 2,00 \$ 6,60 Monitoring/sampling 1 Is \$ 4,000.00 \$ 4,00 Decontaminate area 1 Is \$ 4,000.00 \$ 4,00 Cover fumiture and equipment during decontamination work. 3,300 sf \$ 0,75 \$ 2,50 Calings: Re		_			•	~~ ~~ ~~	•	~~~~~
Dust Control Allowance 1.00 Is \$ 50,000.00 \$ 50,00 Trash bins 1.00 Is \$ \$3,000.00 \$ 3,00 Protect existing work during construction 1.00 Is \$ \$7,500.00 \$ 7,57 TOTAL PREPARATORY WORK: \$ 90,51 02 ASBESTOS ABATEMENT: \$ 90,51 Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. \$ 20,000.00 \$ 20,00 Preparatory work to abate space allow Equipment and set up and removal 1.00 Is \$ 20,000.00 \$ 12,000.00 Contamment construction set up and removal 1.00 Is \$ 20,000.00 \$ 12,000.00 Scrape ceilings 3,300 sf \$ 2.000 \$ 6,60 Remove Ballast from fl fixtures allow 150 ea \$ 50,000 \$ 3,00 Disposal of Contaminate area 1 is \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontaminate orea 1 is \$ 4,000.00 \$ 4,00 Collings: Remove suspended gypsum plaster clg - sf \$ 2.000 \$ 33 Rem								20,000
Trash bins 1.00 is \$3,000.00 \$3,00 Protect existing work during construction 1.00 is \$7,500.00 \$7,50 TOTAL PREPARATORY WORK: \$90,50 02 ASBESTOS ABATEMENT: \$90,50 Ceilings with Acoustic spray assumed to be contaminated with absetsos. The following work is limited to the ceiling areas. \$2,000.00 \$20,00 Preparatory work to abate space allow \$2,000.00 \$20,00 \$20,00 \$20,00 Containment construction set up and removal 1.00 Is \$2,000.00 \$20,00 Scrape ceilings 3,300 sf \$2,000 \$20,00 \$20,00 \$20,00 Scrape ceilings 150 ea \$50,000 \$12,00 \$6,61 Monitoring/sampling 1 ls \$3,000.00 \$3,00 \$3,00 Decontaminate area 1 ls \$4,000.00 \$4,00 \$4,00 Cover furniture and equipment during decontamination work. \$3,300 \$5 \$2,50 Ceilings: Remove Suspended gypsum plaster celi \$5 \$2,00 \$3 Remove doors								-
Protect existing work during construction 1.00 Is \$7,500.00 \$7,55 TOTAL PREPARATORY WORK: \$ 90,51 02 ASBESTOS ABATEMENT: \$ \$00,51 Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow \$ \$20,000.00 \$ 20,000 \$ 20,000 \$ 20,000 \$ 20,000 \$ 20,000 \$ <th< td=""><td></td><td></td><td></td><td></td><td>φ</td><td></td><td></td><td>-</td></th<>					φ			-
TOTAL PREPARATORY WORK: \$ 90,51 02 ASBESTOS ABATEMENT:			-					7,500
02 ASBESTOS ABATEMENT: Ceillings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.00 ls \$ 20,000.00 \$ 20,00 Containment construction set up and removal 1.00 ls \$ 12,000.00 \$ 12,00 Scrape ceilings 3,300 sf \$ 2.00 \$ 6,66 Remove Ballast from fl fixtures allow 150 ea \$ 50,000 \$ 7,55 Disposal of Contaminated material allow 3,300 sf \$ 2.00 \$ 6,66 Monitoring/sampling 1 ls \$ 3,000.00 \$ 3,00 Decontaminate area 1 ls \$ 3,000.00 \$ 3,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,56 Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove suspended gypsum plaster cig - sf \$ 2.00 \$ \$ \$ 2,500.00 \$ \$ Windows and doors 2.00 ea \$ 500.00 \$ \$ \$ \$ Remove windows 2.00 ea \$ 500.00 \$ \$ \$ \$ Remove doors as required and store - ea \$ 2,000 \$ \$ \$ \$ \$,200 \$ \$ \$,200 \$	Trotest existing work during construction	1.00	13			ψ1,000.00	Ψ	7,000
Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow 1.00 ls \$ 20,000.00 \$ 20,00 Containment construction set up and removal 1.00 ls \$ 20,000.00 \$ 12,00 Scrape ceilings 3.300 sf \$ 2.00 \$ 6,60 Remove Ballast from fl fixtures allow 150 ea \$ 50,000 \$ 7,55 Disposal of Contaminated material allow 3.300 sf \$ 2.00 \$ 6,60 Monitoring/sampling 1 ls \$ 3,000.00 \$ 3,00 Decontaminate area 1 ls \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,50 TOTAL ASBESTOS ABATEMENT WORK SELECTIVE DEMOLITION: Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ \$ Remove overhead door - ea \$ 500.00 \$ \$ \$ Remove overhead door - ea \$ 2,500.00 \$ \$ \$ Remove overhead door - ea \$ 2,00 \$ \$ \$ Remove existing roof tiles. 4,110.00 \$ \$ \$ 2.00 \$ \$ </td <td>TOTAL PREPARATORY WORK:</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>\$</td> <td>90,500</td>	TOTAL PREPARATORY WORK:						\$	90,500
Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow 1.00 ls \$ 20,00.00 \$ 20,00 Containment construction set up and removal 1.00 ls \$ 20,00.00 \$ 12,00 Scrape ceilings 3.300 sf \$ 2.00 \$ 6,60 Remove Ballast from fl fixtures allow 150 ea \$ 50,000 \$ 7,55 Disposal of Contaminated material allow 3.300 sf \$ 2.00 \$ 6,60 Monitoring/sampling 1 ls \$ 3,000.00 \$ 3,00 Decontaminate area 1 ls \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,50 TOTAL ASBESTOS ABATEMENT WORK SELECTIVE DEMOLITION: Ceilings: Remove suspended gypsum plaster cig - sf \$ 2.00 \$ Remove overhead doors - ea \$ 150.00 \$ 3 (200 \$ Remove overhead doors - ea \$ 2,500.00 \$ 3 (200 \$ 3 (200 \$ Remove windows 2.00 ea \$ 150.00 \$ 3 (200 \$ 3 (200 \$ 3 (200 \$ Remove verhead door - ea								
Ceilings with Acoustic spray assumed to be contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow 1.00 ls \$ 20,000.00 \$ 20,000 Containment construction set up and removal 1.00 ls \$ 12,000.00 \$ 12,000 Scrape ceilings 3,300 sf \$ 2.00 \$ 6,600 Remove Ballast from fl fixtures allow 150 ea \$ 50,000 \$ 7,550 Disposal of Contaminated material allow 3,300 sf \$ 2.00 \$ 6,600 Monitoring/sampling 1 ls \$ 3,000.00 \$ 3,000 Decontaminate area 1 ls \$ 4,000.00 \$ 4,000 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,500 Ceilings: Remove System plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove suspended gypsum plaster cig - sf \$ 2.00 \$ 500.00 \$ 300 Remove doors - ea \$ 150.00 \$ 300 Remove overhead door - ea \$ 150.00 \$ 300 Remove doors - ea \$ 2,500.00 \$ 300 Remove doors - ea \$ 2,500.00 \$ 300 Remove doors - ea \$ 2,000 \$ 300 Remove overhead door - ea \$	02 ASBESTOS ABATEMENT:							
contaminated with asbestos. The following work is limited to the ceiling areas. Preparatory work to abate space allow Equipment and set up and removal 1.00 Is \$ 20,00.00 \$ 20,00 Containment construction set up and removal 1.00 Is \$ 12,00.00 \$ 12,00 Scrape ceilings 3,300 sf \$ 20.00 \$ 6,66 Remove Ballast from fl fixtures allow 150 ea \$ 50.00 \$ 7,55 Disposal of Contaminated material allow 3,300 sf \$ 2,00 \$ 6,66 Monitoring/sampling 1 Is \$ 3,000.00 \$ 3,00 Decontaminate area 1 Is \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 2.00 \$ 2,50 OTAL ASBESTOS ABATEMENT WORK \$ 0.75 \$ 2,50 Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove suspended gypsum plaster clg - sf \$ 2.000 \$ 30 Remove windows		_						
Preparatory work to abate space allow Equipment and set up and removal 1.00 ls \$ 20,00.00 \$ 20,00 Containment construction set up and removal 1.00 ls \$ 12,000.00 \$ 12,00 Scrape ceilings 3,300 sf \$ 20,00 \$ 6,60 Remove Ballast from fl fixtures allow 150 ea \$ 50.00 \$ 7,55 Disposal of Contaminated material allow 3,300 sf \$ 2,00 \$ 6,60 Monitoring/sampling 1 ls \$ 3,000.00 \$ 3,00 Decontaminate area 1 ls \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,50 Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove windows 2.00 ea \$ 150.00 \$ 3 Remove overhead door - ea \$ 2,500.00 \$ \$ Remove existing roof tiles. 4,110.00 sf \$ 2.00 \$ \$ 2,500.00 \$ \$ Remove for site 1.00 ls \$ 5,000.00 \$ \$ 2,500.00 \$ \$ Remove existing roof tiles. 1.00 ls \$ 5,000.00 \$								
Equipment and set up and removal 1.00 Is \$ 20,000.00 \$ 20,00 Containment construction set up and removal 1.00 Is \$ 12,000.00 \$ 12,00 Scrape cellings 3,300 sf \$ 2.00 \$ 6,60 Remove Ballast from fl fixtures allow 150 ea \$ 50.00 \$ 7,55 Disposal of Contaminated material allow 3,300 sf \$ 2.00 \$ 6,60 Monitoring/sampling 1 Is \$ 3,000.00 \$ 3,00 Decontaminate area 1 Is \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,50 Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ 50.00 \$ 50.00 Windows and doors \$ \$ 2.00 ea \$ 500.00 \$ 50.00 \$ 7.52.00 \$ 50.00 \$ 5.00 Remove windows 2.00 ea \$ 150.00 \$ 33 \$ 50.00 \$ 5.00 \$ 5.00	work is limited to the ceiling areas.							
Equipment and set up and removal 1.00 Is \$ 20,000.00 \$ 20,00 Containment construction set up and removal 1.00 Is \$ 12,000.00 \$ 12,00 Scrape cellings 3,300 sf \$ 2.00 \$ 6,60 Remove Ballast from fl fixtures allow 150 ea \$ 50.00 \$ 7,55 Disposal of Contaminated material allow 3,300 sf \$ 2.00 \$ 6,60 Monitoring/sampling 1 Is \$ 3,000.00 \$ 3,00 Decontaminate area 1 Is \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,50 Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ 50.00 \$ 50.00 Windows and doors \$ \$ 2.00 ea \$ 500.00 \$ 50.00 \$ 7.52.00 \$ 50.00 \$ 5.00 Remove windows 2.00 ea \$ 150.00 \$ 33 \$ 50.00 \$ 5.00 \$ 5.00	Preparatory work to abate space allow							
Scrape ceilings 3,300 sf \$ 2.00 \$ 6,60 Remove Ballast from fl fixtures allow 150 ea \$ 50.00 \$ 7,51 Disposal of Contaminated material allow 3,300 sf \$ 2.00 \$ 6,60 Monitoring/sampling 1 ls \$ 3,000.00 \$ 3,00 Decontaminate area 1 ls \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ \$ 0.75 \$ 2,55 TOTAL ASBESTOS ABATEMENT WORK \$ 0.75 \$ \$ 2,20 \$ 62,21 Of SELECTIVE DEMOLITION: * \$ 2.00 \$ \$ 11,30 Remove Gypsum plaster ceilings 7,522.00 \$ \$ \$ 11,30 Remove suspended gypsum plaster clg - \$ \$ 2.00 \$ \$ 30 Remove overhead door - ea \$ 50.000 \$ \$ 30 Remove doors as required and store - ea \$ 2.000 \$		1.00	ls		\$	20,000.00	\$	20,000
Remove Ballast from fl fixtures allow 150 ea \$ 50.00 \$ 7,50 Disposal of Contaminated material allow 3,300 sf \$ 2.00 \$ 6,66 Monitoring/sampling 1 Is \$ 3,000.00 \$ 3,00 Decontaminate area 1 Is \$ 4,000.00 \$ 4,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,56 Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 11,30 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ Windows and doors - sf \$ 2.00 \$ 30 Remove overhead door - ea \$ 500.00 \$ 30 Remove doors as required and store - ea \$ 2.00 \$ 8,20 Remove existing roof tiles. 4,110.00 sf \$ 2.00 \$ 8,20 </td <td>Containment construction set up and removal</td> <td>1.00</td> <td>ls</td> <td></td> <td>\$</td> <td>12,000.00</td> <td>\$</td> <td>12,000</td>	Containment construction set up and removal	1.00	ls		\$	12,000.00	\$	12,000
Disposal of Contaminated material allow 3,300 sf \$ 2.00 \$ 6,6 Monitoring/sampling 1 is \$ 3,000.00 \$ 3,00 Decontaminate area 1 is \$ 3,000.00 \$ 3,00 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,50 TOTAL ASBESTOS ABATEMENT WORK \$ 62,20 OS SELECTIVE DEMOLITION: Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,31 Remove Suspended gypsum plaster clg - sf \$ 2.00 \$ \$ 11,31 Remove windows 2.00 ea \$ 150.00 \$ 33 Remove overhead door - ea \$ 2,500.00 \$ 3 Remove doors as required and store - ea \$ 2,000 \$ 8,21 Remove from site 1.00 is \$ 1,200.00 \$ 1,20		3,300	sf		\$	2.00	\$	6,600
Monitoring/sampling 1 Is \$ 3,000.00 \$ 3,00 Decontaminate area 1 Is \$ 4,000.00 \$ 4,000 Cover furniture and equipment during decontamination work. 3,300 sf \$ 0.75 \$ 2,50 TOTAL ASBESTOS ABATEMENT WORK \$ 62,20 \$ 62,20 03 SELECTIVE DEMOLITION: \$ \$ 62,20 \$ \$ 62,20 \$ \$ 11,30 \$ \$ 2,50 \$ \$ 11,30 \$ \$ 2,50 \$ \$ 2,50 \$ \$ 11,30 \$ \$ 2,50 \$ \$ 11,30 \$ \$ 2,50 \$ \$ 11,30 \$ \$ 11,31 \$ \$ 2,500 \$ \$ 11,31 \$ \$ 2,500.00 \$ \$ 3 \$ \$ 3 \$ \$ 3,00 \$ \$ \$ 3,00 \$ <td></td> <td>150</td> <td>ea</td> <td></td> <td></td> <td>50.00</td> <td>\$</td> <td>7,500</td>		150	ea			50.00	\$	7,500
Decontaminate area1 ls\$ 4,000.00\$ 4,000Cover furniture and equipment during decontamination work.3,300 sf\$ 0.75\$ 2,500TOTAL ASBESTOS ABATEMENT WORK\$ 0.75\$ 62,20Collings: Remove Gypsum plaster ceilings7,522.00sf\$ 1.50\$ 11,30Remove Gypsum plaster ceilings7,522.00sf\$ 2.00\$Windows and doors-sf\$ 2.00\$\$Remove windows2.00ea\$ 150.00\$30Remove overhead door-ea\$ 500.00\$\$Remove doors as required and store-ea\$ 2,500.00\$\$Remove from site1.00ls\$ 1,200.00\$ 1,200.00\$1,200.00\$Miscellaneous: Allowance for removing cabinets, lockers, etc., to seismic work1.00ls\$ 5,000.00\$ 5,000\$Allowance for removing misc specialties1.00ls\$ 2,500.00\$ 2,500.00\$ 2,500.00\$ 2,500.00\$ 2,500.00	•	3,300						6,600
Cover furniture and equipment during decontamination work.3,300 sf\$0.75 \$2,50TOTAL ASBESTOS ABATEMENT WORK\$62,20Collings: Remove Gypsum plaster ceilings7,522.00 sf\$1.50 \$11,30Remove Gypsum plaster ceilings Remove suspended gypsum plaster clg Windows and doors Remove overhead door-sf\$2.00 \$Remove suspended gypsum plaster clg Nindows and doors-sf\$\$3.00 \$Remove overhead door Remove overhead door-ea\$\$\$Remove doors as required and store Roof Remove from site Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$\$\$Allowance for removing misc specialties1.00Is\$\$\$\$\$Allowance for removing misc specialties1.00Is\$\$\$\$\$\$		1						3,000
decontamination work. 3,300 sf \$ 0.75 \$ 2,50 TOTAL ASBESTOS ABATEMENT WORK \$ 62,21 03 SELECTIVE DEMOLITION: \$ 62,21 Ceilings: 7,522.00 sf \$ 1.50 \$ 11,30 Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,30 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ 30 Windows and doors \$ 2.00 ea \$ 150.00 \$ 30 Remove windows 2.00 ea \$ 150.00 \$ 30 Remove overhead door - eaa \$ 2.000 \$ 30 Remove doors as required and store - eaa \$ 2.000 \$ 8.20 Remove from site 1.00 Is \$ 1.200.00 \$ 8.20 Remove from site 1.00 Is \$ 5.000.00 \$ 5.00		1	ls		\$	4,000.00	\$	4,000
TOTAL ASBESTOS ABATEMENT WORK\$ 62,24O3 SELECTIVE DEMOLITION:Ceillings: Remove Gypsum plaster ceilingsRemove Gypsum plaster ceilings7,522.00sf\$ 1.50Windows and doors\$Remove windows2.00Remove overhead door-Remove doors as required and store-Remove existing roof tiles.4,110.00Remove from site1.00Is\$ 1,200.00Miscellaneous: Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$ 5,000.00Allowance for removing misc specialties1.00Is\$ 2,500.00State1.00Is\$ 2,500.00State1.00 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>								
03 SELECTIVE DEMOLITION: Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,30 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ \$ Windows and doors \$ \$ 2.00 ea \$ 150.00 \$ 30 Remove windows 2.00 ea \$ 150.00 \$ 30 Remove overhead door - ea \$ 500.00 \$ \$ Remove doors as required and store - ea \$ 2.00 \$ \$ Remove existing roof tiles. 4,110.00 sf \$ 2.00 \$ \$ Remove from site 1.00 Is \$ 1,200.00 \$ 1,20 Miscellaneous: - - - - - \$ 5,000.00 \$ 5,00 Allowance for removing cabinets, lockers, etc., 1.00 Is \$ 5,000.00 \$ 5,00 Allowance for removing misc specialties 1.00 Is \$ <td< td=""><td>decontamination work.</td><td>3,300</td><td>st</td><td></td><td>\$</td><td>0.75</td><td>\$</td><td>2,500</td></td<>	decontamination work.	3,300	st		\$	0.75	\$	2,500
03 SELECTIVE DEMOLITION: Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,30 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ \$ Windows and doors \$ \$ 2.00 ea \$ 150.00 \$ 30 Remove windows 2.00 ea \$ 150.00 \$ 30 Remove overhead door - ea \$ 500.00 \$ \$ Remove doors as required and store - ea \$ 2.00 \$ \$ Roof \$ 8 1.00 sf \$ 2.00 \$ \$ Remove existing roof tiles. 4,110.00 sf \$ 2.00 \$ \$ \$ 2.00 \$ \$ \$ 2.00 \$ \$ \$ 2.00 \$ <td>TOTAL ASBESTOS ABATEMENT WORK</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>\$</td> <td>62,200</td>	TOTAL ASBESTOS ABATEMENT WORK						\$	62,200
Ceilings: Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,30 Remove suspended gypsum plaster clg - sf \$ 2.00 \$							•	0_,_00
Ceilings: Remove Gypsum plaster ceilings7,522.00sf\$1.50\$11,30Remove suspended gypsum plaster clg-sf\$2.00\$\$Windows and doors\$\$\$\$\$\$Remove windows2.00ea\$150.00\$30Remove overhead door-ea\$500.00\$\$Remove doors as required and store-ea\$2,500.00\$\$Roof-ea\$2.00\$\$\$Remove from site1.00Is\$1,200.00\$1,20Miscellaneous:1.00Is\$\$5,000.00\$5,00Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$\$5,000.00\$5,00Allowance for removing misc specialties1.00Is\$\$2,500.00\$2,50								
Remove Gypsum plaster ceilings 7,522.00 sf \$ 1.50 \$ 11,30 Remove suspended gypsum plaster clg - sf \$ 2.00 \$ \$ Windows and doors - sf \$ 2.00 \$ \$ \$ Remove windows 2.00 ea \$ 150.00 \$ 30 Remove overhead door - ea \$ 500.00 \$ \$ Remove doors as required and store - ea \$ 2,500.00 \$ \$ Roof - ea \$ 2.00 \$ </td <td></td> <td>_</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>		_						
Remove suspended gypsum plaster clg - sf \$ 2.00 \$ Windows and doors \$ \$ Remove windows 2.00 ea \$ 150.00 \$ \$ Remove overhead door - ea \$ 500.00 \$ \$ Remove doors as required and store - ea \$ 2,500.00 \$ \$ Remove existing roof tiles. 4,110.00 sf \$ 2.00 \$ 8,20 Remove from site 1.00 ls \$ 1,200.00 \$ 1,20 Miscellaneous: 1.00 ls \$ 5,000.00 \$ 5,00 Allowance for removing cabinets, lockers, etc., 1.00 ls \$ 2,500.00 \$ \$ 5,00 Allowance for removing misc specialties 1.00 ls \$ 2,500.00 \$ \$ 5,00	-	7 500 00		- 4	۴	4 50	¢	44.000
Windows and doors \$ Remove windows 2.00 ea \$ 150.00 \$ Remove overhead door - ea \$ 500.00 \$ Remove doors as required and store - ea \$ 2,500.00 \$ Remove doors as required and store - ea \$ 2,00 \$ Remove doors as required and store - ea \$ 2,500.00 \$ Remove doors as required and store - ea \$ 2,00 \$ Remove from site 4,110.00 sf \$ 2.00 \$ 8,20 Remove from site 1.00 Is \$ 1,200.00 \$ 1,20 Miscellaneous: - - - - \$ 5,00.00 \$ 5,00 Allowance for removing cabinets, lockers, etc., 1.00 Is \$ 5,00.00 \$ 5,00 Allowance for removing misc specialties 1.00 Is \$ 2,500.00 \$ 2,50		7,522.00						11,300
Remove windows 2.00 ea \$ 150.00 \$ 30 Remove overhead door - ea \$ 500.00 \$ 7 Remove doors as required and store - ea \$ 2,500.00 \$ 7 Remove existing roof tiles. 4,110.00 sf \$ 2.00 \$ 8,20 Remove from site 1.00 ls \$ 1,200.00 \$ 1,20 Miscellaneous: 1.00 ls \$ 5,000.00 \$ 5,00 Allowance for removing cabinets, lockers, etc., 1.00 ls \$ 5,000.00 \$ 5,00 Allowance for removing misc specialties 1.00 ls \$ 2,500.00 \$ 5,00		-		SI	Φ	2.00		-
Remove overhead door-ea\$ 500.00\$Remove doors as required and store-ea\$ 2,500.00\$Roof-ea\$ 2,500.00\$8,20Remove existing roof tiles.4,110.00sf\$ 2.00\$ 8,20Remove from site1.00Is\$ 1,200.00\$ 1,20Miscellaneous:1.00Is\$ 5,000.00\$ 5,00Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$ 5,000.00\$ 5,00Allowance for removing misc specialties1.00Is\$ 2,500.00\$ 2,500		2.00		00	¢	150.00		- 300
Remove doors as required and store-ea\$ 2,500.00\$RoofRemove existing roof tiles.4,110.00sf\$ 2.00\$ 8,20Remove from site1.00Is\$ 1,200.00\$ 1,20Miscellaneous:1.00Is\$ 5,000.00\$ 5,00Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$ 5,000.00\$ 5,00Allowance for removing misc specialties1.00Is\$ 2,500.00\$ 5,00		-						- 500
Roof Remove existing roof tiles.4,110.00sf\$ 2.00\$ 8,20Remove from site1.00Is\$ 1,200.00\$ 1,20Miscellaneous: Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$ 5,000.00\$ 5,00Allowance for removing misc specialties1.00Is\$ 2,500.00\$ 2,500		-						-
Remove existing roof tiles. 4,110.00 sf \$ 2.00 \$ 8,20 Remove from site 1.00 Is \$ 1,200.00 \$ 1,20 Miscellaneous: 1.00 Is \$ 5,000.00 \$ 5,00 Allowance for removing cabinets, lockers, etc., 1.00 Is \$ 5,000.00 \$ 5,00 Allowance for removing misc specialties 1.00 Is \$ 2,500.00 \$ 2,50	•			ou	Ŷ	2,000.00	Ψ	
Remove from site1.00Is\$ 1,200.00\$ 1,20Miscellaneous:Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$ 5,000.00\$ 5,00Allowance for removing misc specialties1.00Is\$ 2,500.00\$ 2,500		4,110.00		sf	\$	2.00	\$	8,200
Miscellaneous: Allowance for removing cabinets, lockers, etc., to seismic work1.00Is\$ 5,000.00\$ 5,00Allowance for removing misc specialties1.00Is\$ 2,500.00\$ 2,500	-							1,200
Allowance for removing cabinets, lockers, etc.,to seismic work1.00Is\$ 5,000.00\$ 5,00Allowance for removing misc specialties1.00Is\$ 2,500.00\$ 2,500				-	Ŧ	,		,
to seismic work 1.00 Is \$ 5,000.00 \$ 5,00 Allowance for removing misc specialties 1.00 Is \$ 2,500.00 \$ 2,50	Allowance for removing cabinets, lockers, etc.,							
Allowance for removing misc specialties1.00Is\$ 2,500.00\$ 2,500.00	-	1.00		ls	\$	5,000.00	\$	5,000
	Allowance for removing misc specialties							2,500
							*	00 500
	SUBTOTAL SELECTIVE DEMO						\$	28,500


	SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARBA PARTIAL BUILDING RETROFIT A/E: COFFMAN ENGINEERING	RA, CA		Dat Dat Pro	tus: e: e Revised ject # A - SF		Conceptual 5-Oct-10 14-Oct-10 10-1950
ltem	Description	Quantity	Unit		Rate		Total
	STRUCTURALSEISMIC RETROFIT WORK:	-					
1	Foundation work (details 11, 12, 16/S1.1) Saw cut slab on grade	72.00	lf	\$	20.00	\$	1,400
	Breakup and remove slab on grade	224.00	" sf	э \$	4.00	Գ \$	900
	Excavate for foundations and tie beams	34.00	су	φ \$	50.00	\$	1,700
	Backfill and compact	25.00	су	\$	50.00	\$	1,300
	Haul surplus	9.00	су	\$	20.00	\$	200
	Drill and epoxy dowel into existing concrete	0100	cy	Ŷ	20.00	Ψ	200
	footing.	58.00	ea	\$	30.00	\$	1,700
	Roughen surfaces of existing concrete	112.00	sf	\$	5.00	\$	600
	Concrete in enlarging existing footing	9.00	су	\$	400.00	\$	3,600
	Concrete Tie beam	-	су	\$	400.00	\$	-
	Forming sides of footing	114.00	sf	\$	15.00	\$	1,700
	Forming sides of tie beam	-	sf	\$	20.00	\$	-
	Reinforcing bars in foundation	1,140.00	lb	\$	1.25	\$	1,400
	Reinforcing bars in tie beam	-	lb	\$	1.25	\$	-
2	Slab on Grade:						
2		56.00		¢	35.00	\$	2 000
	Drill/ epoxy dowel into existing slab Reinforced concrete slab in patching existing	56.00	ea	\$	35.00	φ	2,000
	slab on grade	224.00	of	¢	20.00	¢	4 500
	Reinforcing rebar and connector to wall	224.00 560.00	sf Ib	\$ \$	20.00 1.25	\$ \$	4,500 700
	Finish concrete slab to receive architectural	500.00	U	φ	1.20	φ	700
	finishes.	224.00	sf	\$	2.50	\$	600
		224.00	31	Ψ	2.00	Ψ	000
3	Shotcrete Shear Wall (Detail 11/S1.1)						
Ũ	Roughen surfaces of existing concrete	616.00	sf	\$	5.00	\$	3,100
	Drill and epoxy into existing concrete wall	616.00	ea	\$	30.00	\$	18,500
	Drill and epoxy dowel into soffit of concrete			Ŧ		Ŧ	
	beam	88.00	ea	\$	40.00	\$	3,500
	Drill and epoxy dowel into existing concrete ftg.					·	,
		60.00	ea	\$	30.00	\$	1,800
	Shotcrete over existing conc wall	16.00	су	\$	400.00	\$	6,400
	Rebound	1.00	ls	\$	1,000.00	\$	1,000
	Finish surface of shotcrete	616.00	sf	\$	2.50	\$	1,500
	Reinforcing bars in shotcrete wall	2,464.00	lb	\$	1.25	\$	3,100
	Block window opening with shotcrete	54.00	sf	\$	60.00	\$	3,200
4	Fiber Wrap:						
-	Saw cut CMU partition walls for Fiber wrap	154.00	lf	\$	20.00	\$	3,100
	Breakup and remove CMU wall	154.00	sf	φ \$	5.00	\$	800
	3 layers to Columns	206.00	sf	\$	45.00	\$	9,300
	3 Layers to Walls	168.00	sf	\$	45.00	\$	7,600
	3 Layers to concrete floor slab	620.00	sf	\$	45.00	\$	27,900
		020.00	5.	Ŷ	.0.00	Ŷ	,000

	SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARBA PARTIAL BUILDING RETROFIT A/E: COFFMAN ENGINEERING	RA, CA		Da Da Pro	atus: te: te Revised oject # A - SF		Conceptual 5-Oct-10 14-Oct-10 10-1950
tem	Description	Quantity	Unit	0.	Rate		Total
	-						
5	Roof Seismic Work:						
	Drill through concrete wall for 3/4" Dia bolt	72.00	ea	\$	50.00	\$	3,600
	3/4" Bolt with nut	72.00	ea	\$	10.50	\$	800
	HSS member	11000.00	lb	\$	5.00	\$	55,000
	WT welded to bottom of existing steel beam	46.00	lf	\$	125.00	\$	5,800
	Miscellaneous steel plates	20.00	ea	\$	500.00	\$	10,000
	Miscellaneous steel in strengthening work	1.00	ls	\$	10,000.00	\$	10,000
	New plywood sheathing 19/32"	4,110.00	sf	\$	5.00	\$	20,600
	Allowance for sistering existing members	4,110.00	sf	\$	5.00	\$	20,600
	Allowance for removing and replacing dry rot of			•	. –	•	
	existing sheathing (10%)	450.00	sf	\$	15.00	\$	6,800
	SUBTOTAL STRUCTURAL					\$	246,300
05	SEISMIC RESTRAINTS: Impact area seismic restraints	11,526.00	sf	\$	1.50	\$	17,300
		11,020.00	51	Ŷ	1100	-	
	SUBTOTAL SEISMIC RESTRAINTS		51	• 		\$	
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR					\$	17,300
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling	7,522.00	sf	\$	10.00	\$	17,300
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended	7,522.00	sf sf	\$	10.00 15.00	\$ \$ \$	17,300 75,200
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions	7,522.00	sf sf sf	\$ \$ \$	10.00 15.00 30.00	\$ \$ \$ \$	17,300 75,200 4,600
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance	7,522.00 	sf sf sf sf	\$ \$ \$ \$	10.00 15.00 30.00 2.50	\$ \$ \$ \$ \$	17,300 75,200 4,600 28,800
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance	7,522.00 154.00 11,526.00 11,526.00	sf sf sf sf sf	\$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50	\$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance	7,522.00 154.00 11,526.00 11,526.00 206.00	sf sf sf sf sf sf	\$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00	\$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors	7,522.00 154.00 11,526.00 11,526.00	sf sf sf sf sf	\$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50	\$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00	sf sf sf sf sf sf	\$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc.,	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00	sf sf sf sf sf ls	\$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 10,000.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for replacing specialties items	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00	sf sf sf sf sf ls ls ls	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 10,000.00 5,000.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc.,	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00	sf sf sf sf sf ls	\$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 10,000.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for replacing specialties items	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00	sf sf sf sf sf ls ls ls	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 10,000.00 5,000.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000 10,000 5,000 23,100
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for replacing specialties items Allowance for painting	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00	sf sf sf sf sf ls ls ls	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 10,000.00 5,000.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000 10,000 5,000 23,100
06	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for replacing specialties items Allowance for painting SUBTOTAL ARCHITECTURAL ROOF	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00 11,526.00	sf sf sf sf sf ls ls sf	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 5,000.00 2.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000 10,000 5,000 23,100 173,100
	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for replacing specialties items Allowance for painting SUBTOTAL ARCHITECTURAL ROOF New clay roof tile	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00 11,526.00	sf sf sf sf ls ls sf sf	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 5,000.00 2.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000 10,000 5,000 23,100 173,100
	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for painting SUBTOTAL ARCHITECTURAL ROOF New clay roof tile Waterproofing membrane	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00 11,526.00 4,110.00	sf sf sf sf sf ls ls sf sf	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 5,000.00 2.00 10,000.00 2.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000 23,100 10,000 5,000 23,100 173,100
	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for replacing specialties items Allowance for painting SUBTOTAL ARCHITECTURAL ROOF New clay roof tile Waterproofing membrane Sheet metal work	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00 11,526.00 4,110.00 4,110.00 265.00	sf sf sf sf sf ls ls sf sf sf	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 5,000.00 2.00 10,000.00 2.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000 23,100 10,000 5,000 23,100 173,100 61,700 14,400 2,700
	SUBTOTAL SEISMIC RESTRAINTS ARCHITECTURAL IMPACT REPAIR New Gypsum plaster ceiling Ditto suspended Rebuild CMU Walls partitions Floor finishes allowance Wall finishes allowance Column surfaces finishes allowance Column surfaces finishes allowance Allowance for reinstalling removed doors Allowance for rebuilding cabinets, replacing lockers etc., Allowance for painting SUBTOTAL ARCHITECTURAL ROOF New clay roof tile Waterproofing membrane	7,522.00 154.00 11,526.00 11,526.00 206.00 1.00 1.00 1.00 11,526.00 4,110.00	sf sf sf sf sf ls ls sf sf	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	10.00 15.00 30.00 2.50 1.50 20.00 5,000.00 5,000.00 2.00 10,000.00 2.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	17,300 75,200 4,600 28,800 17,300 4,100 5,000 10,000 5,000 23,100 173,100

SEISMIC RETROFIT MAIN POLICE DEPT BUILDING 215 EAST FIGUEROA STREET, SANTA BARBA PARTIAL BUILDING RETROFIT A/E: COFFMAN ENGINEERING Item Description	ARA, CA Quantity	Project # GFA - SF				Conceptual 5-Oct-10 14-Oct-10 10-1950 Total
08 IMPACTED MEP						
08 IMPACTED MEP Plumbing Work allowances due to Seismic work	-					
Rework roof drains allow	1.00	ls	\$	10,000.00	\$ 9	10,000
HVAC Allowances due to Seismic work impact:					\$	-
Protect louvers in mechanical rooms Route / move / and reinstall mechanical	1.00	ls	\$	500.00	\$	500
equipment impacted by seismic work Allow for rerouting ducts, pipes, registers etc., in	1.00	sf	\$	80,000.00	\$	80,000
ceilings	1.00	sf	\$	15,000.00	\$	15,00 <u>0</u>
Electrical Allowances due to Seismic Impact: Remove and replace lighting fixtures in					\$	-
removed ceilings	7,522.00	sf	\$	12.50	\$	94,000
Modify all branch circuitry for lighting fixtures	7,522.00	sf	\$	2.00	\$	15,000
Reroute electrical conduits	7,522.00	sf	\$	0.75	\$	5,600
SUBTOTAL IMPACTED MEP					\$	220,100
09 MISCELLANEOUS COSTS	_					
Miscellaneous cuts and patch	11,526.00	sf	\$	1.50	\$	17,300
Scaffolding and barricades	11,526.00	sf	\$	2.00	\$	23,100
Patch interior pathway of construction	11,526.00	sf	\$	2.50	\$	28,800
Regular cleaning and final clean up	11,526.00	sf	\$	2.50	\$	28,800
Miscellaneous items	11,526.00	sf	\$	1.50	\$	17,300
SUBTOTAL MISCELLANEOUS COSTS					\$	115,300

APPENDIX I: PROPOSED RETROFIT SCHEMATIC DRAWINGS:

SANTA BARBARA POLICE STATION SEISMIC RETROFIT STUDY 215 EAST FIGUEROA ST. SANTA BARBARA, CA 93102



<u>sheet in</u>	NDEX:
S0.1 S0.2	GENERAL NOTES GENERAL NOTES
S1.1	DETAILS
S2.1 S2.2 S2.3 S2.4 S2.5	EXISTING BASEMENT RETROFIT PLAN EXISTING FIRST FLOOR RETROFIT PL EXISTING SECOND FLOOR PLAN EXISTING ROOF RETROFIT PLAN WALL ELEVATIONS
S3.1 S3.2 S3.3	BASEMENT REFLECTED CEILING DEMI FIRST FLOOR REFLECTED CEILING D SECOND FLOOR REFLECTED CEILING

LAN

OLITION PLAN EMOLITION PLAN DEMOLITION PLAN

ABBREVIATIONS

ELCALL OT ELCANTREACT EACH WAY EACH WAY EXTERIOR FRAMING, SHEAR CONNECTOR FOUNDATION FLORD LOST FLORD ACTION FLORD ACTION FACE OF CONCRETE FACE OF

STRUCTURAL I TOP TOP & GROUPE TOP & BOTTOM TOPACE & GROUPE THERADOD THICK TOPOG & PARAPET TOPAL TOPOG MALL TOPOG MALL TOPOG MALL UNFORM BULDING CODE UNAFORM STATUS VERTICAL SLOTTED HOLES WOOD WEIGHT WELDED WIRE FARIC WITH TOP

WELDED WINE FABRIC WITH WITH OUT WHERE OCCURS EXTRA STRONG (STEEL PIPE) DOUBLE EXTRA STRONG (STEEL PIPE)

TEB TEG THK THR TN TOP TOS TOW TYP UBC UNO

WP WPJ WT WWF W/ W/O WO

PT PRESERVATIVE TREATED PW PLATE WASHER R RADIUS

THE OWNER SHALL EMPLOY AN INSPECTOR TO PROVIDE INSPECTION PER ______ BUILDING CODE. ALL SPECIAL INSPECTORS SHALL BE APPROVED BY CITY OF SANTA BARBARA DEPARTMENT OF BUILDING & SAFETY.

THE STRUCTURAL CONTRACT DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE STRUCTURE IS

DESINGE TO BE A STABLE UNIT AS A COMPLETE WHOLE. IT IS THE CONTRACTOR'S RESPONSIBILITY DESING, REER TAN DO NEPCT TEMPORARY SHORES, BARCS, ETC. TO SUPPORT THE STRUCTURE AGAINST ALL ANTICIPATED LODGS INCLUDING GRAVITY, WIND AND LITEAL EARTH PRESSURE UNIT, IES COMPLETION. OBSERVATION WISTS TO THE STIE BY THE STRUCTURE. ENGINEER SHALL NOT INCLUDE, INSPECTION OF THESE WETHODS OF CONSTRUCTION. CONSTRUCTION MATERIAL, SHALL BE PLACED ON FRAMED FLOORS AND ROOFS SUCH THAT THE DESING IVER, ILCADS ARE NOT EXCEEDED.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS AND SITE CONDITIONS PRIOR TO STARTING CONSTRUCTION. RESOLVE ANY DISCREPANCY WITH COFFMAN ENGINEERS.

WORKMANSHIP AND MATERIALS SHALL COMPLY WITH 2007 CBC AND ALL OTHER APPLICABLE

NOTES AND DETAILS ON THE DRAWINGS TAKE PRECEDENCE OVER THE GENERAL STRUCTURAL NOTES AND TYPICAL DETAILS. "TYPICAL" DETAILS ARE NOT FLAGGED ON THE DRAWINGS, BUT APPLY UNLESS NOTED OTHERWISE.

APPROVED FABRICATORS SHALL BE LICENSED BY CITY OF SANTA BARBARA DEPARTMENT OF BUILDING & SAFETY.

THESE DRAWINGS REPRESENT WORK TO BE PERFORMED IN THE AREA OF SCOPE ONLY. THE ENGINEER TAKES NO RESPONSIBILITY FOR ANY OTHER PORTIONS OF THIS STRUCTURE.

ALL EXISTING CONDITIONS ASSUMED IN DETAILS MUST BE CONFIRMED IN THE FIELD PRIOR TO FABRICATION OR CONSTRUCTION. ANY DISCREPANCIES MUST BE BROUGHT TO THE ATENTION OF COFFMAN ENGINEERS BEFORE CONSTRUCTION OR FABRICATION.

ALL BOLTS INTO MASONRY ARE ASSUMED TO BE INSTALLED INTO FULLY GROUTED CELLS. IF CELLS ARE FOUND TO BE HOLLOW, DO NOT INSTALL BOLTS AND INFORM COFFMAN ENGINEERS FOR INSTRUCTIONS ON HOW TO PROCEED.

ALL DRAWINGS ARE CONSIDERED TO BE PART OF THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE DRAWINGS AND SPECIFICATIONS ANONG THE SUBCONTRACTORS FINDER TO STATE OF CONSTRUCTORS. ANY DISCREPANCIES THAT ARE FOUND SHALL BE BROUGHT TO THE ATTENTION OF CORTANN TRAVELES PROR TO STATE OF CONSTRUCTION. ANY HORE VERYORIZED IN CONTRACTOR AT HIS CONTRACTOR AT CODE REQUIREMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT HIS OWN EXPENSE AND AT NO SEPTIMENT DIE COMPRENE DE NORMER.

COORDINATION SHALL INCLUDE, BUT NOT BE LINITED TO, VERIFYING THE LOCATION AND WEIGHT OF ALL MECHANICAL AND ELECTRICAL EQUIPMENT AS WELL AS THE SIZE AND LOCATION OF ALL WECHANICAL OPENIOS IN ROOTS, ROOTS AND WALLS, UNLESS OTHERWISE NOTED ON THE BRANNICS, DO NOT PENETRATE ANY STRUCTURAL ELEVENTS SUCH AS BEAMS, OLUMAS, WALLS, SLASS, ETC. WINDOT FROM WHITEN APPROVAL OF THE STRUCTURAL REGNERE.

COORDINATION SHALL INCLUDE, BUT NOT BE LIMITED TO, DETERMINING THE LOCATION OF ALL

CONDIMINING SHALL INCODE, BUT NOT BE DIMITED TO, DELEMINING THE DOLATION OF ALL EXISTING UTILITY LINES THAT MAY INTERFERE WITH THE INSTALLION OF THE NEW STRUCTURAL ELEMENTS. THE CONTRACTOR SHALL INFORM THE OWNER IF INTERFERENCE IS ENCOUNTERED. THE OWNER WILL DETERMINE IF THE LINES ARE TO BE REMOVED OR RELOCATED.

ALL EXISTING ANALYSIS PER ASCE 41-06. ALL NEW DESIGN PER CBC 2007.

DESIGNED TO BE A STABLE UNIT AS A COMPLETED WHOLE. IT IS THE CONTRACTOR'S

CODE:

INSPECTIONS:

GENERAL:

DECULATION

COORDINATION:

2007 CBC AND ASCE 41-06.

DESIGN LIVE LOADS: ROOF LIVE LOAD ----- 20 PSF ----- 20 PSF (10 PSF SEISMIC) PARTITION LOAD

WIND:	
BASIC WIND SPEED	85 MPH
EXPOSURE	"C"
Kz	1.0
Kzt	1.0
SEISMIC:	
SITE CLASS	Τ Γ
IMPORTANCE FACTOR	1.5
OCCUPANCY CATEGORY	IV
Ss	2.047
S1	0.782
Fo	1.0
E.,	16

SNOW LOADS DO NOT APPLY TO THIS SITE. FLOOD LOADS DO NOT APPLY TO THIS SITE

FOUNDATION:

ALLOWABLE SOIL BEARING PRESSURE: 1500 PSF 24" MIN. DEPTH ULTIMATE SOIL PRESSURE = 7000 PSF CONCRETE:

CONCRETE CONSTRUCTION SHALL CONFORM WITH THE LATEST EDITION OF ACI 301, "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS" AND ACI 318, "BUILDING COORE REQUERENTS FOR REINPROCED CONCRETE," SUBMIT MIX DESINS FOR EACH CLASS OF CONCRETE. ALL LIGHTWEIGHT CONCRETE TO BE SAND LIGHTWEIGHT CONCRETE.

CONCRETE CONTAINING SUPERPLASTICIZING ADMINTURE SHALL HAVE A SLUMP NOT EXCEEDING 3", TO BE FIELD VERIFIED, PRICH TO ADDING ADMINTURE, AND NOT EXCEEDING 8" AT PLACEMENT. ADDITION OF WATER TO A MIX WITH INSUFFICENT SLUMP WILL NOT BE FEMALITED.

MECHANICALLY VIRBATE ALL CONCRETE WHEN PLACED. EXCEPT THAT SLARS ON GRADE NEED BE ABRATED ONLY AROUND UNDER-FLOOR DUCTS, ETC. CAST CLOSURE POUR AROUND COLUMN AFTER DEAD LOAD IS APPLIED.

SHOT PINS AT CURBS ANS SLAB EDGES ARE NOT ALLOWED. THE USE OF EXPANSION ANCHORS AT CURBS IS NOT ALLOWED UNLESS SPECIALLY DETAILED OR APPROVED BY SEOR. MINIMUM CONCRETE MIX DESIGN REQUIREMENTS SHALL BE AS FOLLOWS:

	28 DAY				
ITEM	STRENGTH F'c (PSI)	MAX. SIZE AGGREGATE	AIR ENTR.	Max. Slump	DENSITY
FOOTINGS/SLAB ON GRADE	3,000	1*	2%	4*	150 PC
SHOTCRETE	4,000	1*	2%	4"	150 PC

NOTE- A HIGHER GRADE OF CONCRETE MAY BE SUBSTITUTED FOR THOSE SHOWN ABOVE BUT WILL BE SUBJECT TO THE CODE REQUIREMENTS OF THE HIGHER GRADE.

CONTINUOUS INSPECTION IS REQUIRED FOR ALL CONCRETE IN EXCESS OF 3000 PSL BEFORE CONCRETE IS POURED, CHECK WITH ALL TRADES TO INSURE PROPER PLACEMENT OF ALL OPENINGS, SLEEVES, CURBS, CONDUITS, BOLTS, INSERTS, ETC. RELATING TO WORK ALL SLEEVES NOT SPECIFICALLY SHOWN ON DRAWINGS SHALL BE LOCATED BY THE TRADES INVOLVED & SHALL BE APPROVED BY STRUCTURAL ENGINEER.

DRYPACK CONCRETE SHALL BE ONE PART PORTLAND CEMENT & ONE PART SAND WITH SUFFICIENT WATER TO ALLOW A SMALL AMOUNT OF PASTE TO COME TO THE SURFACE.

CONCRETE GROUT SHALL BE NON-SHRINKING WITH SUFFICIENT WATER TO ALLOW POURING. MINIMUM ULTIMATE COMPRESSIVE STRENGTH F'C AT 28 DAYS SHALL BE 2000 PSI. MIX THAT PRODUCES LOWEST SLUMP COMPATIBLE WITH PROPER PLACEMENT SHALL BE USED (4" MAX_SLUMP_UNLESS_OTHERWISE_APPROVED_BY_STRUCTURAL_ENGINEER

REINFORCING STEEL:

DEFORMED BARS:

ASTM A615 GRADE 40 FOR #3 AND GRADE 60 FOR #4 AND LARGER. REINFORCING TO BE WELDED SHALL BE ASTM A706, GRADE 60, LOW ALLOY.

CLEAR CONCRETE COVERAGE (APPLIES UNLESS NOTED OTHERWISE): CONCRETE CAST AGAINST AND FERMANERITY EXPOSED TO EARTH FORMED CONCRETE ENTO EXPOSED TO EARTH OR WEATHER FORMED CONCRETE NOT EXPOSED TO EARTH OR WEATHER FORM TOP SUFFACE OF SLAB ON GRADE 1 1/2

WELDING: UNLESS NOTED OTHERWISE, WELDING OF REINFORCING STEEL IS PROHIBITED. WHERE WELDING IS NOTED, WELD IN ACCORDANCE WITH AWS 0.1.1 USING E90 SERIES ELECTRODES. SUBJUT MILL TEST REPORTS ON THE REINFORCING TO BE WELDED AND THE PROPOSED WELDING PROCEDURE.

LAP SPLICES IN CONCRETE:

SEE TYPICAL DETAIL FOR LAP SPLICES IN CONCRETE BEAMS, WALLS, SLABS AND FOOTINGS. (UNLESS NOTED OTHERWISE, LAP SPLICES IN CONCRETE BEAMS, WALLS, SLABS AND FOOTINGS SHALL BE CLASS TO TENSION LAP SPLICES AND LAP SPLICES IN CONCRETE COLUMING SHALL BE STANDARD COMPRESSION LAP SPLICES IN CONCRETE BE STANDARD COMPRESSION LAP SPLICES IN COMPRESSION LAP SPLICES DE SPLICES IN COMPRESSION LAP SPLICES IN COM SPLASE IN CONCRETE TO APPROVE.

PROVIDE BENT CORNER BARS TO MATCH AND LAP WITH HORIZONTAL BARS AT CORNERS HYDDLE EENI COMREK BASI TO MAICH AND LAP WITH HORICONAL, BANS AT COMINES AND INTERSECTIONS OF FOOTINGS AND MULLS. SPACING SHOWN FOR ENERFOCING BARS ARE MAXIMUM ON CENTRES. ALL BARS PER CRS SPECIFICATIONS AND HANDBOOK. DOWEL ALL VERTICAL ENFORCING TO HE FOUNDATION. CONCRETE COLUMN DOWEL DIMEDIATED SHILL BE A STANARD COMPRESSION DOWEL EMBEMBERT LIDITH ACCORDENT TO HE LATCE EDTION OF AUX 318. SCURENT VE ALL BARS IM POSITION PROR TO FLACING CONCRETE. SUPPORT SLAB REMFORCEMENT WITH CONCRETE BLOCKS OF SUPPORT CHARS. REMFORCING SHALL NOT BE SUPPORTED BY STARES DIRVEN INTO THE CRCUMO.

STRUCTURAL STEEL:

ROLLED SHAPES OTHER THAN WIDE-FLANCE SHAPES, ALL PLATES, BARS AND RODS ----- ASTM A36, Fy = 36 KSI HSS STEEL -----_____

ASTM ASOO GR. B, Fy = 46 KSI — ASTM ASOO GR. B, Fy = 46 KSI — ASTM A307 — ASTM A36 ROD STOCK OR F1554, Fy=36 — CONCRETE HILTI TZ "ESR# 1917" MASONRY HILTI KB−3 "ESR# 1385" NCHOR BOLTS -EXPANSION BOLTS -----FABRICATION AND ERECTION:

LATEST AISC AND AWS CODES APPLY. FABRICATE AND ERECT IN ACCORDANCE WITH LATEST EDITION OF ANS "SPECIFICATION FOR DESCH, FABRICATION AND ERECTION OF STRUCTURAL MEETEL FOR BUILDON'S "SPUCING OF STRUCTURAL MEMBERS IS NOT PERMITED UNLESS WOTED ON THE DRAWINGS. ALL BEAMS SHALL BE ERECTED WITH THE MATURAL CAURER UPWRADS.

ALL FABRICATORS SHALL BE LICENSED BY CITY OF LOS ANGELES. WELDING:

ALL WELDING BY CERTIFIED WELDERS HAVING CURRENT EXPERIENCE IN TYPE OF WELD SHOWN ON DRAWINGS OR NOTES. CERTIFICATES SHALL BE THOSE ISSUED BY LOBS. LA WELDING SHALL BE IN ACCORDANCE WITH THE LATEST EDTION OF ANS "CODE FOR ARCA NO GAS WELDING. IN BUILDING CONSTRUCTION". USE E70 SERIES LOW HYDROGEN LECTOROUS. SHOW BUILDING CONSTRUCTION". USE E70 SERIES LOW HYDROGEN LECTOROUS. SHOW BUILDING CONSTRUCTION". USE E70 SERIES LOW HYDROGEN LECTOROUS. SHOW BUILDING SHALL BE ENTIT AND AND CERTIFIED BY AN INDEPINION TESTING AGENCY. ALL DEFORMED BAR NACHONS, HARDED STUDS AND INFRADED STUDS SHUL BE END WELDED FER MUNICATURE'S RECOMBINIZION.

BOI TS:

ALL BOLTS, ANCHOR BOLTS, EXPANSION BOLTS, ETC., SHALL BE INSTALLED WITH STEEL WASHERS. TYPE N BOLTS PER LATEST EDITION OF ASC "SPECIFICATION. INSPECTOR OF RECORD TO VERITY RE-TOHERING OF ALL BOLTS PRIOR TO LICONIG IN. HILT BOLTS AND ANCHORS MAY BE SUBSTITUTED WITH AN APPROVED LARR RATED PRODUCT.

EPOXY ANCHOR RODS (ALL-THREAD AND REBAR);

1. EPOXY ANCHORS NOTED IN DRAWINGS ARE HILTI RE500 ANCHORS SYSTEM, OR APPROVED FOLIAL

3. MINIMUM EMBEDMENT DEPTHS AS FOLLOWS UNLESS NOTED OTHERWISE.

ALL-THREAD	EPOXY AND	HOR	ALLOWABLE/TESTING LOADS		
ROD ANCHOR SIZE (DIA.)	MINIMUM Embedment*	MIN. EDGE DIST	T ALLOWABLE LOAD(LBS) **	TESTING LOAD (LBS)	
3/8" DIA	3-1/2"	5-1/4"	1,388	2,776	
1/2" DIA	4-1/4"	6-3/8"	2,224	4,448	
5/8" DIA	5*	7-1/2"	3,900	7,800	
3/4" DIA	6-3/4*	10-1/8*	4,888	9,776	
7/8" DIA	7-3/4*	11-5/8*	4,888	9,776	
1" DIA	9"	13-1/2*	10,036	20,072	

 MIN CONCRETE THICKNESS = 1.5 MIN EMBEDMENT
 MIN CONCRETE STRENCTH = 3000 PSI (HARDROCK), ALL-THREAD ROD SHALL BE ASTM A-193 GRADE BJ ALLOWABLE TENSION LOAD = 80% OF ICC REPORT REBAR EPOXY ANCHOR ALLOWABLE/TESTING LOADS

NCHOR IZE	MINIMUM EMBEDMENT*	MIN. EDGE DIST	T ALLOWABLE LOAD(LBS) **	TESTING LOAD (LBS)
# 4	4-1/4"	6-3/8*	3,480	6,960
# 5	5*	7-1/2*	5,064	10,128
# 6	6-3/4"	10-1/8"	7,888	15,776
# 7	7-3/4*	11-5/8"	9,552	19,104

MIN CONCRETE THICKNESS = 1.5 MIN EMBEDMENT
 MIN CONCRETE STRENGTH = 3000 PSI (HARDROCK), REBAR SHALL BE ASTM A615, GRADE 60 ALLOWABLE TENSION LOAD = 80% OF ICC REPORT

3. EPOXY ANCHORS SHALL BE TESTED PER SECTION 1923A.3.5. THE TENSION TEST SHALL BE TWICE THE ALLOWABLE LOAD FOR THE SPECIFIC LOCATION.

4. THE TEST PROCEDURE FOR EXPANSION ANCHORS IN THE EXPANSION ANCHOR TABLE SHALL ALSO BE USED FOR EPOXY INCHORS. TORQUE TESTING IS NOT PERMITTED. WHERE EPOXY DOWELS ARE USED AS SHERE DOWELS ACROSS COLD JOINTS IN SUAB ON GRADE AND THE SLAB IS NOT A PART OF THE STRUCTURAL SYSTEM, TESTING OF THOSE DOWELS IS NOT REQUIRED.

5. ANCHORS SHALL EXHIBIT NO DISCERNIBLE MOVEMENT DURING THE TEST.

WOOD: GENERAL:

CENERAL: DO NOT NOTCH OR DRLL JOSTS, BEAKS OR LOAD REVENIG STUDS WITHOUT PROR APPROVAL OF THE STRUCTURAL BIGHEER HEROLICH THE ARCHITCT, DOUBLE UP STUDS AT AMEES AND UNDER BEAKS IN BERNIG WALLS PRONDE 2X SOLD BECOMEN AT MOI-HEIGHT OF LOAD BEARING STUD WALLS, ALL NAKS SHALL BE COMMON NAILS, ALL NAUTION LOT THE SHALL BE IN ACCOMMENT WITH TABLE 2204.01 OF THE LATEST EDITION OF THE CALIFORMA BUILDING CODE, ALL FRAMING ANCHORS AND CONNECTORS SHALL BE AS MANIFACTURED BY SUPERSYN CALIFARMOR ON OTHER APPROVED EDUAL WITH CBD CERTERATION, ALL NAIL HOLES IN FRAMING ANCHORS AND CONNECTORS SHALL BE FLUED WITH NAILS PER MANUFACTURERS PUBLISHED NAIL SZES. ALL BOUTS SHALL BE ASTM X307 BOLTS INSTALLED WITH STEEL WISHERS.

FRAMING LUMBER:

	BASE	VALUES FOR	DIMENSION LUN	IBER	
MEMBER	Fb (PSI)	Fv (PSI)	E (PSI)	Fc//(PSI)	& GRADE
JOISTS BEAMS	875	95	1,600,000	1300	DOUG FIR #2
4X MEMBERS	1000	95	1,700,000	1450	DOUG FIR #1 DOUG FIR #1
6X MEMBERS	1350	85	1,600,000	925	DOUG FIR ∦1
POSTS					
4X MEMBERS	1000	95	1,700,000	1450	DOUG FIR #1 DOUG FIR #1
6X MEMBERS	1200	85	1,600,000	1000	DOUG FIR #1
STUDS	900	95	1,600,000	1350	DOUG FIR 2
LEDGERS AND					
TOP PLATES	1000	95	1,700,000	1450	DOUG FIR #1
TREATED SILL	DOUG FIR	#2 MIN. EA	CH PIECE SHALL	BEAR A STAN	IP OF APPROVED
PLATES	INDEPEND	ENT AGENCY	OPERATING UND	ER AITC.	

FRAMING LUMBER SHALL COMPLY WITH THE LATEST EDITION OF THE GRADING RULES OF THE WESTERN WOOD PRODUCTS ASSOCIATION OR THE WEST COAST LUMBER MARK OF AN APPROVED GRADING AGENCY. MOISTURE CONTENT SHALL NOT EXCEED 19%.

MACHINE NAILING;

USE OF IMACHINE INVLING IS SUBJECT TO A SATISFACTORY JOBSITE DEMONSTRATION FOR EACH PROJECT AND THE APPROVAL OF THE PROJECT ARCHITECT OR STRUCTURAL DEWIDER: NOT THE ENFORCEMENT ARCKY: THE APPROVAL IS SUBJECT TO CONTINUED SATISFACTORY PERFORMANCE. MACHINE INALIA SAL SALEST TO CONTINUED SATISFACTORY PERFORMANCE. MACHINE INALIANS IN AT ALLOWED FOR 5/16" INCH PLYMODD. IF THE NILL HEAD SPECIATE THE OUTER PLY MORE THIN WOULD BE NOTALLY FOR A HAND HELD HANDER. OR IF MANNUM ALLOWAGE EDGE DESTARCES ARE NOT MANTARED, THE PRYRYGAMACHINE MILL BE DEEMED UNSATISFACTORY MON MACHINE INALIANS SALE BE

UNLESS SPECIFICALLY SHOWN ON THESE PLANS NO STRUCTURAL MEMBER SHALL BE CUT. NETHER DEILLED NOR NOTCHED WITHOUT PRIOR WRITEN AUTHORIZATION FROM THE STRUCTURAL ENGINEER AND THE CITY OF LOS ANGELES DEPARTMENT OF BULLINDA & SKETY.

STRUCTURAL SHEATHING:

STRUCTURAL SHEATHING PROPERTIES AND ATTACHMENT (MINIMUM, U.N.O.) ITEM THICKNESS RATIO NAILING INTERMEDIATE NAILING NAILING NAILING ROOF 23/32* 32/16 SEE SCHEDULE SEE SCHEDULE ROOF

ALL STRUCTURAL SHEATHING IS TO BE DOUGLAS FIR CONFORMING TO PS-1-83, GROUP 10 R 2 OR FAP EPERGRUNNCE RATED PARELS. STRUCTURAL-1 SHEATHING INCLUES ALL-VERER TYPICOL ORIGISTE PARELS CONTAINING A COMBINITION OF VEREER AND INCOD BASED MATERIALS. AND MAT-TORNED PARELS SUCH FYNICOD DAS TO BE "DISTERIO" THE, GROUP-MAKED DI THE ANDREAM FYNICOD ASCOUTING, GROUE STRUCTURAL-1 UNLESS. NOTED OTHERTINGE. SHEATHING THEM, INCOL TO BE MAN. 37/16 FOR NOTE SHEATHING TO HEM ANDREAM FYNICIDA UND AND STRUCTURAL-1 UNLESS. NOTED OTHERTINGE. SHEATHING THEM, INCOL TO BE MAN. 37/16 FOR NOTE SHEATHING AND 4704 FOR DISTERIOR SHEATHING.

THE MINIMUM PLYWOOD WIDTH FOR ROOF SHEATHING SHALL BE 24" WIDE AND 12" NUE FOR ALL SHEAR WALL SHEATHING. INSTALL PLYWOOD SHEATHING TO ALL EXTERIOR SOLID WALLS, SHEARWALLS & NON-SHEARWALLS, TOP SIDES AND BOTTOM OF WALL

SILL PLATES ON MASONRY OR CONCRETE TO BE 3x PRESSURE TREATED LUMBER. WALL STUDS AND BLOCKING AT ADJOINING PANEL EDGES TO BE 3x OR LARGER. PLYWOOD JOINT AND SILL PLATE NALUNG TO BE STAGGERED IN ALL CASES.

ALL NAILS TO BE COMMON WIRE NAILS AS INDICATED IN THE NAILING SCHEDULE All must to be common when must as indicated in the multime schedule (fare 2044). Tastinnis schedule" of the 2007 dec) and per phan. Bon to the experiment that the must be the table of the 2007 dec) and per phan. Bon to the experiment of the table must be the must be table of the table of the table of the table of table of the table of table

ALL FRAMING CONNECTORS TO BE SIMPSON STRONG TIE COMPANY OR AS REQUIRED BY THE STRUCTURAL PLANS. SUBSTITUTIONS FOR EQUIVALENT PRODUCTS MAY BE USED. CONTRACTOR IS RESPONSIBLE FOR PROVINGE PROC FOR EQUIVALENCY. TO INCLUDE BUT NOT LIMITED TO THE ICC REPORT. PROVIDE THE TYPE OF MALLS SPECIFIED BY THE MAURAFCHIERE MO FULLY DRIVE MALLS THAT ALMOST OF THE CONNECTOR UNLESS NOTED OTHERMISE ON THE FLANS. ALL CONNECTORS SHALL BE GALVANIZED OR HAVE ANOTHER PRICTOR PHILED INGN. LAL STELL REMAIN WARKERS TO BE TORSCIONAL RESTRUMT. SOLD BLOCKING REQUIRED BETWEEN JOISTS WHERE TORSGONAL RESTRIANT HWORES DO INGI OCCUR.

SANTA BARBARA DEPARTMENT OF BUILDING AND SAFETY: GENERAL NOTES FOR STRUCTURAL OBSERVATION:

- I. STRUCTURAL OBSERVATION IS REQUIRED FOR THE STRUCTURAL SYSTEM IN ACCORDANCE WITH 2007 CBC CHAPTER 17. STRUCTURAL OBSERVATION IS THE VISUAL OBSERVATION OF THE LEILENTIS AND CONNECTIONS OF THE STRUCTURAL SYSTEMS TSIGNIFICATIO CONSTRUCTION STROSE AND THE COMPLETED STRUCTURE FOR GENERAL CONFORMANCE TO THE APPROVED PLANS AND SPECIFICATIONS. STRUCTURAL OBSERVATION DOES NOT WAVE THE RESPONSIBILITY FOR THE INSPECTIONS REQUIRED OF THE BUILDING INSPECTOR OR THE DEPUTY INSPECTOR.
- 2. THE OWNER SHALL EMPLOY A OWL OR STRUCTURAL ENGINEER OR ARCHITECT TO PERFORM THE STRUCTURAL DESERVATION. THE ENGINEER OR ARCHITECT SHALL BE REGISTERE OR DUCHSEDD IN THE STATE OF CALFORMA. THE DEPARTMENT OF BULLINGS AND SAFETY RECOMMENDS THE USE OF THE ENGINEER OR ARCHITECT RESPONSELE (FOR THE STRUCTURAL DESGN WHICH THEY ARE INDEPENDENT OF THE STRUCTURAL DESING WHICH ARE AND THE ARE INDEPENDENT OF THE DESINGUESTICS. CONTRACTOR
- 3. THE STRUCTURAL OBSERVER SHALL PROVIDE EVIDENCE OF EMPLOYMENT BY THE OWNER. A LETTER FROM THE OWNER OR A COPY OF THE ARREEMENT FOR SERVICES SHALL BE SENT TO THE BUILDING MSEFCORE BEFORE THE REF RRST STE VISIT. THE STRUCTURAL OBSERVER SHALL ALSO INFORM THE OWNER OF THE REQUIREMENTS FOR A PRECOMBUNCTION MEETING AND SHALL PRESON CHRE THIS MEETING
- 4. THE OWNER OR OWNER'S REPRESENTATIVE SHALL COORDINATE AND CALL FOR A THE OWNER OR OWNER'S REPRESENTATIVE SHALL COORDINATE AND CALL FOR A METING BETWEEN THE ENDINER OF ADMETICT RESPONSIBLE FOR THE STUCTURAL DESING, STRUCTURAL DESKRER, CONTRACTOR, AFFECTED SUBCONTRACTORS AND DEPUTY RESPECTIONS. THE PURPOSE OF THE MEETING SHALL BE DEPUTY MAYOR STRUCTURAL ELEMENTS AND CONNECTIONS THAT AFFECT THE VERTICAL AND LEMENAL LOAD STETUSION OF THE MEETING SHALL BE DEPUTY RESULTING DESCRIPTIONS. A RECOMO OF THE MEETING SHALL BE NACLUDE IN THE FERST OBSERVATIONS. A RECOMO OF THE MEETING SHALL BE INCLUDED IN THE FERST OBSERVATIONS. A RECOMO OF THE MEETING SHALL BE INCLUDED IN THE FERST OBSERVATIONS. A RECOMO OF THE MEETING SHALL BE INCLUDED IN THE
- 5. THE STRUCTURAL OBSERVER SHALL PERFORM SITE VISITS AT THOSE STEPS IN THE PRODESS OF THE WORK THAT ALLOW FOR CORRECTION OF DEFICIENCES WITHOUT SUBSTAINTLE FORTOR TO RUCORENCE OF THE WORK INVOLUE. A TA MANNUM, THE FOLLOWING SIGNIFICANT CONSTRUCTION STACES RECOURE A SITE VISIT AND AN OSESTIVATION ERPORT FROM THE STRUCTURAL OBSERVER.
- 6. THE STRUCTURAL OBSERVER SHALL PREPARE A REPORT ON THE DEPARTMENT FOR EACH SIGNIFICANT STAGE OF CONSTRUCTION OBSERVED. THE ORIGINAL OF THE OBSERVATION REPORT SHALL BE SENT TO THE BUILDING INSPECTOR'S OFFICE AND OBSERVITION REPORT SHALL BE SENT TO THE BUILDING APSPECTOR'S OFFICE AND SHALL BE SIGNED AND SEALED (WT STAMP) BY THE RESPONSIBLE STRUCTURAL OBSERVER. ONE COPY OF THE OBSERVATION REPORT SHALL BE ATTACHED TO THE APPROVED PLVAS. THE COPY ATTACHED TO THE PLVAS. INSEE NOT BE SEALED BUT SHALL BE SIGNED BY THE RESPONSIBLE STRUCTURAL OBSERVER OR THER DESCRICE. COPIES OF THE REPORT SHALL ALSO BE GIVEN TO THE OWNER, CONTRACTOR, AND DEFUTY NERSECTOR.
- 7. A FINAL OBSERVATION REPORT MUST BE SUBMITTED WHICH SHOWS THAT ALL OBSERVED DEFICIENCIES WERE RESOLVED AND THE STRUCTURAL SYSTEM GENERALLY Objective of our development of the structure of the stru
- 8. WHEN THE OWNER ELECTS TO CHANGE THE STRUCTURAL OBSERVER OF RECORD, THE OWNER SHALL
- A. NOTIFY THE BUILDING INSPECTOR IN WRITING BEFORE THE NEXT INSPECTION. NOIPT THE BOILDING INSPECTOR IN WINING BEFORE THE NEXT INSPECTION B. CALL AN ADDITIONAL PRECONSTRUCTION MEETING, AND.
 C. FURNISH THE REPLACEMENT STRUCTURAL OBSERVER WITH A COPY OF ALL PREVIOUS OBSERVATION REPORT.
- THE REPLACEMENT STRUCTURAL OBSERVER SHALL APPROVE THE CORRECTION OF THE ORIGINAL OBSERVED DEFICIENCIES UNLESS OTHERWISE APPROVED BY PLAN CHECK SUPERVISION. THE POLICY OF THE DEPARTMENT SHALL BE TO CORRECT ANY PROPERLY NOTED DEFICIENCIES WITHOUT CONSIDERATION OF THEIR SOURCE
- THE ENGINEER OR ARCHITECT OF RECORD SHALL DEVELOP ALL CHANGES RELATING TO THE STRUCTURAL SYSTEMS. THE BUILDING DEPARTMENT SHALL REVIEW AND APPROVE ALL CHANGES TO THE APPROVED PLANS AND SPECIFICATIONS.

SHEET INDEX: S0.1 GENERAL NOTES S0.2 GENERAL NOTES S1.1 DETAILS EXISTING BASEMENT RETROFIT PLAN EXISTING FIRST FLOOR RETROFIT PLAN EXISTING SECOND FLOOR PLAN EXISTING ROOF RETROFIT PLAN WALL ELEVATIONS S2.1 S2.2 S2.3 S2.4 S2.5 S3.1 S3.2 S3.3 BASEMENT REFLECTED CEILING DEMOLITION PLAN FIRST FLOOR REFLECTED CEILING DEMOLITION PLAN SECOND FLOOR REFLECTED CEILING DEMOLITION PLAN

			REVISIONS		
NO.	DATE		DESCRI	PTION	Br
		_			
			fax 818.285.2	651	
OWNER		OF S ASTING MARK	ANT	BAR	
PROJECT	CITY CITY 8 POLICE 21	OF S BANTA	ANT/ BARB. SEISM	A BARI ARA, C. IIC RETRI EROA (A Ofit stui st.
PROJECT	CITY CITY SAN	OF S ASTING SANTA STATION 5 EAST	ANT/ BARB. SEISM	A BARI ARA, C. IIC RETRI EROA (A Ofit stui st.
PROJECT SB P	CITY CITY SAN	OF S BANTA STATION 5 EAST TA BAF	ANT/ BARB. SEISM	A BARI ARA, C. IIC RETRI IEROA 3 I, CA 9	A Ofit stui st.
PROJECT SB P DRAWING PROJECT	LITY SOLICE 21: SAN TITLE	ASTING COMPACTION ASTING COMPACT SANTA STATION 5 EAST TA BAF GENE	ANTA BARB SEISM FIGU BARA RAL N	A BAR ARA, C IIC RETR EROA : , CA 9 IOTES	A Ofit stui st.
PROJECT SB P DRAWING PROJECT 1030	CITY 8 00LICE 21: SAN TTLE	OF S ASTING OF S BANTA STATION 5 EAST TA BAF GENE SOLLE AS SHOWN	ANTA BARB SEISM FIGU RBARA RAL N	A BAR ARA, C. IIC RETR EROA (, CA 9 IOTES	A OFIT STUI ST. 3102
PROJECT SB P DRAWING PROJECT	CITY 8 00LICE 21: SAN TTLE	OFFINIC INTERNATION ASTING INTERNATION OF S SANTA STATION 5 EAST TA BAF GENE	ANTA BARB SEISM FIGU BARA RAL N	A BAR ARA, C IIC RETR EROA : , CA 9 IOTES	A OFIT STUI St. 3102

FIBER REINFORCED POLYMER (FRP) STRENGTHENING

1. PROPOSED FRP COMPOSITE SYSTEM SHALL HAVE A CURRENT ICC EVALUATION REPORT AND BE INSTALLED ACCORDING TO THE CONTRACT DOCUMENTS, MANUFACTURER'S AND ICC RECOMMENDATIONS AND PROCEDURES.

CONTRACTOR SHALL HAVE A MINIMUM OF TEN (10) STRENGTHENING PROJECT REFERENCES USING FRP COMPOSITE SYSTEMS FOR SIMILAR PROJECTS AND APPLICATIONS IN THE LAST TWO YEARS. THIS LIST SHALL BE INCLUDED IN THE SHOP RAMING SUBMITTAL.

3. THE ONSITE SUPERVISOR, FOREMAN AND SATURATION/MIXING TECHNICIAN SHALL THE UNSITE SUPERVISION, FURGIAMIN AND SATURATION MANNO TECHNICIAN STALL HARE A NIMIMM OF THREE (JYARS EXPERIENCE ON AT LEAST FIFTEIN (15) DIFFERENT FROLECTS. THESE THREE INDIVIDUALS SHALL PROVIDE WRITTEN VERIFICATION FROM THE MATERIAL MANUFACTURER AS BEING FULLY TRAINED AND CERTIFIED TO INSTALL THE FRP.

4. COMPOSITE SYSTEM APPLICATOR SHALL SUBMIT WITNESS PANELS PREPARED AT THE JOBSITE FOR MATERIALS TESTING (ASTM D3039). THE TESTING SHALL BE DONE BY AN INDEPENDENT TESTING LABORATORY TO VERIFY ALL SUBMITED DESION REPORTENTES. TESTING SHALL BE PAD FOR BY THE OWNER. FIELD DESIGN PROPERTIES. TESTING STALL BE PAID FOR BY THE OWNER, FIELD TEST RESULTS THAT ARE LOWER THAN THE DESIGN PROPERTIES SUBMITTED SHALL REQUIRE THE CONTRACTOR TO PAY FOR REMEDIAL MEASURES TO BE APPROVED BY THE ENGINEER-OF-RECORD.

5. CONTRACTOR SHALL SUBMIT CALCULATIONS VERFYING COMPLIANCE WITH THE DESIGN CRITERIA STATED ON THE CONTRACT DRAININGS. CALCULATIONS SHALL BE RASED ON THE VERFIED MATERIAL PROPERTIES AND CORRESPONDICA LYRE THICKNESS AND SHALL BE STAMPED AND SIGNED BY A REDISTRED CIVIL OR STRUCTURAL ENANDER.

6. SEE FULL SPECIFICATIONS ON SHEET SO.1.

SECTION 03930

FIBER REINFORCED POLYMER STRENGTHENING SYSTEM

PART 1-GENERAL

- 1.01 THIS SPECIFICATION IS INTENDED FOR USE IN DEFINING THE REQUIREMENTS OF REINFORCED CONCRETE. AND MASONRY STRENGTHENING USING EXTERNALLY BONDED FIBER REINFORCED POLYMER (FRP) SYSTEMS.
- 1.02 THE CONTRACTOR OR SUB-CONTRACTOR SHALL FURNISH ALL SUBMITTALS, MATERIALS,
- TOOLS, EQUIPMENT, TRANSPORTATION, NECESSARY STORAGE, LABOR, AND SUPERVISION REQUIRED FOR THE APPLICATION OF THE COMPOSITE SYSTEM.

1.03 REFERENCES

- GENERAL 1. THE PUBLICATIONS LISTED BELOW FORM A PART OF THIS SPECIFICATION TO THE

- Lister DIRELATIONS LISTED BELOW FORM A PART OF THIS SPECIFICATION TO THE EXTEMT REFERENCE.
 WHERE A DATE IS GYNEN FOR REFERENCE STANDAROS, THE EDITION OF THAT DATE SHALL BUSED, WHERE NO DATE IS GYNEN FOR REFERENCE STANDAROS, THE LATEST EDITION AMULABLE ON THE DATE OF NOTICE INMITING BIDS SHALL BE USED.
 MERCINA STANDARO FOR TISTING AND MATERIALS (SATN)
 ASTIM D3239 (1993A), STANDARO TEST WETHOD FOR TENSILE PROPERTIES OF POLYMER MATRIX COMPORTIMACE (MATERNA AND TEST WETHOD FOR TENSILE PROPERTIES OF POLYMER MATRIX COMPORTIMACE (MATERNA FOR CONCRETE AND REINFORCED AND UNREINFORCED MASCINITY STRENGTHENING USING EXTERNALLY BONDED TIBER-REINFORCED POLYMER (RFP) COMPACED MASCINY STRENGTHENING USING FIBER REINFORCED DALVIER (CAMPOSITE SYSTEMS.
 LICACATSE (2001), ACCEPTANCE GRIFTIAN FOR INSPECTION AND VERIFICATION OF CONCRETE AND REINFORCED DALVIER COMPOSITE SYSTEMS.
 LICACATSE (2007), ACCEPTANCE GRIFTIAN FOR INSPECTION AND VERIFICATION OF CONCRETE AND REINFORCED DALVIER COMPOSITE SYSTEMS.
 MERCINA CONCRETE INSTITUTE (AC)
- AMERICAN CONCRETE INSTITUTE (ACI)
 AMERICAN CONCRETE INSTITUTE (ACI)
 ACI 440.2R-02, GUIDE FOR THE DESIGN AND CONSTRUCTION OF EXTERNALLY
 BONDED FRP SYSTEMS FOR STRENGTHENING CONCRETE STRUCTURES.

1.04 MATERIAL QUALIFICATIONS

MATERIALS FOR THE FRP SYSTEM HAVE BEEN PRE-QUALIFIED AND SHALL BE SUPPLIED BY FYFE MALENUS FOR THE THE STIGLE THREE ECEN PRE-COUNTED AND SHALL BE SUPPLIED BY THE COLLE (NAMEY) THREE TECHNOLOGY CONTER, 6310 NAMEY RODE DRIVES, SUPE 103, SAN DIEGO, CA 92121. TEL: 858-842-094, FAX: 858-842-0947, EMAIL: <u>BYDENTECOLOGU</u> (<u>AMILIONICOPTECOLOGU</u>) OR NAMPROVED ALTERNET STELEN KUST PROVIDE ALL TELEN LISTED IN SECTION 1.068 OF THIS SPECIFICATION AND SUBMIT TWO-WEEKS PROR TO THE PROJECT BO DATE. (UAR 2200)

1.05 CONTRACTOR QUALIFICATIONS

- A. THE WORK SPECIFIED UNDER THIS SPECIFICATION SHILL BE PERFORMED BY AN APPLICATOR WITH PROYEN PAST EXPERIENCE APPLING THE APPROVED COMPOSITE SYSTEM FOR A MINIMUM OF 20 PORVECTS WITH OHER 20 OLENDRATIS STERENTIFIED. THE APPLICATOR MUST SUPPLY THE NAMES OF AT LEAST THREE INDIVIDUALS WHO HAVE BEED RETRIED AND TANNED BY THE FIRP SYSTEM MANUFACTURER TAND WHO MULE Been Centrieu and Inaneu By The PROJECT Stylem Manufacioner and Who Mill Be on Step During all Phases of the Product. The Engineer of Regoon Shall have The Right To Approve or Reject The Personnel Qualifications as submitted. The Engineer May Suspend The Work if The Contractors Substitutes Unauthorized Personnel for Authorized Personnel During Construction.
- B THE COMPOSITE SYSTEM APPLICATOR SHALL SUBMIT A WRITTEN DESCRIPTION OF THE THE COMPOSITE SYSTEM APPLICATOR SHALL SUBMIT A WHITEN DESCRIPTION OF THE PROPOSED EPOXY, INCLUNIEN VIC LEUES, MOI A COMPLETE WHITEN DESCRIPTION OF THE APPLICATION OF NOCEDIESE OF REVIEW BY THE ENGINEER-OF-RECORD. THE APPLICATION COMPARY MUST BE CERTIFIED BY THE BUNGETRATIONERFS/SUPPLIENT IN WHITING AND PROVIDE A QUALITY CONTROL, PROCEDURE IN ACCORDANCE WITH SECTION 3.04 OF THIS SPECIFICIDIA.

1.06 SUBMITTALS

- A. DESIGN AND WORKING DRAWINGS:
- STAMPED AND SCRED STRUCTURAL CALCULATIONS AND DRAWINGS BY A LICENSED CALL OF STRUCTURAL DRIVER.
 WORNED DRAWING SETUALING THE TYPE, LOCATIONS, DMENSONS, NUMBERS OF LUKERS, AND ORIENTATION OF ALL FRP MATERIALS AND COATINGS TO BE INSTALLED.
 A LIST OF TWO DIFFERENT GUALIFIED TESTING LABORATORIES THAT CAN PERFORM THE REQUIRED ASTIM D 3039 TESTS AS PER SECTION 3.04 OF THIS SPECIFICATION.

B. PRODUCT INFORMATION:

- AN APPROVED ICC EVALUATION REPORT FOR THE PROPOSED COMPOSITE SYSTEM. EVALUATION REPORT MUST COVER THE TYPE OF STRENGTHENING BEING PROPOSED.
 AN APPROVED RESEARCH REPORT WITH THE CITY OF LOS ANGELES.
- an approved the bank theory with the uit of los and effects.
 Provide A class 1 (A) Flame and smoke, fire resistance rating as per astmices for the proposed assembly (if interior Application).
 Properties of the composite materials as determined by independent
- LABORATORY TESTING IN ACCORDANCE WITH ASTM D 3039 (TENSILE MODULUS. LABORATORY TESTING IN ACCORDANCE WITH ASTIN D 3039 (TENSILE MODULUS, STRESS AND STANN). 5. LARGE-SCALE STRUCTURA, TESTING ON SMILLAR SECTIONS. 6. INSTILLATION PROCEDURES, WARTENNICE (INSTILLATIONS, NID GENERAL RECOMMENDATIONS RECARDING EACH MATERIAL TO BE USED. 1. MANUFACTURER'S MATERIAL SAFETY DATA SHEETS (MUSD) FOR ALL MATERIALS TO BE USED. 6. MANUFACTURER'S PRODUCT DATA SHEET INDICATING PHYSICAL, MECHANICAL AND CHARACTURER'S MATERIAL "MANAFACTURER THAT TRAVINGT MAS RECEIVED THE REQUIRED CERTIFICATIONS AND TRANSING. 10. CERTIFICATION BY THE MANAFACTURER THAT TRAVINGT SUPPLICATOR MAS RECEIVED THE ST'LE MANAFACTURER THAT PROJECTS SUPPLIED COMPLY WITH LOCAL, REGULATIONS CONTROLLING USE OF VOLATLE ORDINIC COMPOUNDS (VOC'S).

1.07 PERFORMANCE

- A. DESIGN THE COMPOSITE SYSTEM TO ACHIDVE THE STRUCTURAL PERFORMANCE SHOWN ON THE STRUCTURAL DEWINNESS. DESIGN CALCULATIONS FOR THE COMPOSITE SYSTEM SAILL BE SUBMITTE FOR APPROVAL BY THE EXORERE OF RECORD, AND SHALL DE STAMPED BY A REGISTERED CNIL ENDINEER. B. CALCULATIONS SHALL CONFORM TO REQUIREMENTS SET FORTH IN NOC E S ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND BE BASED ON THE DESIGN MODULUS AND ACCEPTINCE CRITERIA (AC25) AND ACCEPTINCE ACCE
- ASCEPTINGE OFFICIENT (ALIZS) AND BE BASED IN THE DESIGN MODULUS AND ASSOCIATED AREA OF THE COMPOSITE TO BE INSTALLED. FRP DESIGN VALUES MUST BE LOWER THAN THE CALCULATED MEAN DETERMINED FROM THE TEST RESULTS RECEIVED FROM THE ASTM D3039 FIELD TEST SPECIMENS (SEE SECTION 3.07 OF THIS SPECIFICATION).
- 1.08 PRODUCT DELIVERY, STORAGE AND HANDLING
 - A. DELIVER EPOXY MATERIALS IN FACTORY-SEALED CONTAINERS WITH THE MANUFACTURER'S LABELS INTACT AND LEGIBLE WITH VERIFICATION OF DATE OF MANUFACTURE AND SHELF LIFE.
 - B. STORE MATERIALS IN A PROTECTED AREA AT A TEMPERATURE BETWEEN 40° AND
 - C. PRODUCTS SHALL BE STORED ACCORDING THE MANUFACTURER'S REQUIREMENTS AND

PART 2-PRODUCTS

- 2.01 COMPOSITE STRENGTHENING SYSTEM
- APPROVED TYFO® FIBRWRAP® SYSTEM TO BE SUPPLIED BY FYFE COMPANY, NANCY RIDGE TECHNOLOGY CENTER, 6310 NANCY RIDGE DRIVE, SUITE 103, SAN DIEGO, CA 92121. TEL: 858-642-0694, FAX: 858-642-0947. PRODUCTS INCLUDE:
- A. COMPOSITE FABRIC: SCH FIBER PRIMARY CARBON FIBER, UNIDIRECTIONAL. SEH FIBER PRIMARY GLASS FIBER, UNIDIRECTIONAL.
- B. EPOXY SATURANT/PRIMER: TYFOD S EPOXY IS USED AS A PRIMER AND IS ALSO COMBINED WITH THE FIBER TO FORM THE TYFOD FIBRWRAPD SYSTEM.
- C. PRIMER/FILLER: TYFOD WS OR TO THICKENED EPOXY FOR PROTECTIVE SEAL COAT FILLING YOUNS AND PRIMER WHERE NEEDED
- D. FINISHES: TYFO® RR OR TYFO® FC/F, TYFO® A PAINT TO BE COLOR MATCHED ARCHITECT. ALTERNATE FINISHES MUST BE APPROVED BY THE ARCHITECT.
- E. FIELD THICKENED EPOXY MATRIX, WHICH IS COMPATIBLE WITH COMPOSITE SYSTEM RESIN MATRIX, MAY BE USED TO PATCH "BUGHOLES" UP TO 1.5" IN DEPTH AND FILL VOIDS
- 2.02 OTHER MATERIALS
- PROVIDE OTHER MATERIALS AS NEEDED FOR THE PROPER INSTALLATION OF THE COMPLETE COMPOSITE SYSTEM, AS SELECTED BY THE CONTRACTOR IN CONFORMANCE WITH THESE SPECIFICATIONS.

PART 3-EXECUTION OF WORK

3.01 SURFACE PREPARATION:

WALLS: A. CONCRETE SURFACES SHALL BE PREPARED FOR BONDING BY MEANS OF ABRASIVI BLASTING OR GRINDING TO ACHIEVE A 1/16" MINIMUM AMPLITUDE. ALL CONTACT SURFACES SHALL THEN BE CLEANED BY HAND OR COMPRESSED AIR. ONE PRIME COAT OF THE MANUFACTURER'S EPOXY SHALL BE APPLIED AND ALLOWED TO CUR FOR A MINIMUM OF ONE HOUR. PRIOR TO THE APPLICATION OF THE SATURATED COMPOSITE FABRIC, FILL ANY UNEVEN SURFACES WITH THE MANUFACTURER'S THICKENED EPOXY. PROVIDE ANCHORAGE AS DETAILED ON APPROVED CONSTRUCTION DRAWINGS.

3.02 PROCEDURES FOR APPLICATION

- A. PREPARATION WORK FOR PROJECT: VISIT SITE TO INSURE THAT ALL PATCH WORK IS COMPLETE AND CURED. REVIEW PROJECT SPECIFICATIONS IN DETAIL.
- B. VERIFY AMBIENT AND CONCRETE TEMPERATURES. NO WORK SHALL PROCEED IF TI TEMPERATURE OF THE CONCRETE SURFACE BEING REPARED IS LESS THMI 40 F OR GRAZIER THMI 100 F. THE TEMPERATURE OF THE FDOX COMPONENTS SHA BE BETWEEN 407 AND 100 F AT THE TIME OF MIXING OR AS SPECIFIED ON THE COMPONENT LABLES. WHEN AN TEMPERATURE IS OUTSIDE THE PRESCREME PARK OTHER MEASURES MIST BE EMPLOYED TO ENSURE COMPONENTS' TEMPERATURE IS MINIMINING THEMINI THE BANK OF MISING THE AS THE COMPONENTS' TEMPERATURE IS MINIMINING THEMINI THE BANK OF MISING COMPONENTS' TEMPERATURE IS NTAINED WITHIN THIS RANGE
- PREPARE THE EPOXY MATRIX BY COMBINING COMPONENTS AT A RATIO SPECIFIED IT THE SYSTEM MANUFACTURER, WITH AN ALLOWABLE TOLERANCE OF \pm 10%. THE COMPONENTS OF EPOXY RESIN SHALL BE MIXED WITH A MECHANICAL MIXER UNTIL UNIFORMLY MIXED, THYLALLY 5 MINUTES AT 400-600 RPM. COMPONENTS THAT HAVE EXCEEDED THEIR SHELF LIFE (AS DESIGNATED ON THE MATERIAL LABEL) SHALL NOT BE USED
- D. BOTH EPOXY RESN AND FABRIC SHALL BE MEASURED ACCURATELY, COMBINED, AN DEPOSITED UNFORMLY AT THE RATES SHOWN ON THE APPROVED WORKING DEWAINGS AND PER MANAFACTURER'S RECOMMENDATIONS. THE COMPOSITE SYSTEP SHALL BE COMPRISED OF FIBERS COMPLETELY SATURATED WITH EPOXY RESN PER PRODEE PROVED FILE OF FIBERS COMPLETELY SATURATED WITH EPOXY RESN PER PRODEE PROVED. PROPER RATIO.
- E. QUALITY CONTROL PROCEDURES: RECORD BATCH NUMBERS FOR FABRIC AND EPOXY USED EACH MAY, AND NOTE LOCATIONS OF INSTALLATION, MEASURE SQUAI FOOTAGE OF FABRIC AND VOLUME OF EPOXY USED EACH DAY. COMPLETE REPOR AND SUBMIT TO SEEDUL INSPECTION AND SYSTEM MANUFACTURER. SEE SECTION 3.04 OF THIS SPECIFICATION
- 2.50 OF THIS BLOCKENDER: ON A SMOOTH, FLAT, LEVEL SURFACE COVERED WITH POLICIPATLENE SHEETING, OR 16 ML PULSTIC FLM, PRIME WITH EPOXY SATURANT, THEN PREPARE SMIPLE BY PLACING TWO LAYERS OF SATURATED FARM OREINED IN TE SAME DRECTIONA NOA OLLOW TO CURE. APPLY ADDITIONAL TOPPING OF EPOXY AS REQUIRED TO ENSURE COMPLETE SATURATION. SAMPLES SHALL BE STORED IN A SAMPLE SOX AND NOT MOVED FOR A INMUMU AS HOURS AFTER CASTING. THE PREPARED, DESTIFIED SAMPLES SHALL BE GREVE TO A PREAPPROVED TESTING LARGORY FROM THE SUBMITED LST. (SEE SECTION 3.04 FOR TESTING PROCEDURES AND REQUIREMENTS).


G. INSTALLATION PROCEDURES:


- I. PREPARE SURFACE AS REQUIRED, INCLUDING CORNER PREPARATION.
 REMOVE DUST AND DEBRIS BY HAND OR WITH COMPRESSED AIR AS PER
- SPECIFICATION. CLEAN UP AND PROTECT AREA ADJACENT TO ELEMENT. USING A ROLLER OR TROVEL, APPLY ONE PRIME COAT OF EPOXY RESIN TO THE COURGETE SURFACE (2 MIL, MIN.). ALLOW PRIMER TO BECOME TACKY THE TOUCH.
- THE COUCHETE SUPPORT (2 MLL MIN). ALLOW PRIMER TO BECOME TACK'T THE TOUCH. 5. FILL MAY UNEXEN SUPPORTS OR RECESSES WITH THICKENED EPOXY. 6. SAUDART FARING WITH FORY MAIRY AS PER MANUARCHURES SPECIFICATION 7. APPLY SATURATED FARING TO CONCRETE SUPPACE OF HAND LAY-UP, USING METHODS THAT PRODUCE A UNFORM, CONSTANT TENSILE FORCE THAT IS DISTIBUTED ACROSS THE ENTINE WOTH OF FARING. UNDER CERTIAN TA PAPULATION CONTINION, THE STSTEM MAY EE PLACED DIVINICY OF HAND METHODS ASSURING A UNFORM, DYNE FINAL APPERANCE. (APPS ETWEND UNFORMS THAT BOTTLED IN WOTHON, MY CONTENT THAT APPERANCE. (APPS ETWEND UNFORMS THAT DIVINICAL WITHOUT ON MORE DIVINICY AND ADDITION.) METHODS ASSURING A UNFORM, DYNE FINAL APPERANCE. (APPS ETWEND UNLESS OTHERWISE WOTED ON PROJECT DRAMINGS. A LAY LINNITY METHODS THAT AND ADDITION. THE STRUCTURED WITH ON THE FORMY. STRUCTURES UNIT WILLESS OTHERWISE WOTED ON PROJECT DRAMINGS. A LAY LINNITY OF METHODS ASSURING A UNFORCE OF AND ADDITION. AT LEAST 6" IS REQUIRED AT ALL NECESSARY OVERLAPS IN THE PRIMARY FI
- AT LEAST 6° IS REQUIRED AT ALL NECESSARY OVERAPS IN THE PRIMAY HED DIRECTION OF THE PARINE. 8. APPLY SUBSCILIENT LYNERS, CONTINUOUSLY OR SPLICED, UNTIL DESORDED NUMBER OF LYNERS IS ACHIEVE, PER PROLET DRAWNIGS. 9. USING A ROLLER OR HWAD PERSSURE, INSIGE PROFER ORENATION OF PREFERS, RELEXES OR FOLL OUT DIRAPPED AR, AND ENSIGIE THAT EACH NOMOLIM. LAYER IS FRMLY BEDOED AND ADMERED TO THE PRECEDING LAYEF
- OR SUBSTRATE. 10. DETAIL ALL FABRIC EDGES, INCLUDING TERMINATION POINTS AND EDGES, WITH
- EPOXY. I. MNSH: ALL EDGES AND SEANS MUST BE FEATHERED. USE SYSTEM AS DIRECTED BY MANUFACTURER. PAINT AS SPECIFIED BETWEEN 24 AND 72 HOURS AFTER TINUL AFPLICATION OF EPOXY. IF AFTER 72 HOURS THE EPOX IS CURED, THE SURFACE UNITS DE ROUGHERED BY HAND SANDING OR BRUSS-
- BLASTING. 12. SYSTEM MAY INCORPORATE STRUCTURAL FASTENERS BUT LIMITATIONS AND DETAILING MUST BE VERIFIED WITH COMPOSITE SYSTEM MANUFACTURER.

3.03 PROCEDURE MODIFICATIONS

INSTALLATION PROCEDURES MAY BE MODIFIED TO ACHIEVE MAXIMUM RESULTS, SUBJECT TO HADRONAL THOUSAND THE DE MOUTH TO THOUSE HADRON THEORY THOUSAND THE CITY/COUNTY AND THE ENGINEER-OF-RECORD. PROCEDURE MODIFICATIONS SHALL BE DEGUSSED WITH THE CITY/COUNTY AND ENGINEER-OF-RECORD PRIOR TO IMPLEMENTING THE MODIFICATIONS.


	3.04 FIEL	A.	JALITY CONTROL INSTALLERS: RECORD BATCH NUMBERS FOR LOCATIONS OF INSTALLATION. OF EPOXY USED EACH DAY.	FABRIC MEASURI	AND EPOXY E SQUARE F E REPORT A	USED DOTAGE	EACH DAY, OF FABRI	, AND NOTE IC AND VOLUME ITY/COUNTY.			
		в.	ENGINEER-OF-RECORD AND ST INSPECTION: CERTIFIED SPECIAL INSPECTOR,	APPRON	ANUFACTURE	r. City/c	ounty, sh	ALL			
)			PERIODICALLY OBSERVE ALL AS OF MATERIALS, INCLUDING THE	FOLLOW	of Prepara' Ing:	10N, M	ixing, and	APPLICATION			
AT,			1. MATERIAL CONTAINER LABELS 2. SUBFACE PREPARATION 3. MIXING OF EPOXY								
BY			 APPLICATION OF EPOXY TO APPLICATION OF COMPOSITE CURING OF COMPOSITE MA 	3. MIXING OF EPOXY 4. APPLICATION OF EPOXY TO THE FIBER 5. APPLICATION OF COMPOSITE SYSTEM 5. CURING OF COMPOSITE MATERIAL							
			7. PREPARATION AND LABELIN THE CONTRACTOR SHALL MONT	IG OF TE	EST SAMPLES		OVY COME	ONENTS FOR			
rs TO			PROPER RATIO AND ADHERENC								
			LABORATORY TESTING: RECORD LOT NUMBER OF FABRIC AND RESIN USED, AND LOCATION OF INSTALLATION, A "SUMPLE BATCH SHALL CONSIST OF TWO 12" X 12" SAMPLES OF CURED COMPOSITE: A UNIMAM OF TWO SAMPLE BATCHES SHALL BE MADE DALY. THE TWO SAMPLE BATCHES WILL BE TAKEN AT APPROPRIATE INVESTORMING THE DAYS OF AS TO ENSURE THE MAXIMUM ANTERAL DEVANCE IN THE COMPONENTS OF THE COMPOSITE. TESTING, BADRORATOR YALL PRE-CONDITION SAMPLES AT 140° FOR 48 HOURS BEFORE TESTING, SAMPLES SHALL BE TESTED, AT RANDOM, AT OWNER'S DISORTION AND COST.								
Æ			TESTED SAMPLES SHALL BE TE SHALL HAVE 5 COUPONS, 3/4" PROPERTIES IN THE LONGITUDII CONFORM TO ASTM PROCEDUR	X 9", RI NAL (PRI ES AND	EMOVED AND MARY FIBER MANUFACTUR	testei Direc Rer's f	d for the tion. Te: Published	eir Material STS Shall Testing			
RE			METHODS. ONLY PRE-QUALIFI TESTING RESULTS SHALL BE M SUBMISSION. THE TESTING SH 1. ULTIMATE TENSILE STRENG 2. TENSILE MODULUS	ADE AVA	ILABLE WITH	N 3 W	FEKS OF S	SAMPLE			
			 PERCENT ELONGATION 15% OF ALL SAMPLE BATCHES 	ARE SU	ggested to	BE TE	STED. IF (DNE 12" X 12"			
ik The			SAMPLE FAILS (ON AVERAGE), TESTED. IF THESE SPECIMENS FROM THE SAME SAMPLE BATC THIS SAMPLE ALSO FAILS, THE TESTED AND APPROPRIATE REM	SPECIME ALSO F H WILL REMAIN MEDIAL M	NS FROM TH AIL (ON AVE BE TESTED. ING SAMPLE EASURES, P	IE SAMI (RAGE), IN TH BATCH ER SEC	E SAMPLE THE OTHE E EXTREME FOR THAT TION 3.07.	WILL BE ER 12" X 12" E CASE THAT I DAY WILL BE LE, WILL BE			
HALL E NGE,			TAKEN TO ENSURE INTEGRITY (IN ADDITION, 25% OF THE REM THE SAME CRITERIA.	of the Kaining S	SYSTEM FRO SAMPLE BATO	m The Ches W	FAILED SA ILL THEN	MPLE BAICH. BE TESTED BY			
IS			REPAIRS: ALL DEFECTS, INCLUDING BUBE								
BY			MORE THAN 5% OF THE SURFA ENGINEER, SHALL BE REPAIRED 1. SMALL DEFECTS (ON THE BACK FILLED WITH EPOXY. 2. LARGE DEFECTS SHALL BE). TWO ORDER (REPAIR	TYPES OF F OF 3" DIAME ED AS REQU	EPAIRS TER) S IRED B	SHALL BE HALL BE I Y THE COT	e performed: Njected or Nsulting			
ND			ENGINEER'S SPECIFICATION SMALL ENTRAPPED AIR POCKET	IS AND	VOIDS NATUR	ALLY O	ICCUR IN I	MIXED RESIN			
TEM ER			SYSTEMS AND DO NOT REQUIR PROVIDED BY THE MANUFACTUR ENGINEER OF RECORD FOR AP	RER AND	BE SUBMIT	TED TO	THE STRU	epair shall be JCTURAL			
-			REMEDIAL MEASURES: IN THE EVENT THAT MATERIAL	TESTING,	PER SECTION	IN 3.07	.C, DETER	MINES A SAMPLE			
IARE DRT N			BATCH TO POSSESS INSUFFICIE SHALL BE TAKEN. IF THE TES DETERMINED TO BE BELOW THI SHALL BE INSTALLED UNTIL TH SAME PERCENTAGE AS THE DE REQUIRED ADDITIONAL MATERIAL	sted Con E Minimu E Final Ficiency L AND L/	MPOSITE SYS IM SPECIFIED COMPOSITE OF THE MA ABOR FOR R	TEM HA VALUE THICKN TERIAL	as materia Es, additio Ess is in S elastic	NL PROPERTIES ONAL LAYERS CREASED BY THE MODULUS. ANY			
RIC			PAID FOR AS AN EXTRA TO TH	E CONTR	RACTED WOR	κ.					
RS											
то											
DNS.											
ε											
of IBER											
				NO.	DATE		REVIS	IONS Scription		BY	
ER											
н											
хх											
БН											
s					ph i cof	33 Ventu	NGI Ira Bivd., Suit 650 fax 818.	FMAN NEER 285.2651	S		
								TA BARI Rbara, C		A	
					215 Sant	EA	ST FI	SMIC RETR Gueroa (Ra, ca 9)	ST.	TUDY	
				DRAWING				. NOTES			
				PROJECT 1030 Designed	3	CALE: AS SI	HOWN CHECKED BY	DATE: 10/18/10	REVISION N	10.	
				PVB DRAWN B MBH			PVB REVIEWED B" PVB).2	









			REVI	SIONS	
NO.	DATE			ESCRIPTION	BY
		-	-		
		-			
		-			
		-			
		-			
OWNER		offman.com ASTING	\$50 fax 81	IN EER Ite 1010 Endno, Califo 8:285:2851 ITA BAR RBARA, C	BARA
	21	5 EA	ST F	ISMIC RETR Igueroa Ara, ca 9	
DRAWING	TITLE				
EX	ISTIN	G BA	SEME	NT RETRO	FIT PLAN
PROJECT 10.30		SCALE:	HOWN	DATE: 10/18/10	REVISION NO.
DESIGNED		10 3	CHECKED		DRAWING NO.
PVB			PVB		004
DRAWN B	r:		REVIEWED PVB	BY:	JZ. I






			REVI	SIONS			
NO.	DATE		1	ESCRIP	TION		BY
		-					
		+					
		-					
		+					
OWNER		h 818.285.2 offman.com ASTING	\$50 fax 81	1.285.24	EER ⁹ Encino, Califo ⁵¹ BAR	BARA	•
PROJECT SB F	POLICE	5 EA	ST F	GU	IC RETR EROA (, CA 9	ST.	TUDY
DRAWING	TITLE						
	E		NG F		T FLOO PLAN	R	
PROJECT 10.3		SCALE:	HOWN	DATE:	10/18/10	REVISION NO	D.
DESIGNET) BY:	A5 5	CHECKED	l BY:	10/10/10		
DRAWN B			REVIEWED PVB	8Y:		32	.2











			REVI	SIONS			
NO.	DATE		C	ESCRIP	TION		BY
				ite 1010	Encino, Calif	fornia 91436	
OWNER		OFF	SAN	ITA	BAR		A
PROJECT	CITY CITY 90LICE 21	OF BANT. STATI	SAN A BA ON SI ST F	ITA RBA EISMI	BAR	A ROFIT S ST.	
PROJECT	CITY SOLICE 21 SAN	OF BANT. STATI	SAN A BA ON SI ST F	ITA RBA EISMI	BAR RA, C C RETR EROA	A ROFIT S ST.	
PROJECT SB F	CITY SOLICE 21 SAN	OF SANT. STATI 5 EA TA B	SAN A BA ON SI ST F	ITA RBA EISMI IGUI ARA	BAR RA, C C RETR EROA CA 9	A Rofit 8 St.	
PROJECT SB F	CITY SOLICE 21 SAN	OF SANT. STATI 5 EAS TA B EX	SAN A BA ON SE ST F ARB/	ITA RBA ISMI IGUI ARA, IG R	BAR RA, C C RETR ROA CA 9	A Rofit 8 St.	
PROJECT SB F	CITY tolice 21 SAN TTLE	OF SANT. STATI 5 EAS TA B EX RE	SAN A BA ON SE ST F ARB/	ITA RBA IGUI ARA, IG F	BAR RA, C C RETR ROA CA 9	A 10FIT { 105102	STUDY
PROJECT SB F DRAWING PROJECT	CITY SOLICE 21 SAN TILE	OF SANT. STATIS 5 EAS TA B EX RE	SAN A BA ON SE ST F ARB/	ITA RBA ISMI IGUI ARA, IG R	BAR ARA, C C RETF EROA CA 9 OOF PLAN	A 10FIT { ST. 03102	STUDY
PROJECT SB F	CITY SOLICE 21 SAN THE NO. 23	OF SANT. STATI 5 EAS TA B EX RE	SAN A BA ON SE ST F ARB/	ITA RBA EISMI IGUI IGUI IG F FIT I	BAR RA, C C RETR ROA CA 9	A 10FIT { ST. 03102	STUDY
PROJECT SB F DRAWING PROJECT 1030	CITY SOLICE 21 SAN TILE NO. 23 BT:	OF SANT. STATIS 5 EAS TA B EX RE	SAN A BA ON SE ST F ARB/ ISTIN TROF	ITA RBA IGUI IGUI IGUI IGUI IGUI IGUI IGUI	BAR ARA, C C RETF EROA CA 9 OOF PLAN	A 10FIT { ST. 03102	STUDY








		RE	ISIONS			
₩0.	DATE		DESCRI	PTION		BY
OWNER (CITY	OF SA	NT			•
PROJECT SB P	21	STATION S 5 East f Ta barb	IGU	ERQA	ST.	TUDY
DRAWING		MENT REI DEMOLI			EILING	
PROJECT 1030		SCALE: AS SHOWN	DATE	10/18/10	REVISION NO).
1030 Designed	13	AS SHOWN	D BY:		REVISION NO	
1030 Designed PVB	13 BY:	AS SHOWN CHECKER PVE) BY:			
1030 Designed	13 BY:	AS SHOWN	D BY:			





			REVIS	ONS		
NO.	DATE		DE	SCRIPTION		BY
OWNER	P c L	h 818.285.265 offman.com ASTING	0 fax 818.	anordoja		
				TA BAR RBARA, (4
PROJECT						
SB F	21	5 EAS	T FI	SMIC RET Gueroa Ra, ca :	\$T.	TUDY
DRAWING	21 SAN	5 EAS TA BA FLOOF	T FIG	GUEROA	ST. 93102 CEILIN	
DRAWING	21: SAN TITLE FIRST	5 EAS TA BA FLOOF DEM	T FIG	GUEROA RA, CA LECTED ON PLAN	ST. 93102 CEILIN	G
DRAWING PROJECT 1030 DESIGNED	21: SAN TITLE FIRST NO. 03	5 EAS TA BA FLOOF DEM(GUEROA RA, CA LECTED ON PLAN	ST. 93102 CEILIN	G 0.
DRAWING F PROJECT 103	21: SAN TITLE FIRST 03 BY:	5 EAS TA BA FLOOF DEM SCALE: AS SHO		BUEROA RA, CA	ST. 93102 CEILIN	G 0.





			REVE	SIONS				
NO.	DATE			ESCRIPT	ION		BY	
		-	-					
		+						
		-						
		-						
		-						
		+						
		+						
		+						
OWNER		ASTING	\$50 fax 81	8.285.265 	BAR	BAR	A	
PROJECT SB P	21	5 EA	ST F	GUE	CRETR ROA (CA 9	ST.	TUDY	
DRAWING	TITLE							
SE	SECOND FLOOR REFLECTED CEILING DEMOLITION PLAN							
PROJECT		SCALE:	HOWN	DATE:	10/18/10	REVISION N	ю.	
DESIGNED			CHECKED			DRAWING N	0.	
PVB			PVB			00	3	
DRAWN B	r:		REVIEWED PVB	BY:		00	0.0	